



501 S Cherry St
Suite 300
Glendale, CO 80246
www.ees.us.com
303-572-7997

September 26, 2022

Castle Rock Water
ATTN: Stormwater
175 Kellogg Ct.
Castle Rock, CO 80109

**Re: Perry Street – South Street Social
Final Drainage Compliance Letter**

EES is pleased to provide a drainage letter of conformance for the proposed site layout for Lot 4A, Block 11 of the town of Castle Rock, more specifically located at 414 and 404 North Perry Street, and 411 4th Street, Castle Rock, Colorado. The proposed project site is approximately 0.40 acres and is located at the northeast corner of 4th Street and Perry Street intersection. The site is bound to the north by a residential single-family home, Perry Street to west, and 4th Street to the south and east. In the existing condition, the site has 3 main buildings, two commercial stores to the south (1,065-sf and 2,508-sf), and a two-story residence building (1,340-sf) to the north. Additionally, there is an approximate 5,521-sf overhead canopy with steel frames in the center of the property. The existing conditions also has associated sidewalks, underground utilities, step walls, rockscaping, and landscaping on site. The existing drainage patterns were analyzed as three (3) existing drainage basins herein referred to as H-1, H-2, and H-3.

Per the NRCS Soil Survey, the subsurface characteristics consist of Bresser-Truckton sandy loam at 5-25% slopes. The soils have a moderate infiltration rate and are defined as hydrological soil group B. Refer to the Appendix for the NRCS Soil Survey Map.

There are no recently reported cases of flooding within or around the development. The site is located within Zone "X", areas determined to be outside 0.2% annual chance floodplain, of the Flood Plain, as designated on the Flood Insurance Rate Map (FIRM) 08035C0301G, map last revised 03/16/2016. Refer to the Appendix for the FIRMette.

BASIN H-1 – Basin H-1 is the 0.14 acres on the eastern portion of the existing parcel. The impervious value for the basin is 87%. The 5-year and 100-year runoff coefficients are 0.74 and 0.83, respectively. The runoff for the 5-year and 100-year storm event are 0.49-cfs and 1.00-cfs, respectively. Historically, runoff sheet flows to the east into the 4th Street Right-Of-Way. Once in the Right-Of-Way the flow is captured by an existing public storm sewer infrastructure within the R.O.W.

BASIN H-2 – Basin H-2 is 0.16 acres on the western portion of the existing parcel. The impervious value for the basin is 60%. The 5-year and 100-year runoff coefficients are 0.50 and 0.66, respectively. The runoff for the 5-year and 100-year storm event are 0.40-cfs and 0.95-cfs, respectively. Historically, runoff sheet flows to west into the Perry Street Right-Of-Way. Once in the Right-Of-Way the flow is captured by an existing public storm sewer infrastructure within the R.O.W.

BASIN H-3 – Basin H-3 is 0.10 acres on the southern portion of the existing parcel. The impervious value for the basin is 81%. The 5-year and 100-year runoff coefficients are 0.68 and 0.78, respectively. The runoff for the 5-year and 100-year storm event are 0.32-cfs and 0.68-cfs, respectively. Historically, runoff sheet flows to the south into the 4th Street Right-Of-Way. Once in the Right-Of-Way the flow is captured by an existing public storm sewer infrastructure within the R.O.W.

EXISTING RUNOFF SUMMARY TABLE							
DESIGN POINT	TRIBUTARY BASIN	AREA (AC)	PERCENT IMPERVIOUS	COEFFICIENT		TOTAL RUNOFF	
				C5	C100	Q5 (CFS)	Q100 (CFS)
1	H-1	0.14	87%	0.74	0.83	0.49	1.00
	H-2	0.16	60%	0.50	0.66	0.40	0.95
	H-3	0.10	81%	0.68	0.78	0.32	0.68
Total Existing Parcel		0.40	74%	0.62	0.73	1.21	2.62

The proposed redevelopment of the area will include the demolition of the northern residential building to construct a 2,696-sf restaurant and bar area with 800-sf basement. The southwestern commercial building will have the back portion of it demolished and an addition will be added to the building, resulting in a 1,387-sf restaurant and bar area. The southeast building will be redeveloped as a three level restaurant with a total square footage of 4,225-sf restaurant. Sidewalks and rockscape on site are to be removed and replaced with pavers and landscaping. Drainage patterns have been analyzed as three (3) proposed drainage basin for comparison to the existing conditions.

BASIN P-1 – Basin P-1 is 0.23 acres and consists of all proposed tap room and southeast restaurant as well as half the existing canopy on site, flowing to the east. The impervious value for the basin is 92%. The 5-year and 100-year runoff coefficients are 0.78 and 0.86, respectively. The runoff for the 5-year and 100-year storm event are 0.87-cfs and 1.74-cfs, respectively. Runoff on site will be picked up by both underground storm infrastructure and sheet flow to the east. Once in the Right-Of-Way the flow is captured by an existing public storm sewer infrastructure.

BASIN P-2 – Basin P-2 is 0.11 acres and consists of half the existing canopy as well as sheet flow from the western side of the site. The impervious value for the basin is 86%. The 5-year and 100-year runoff coefficients are 0.73 and 0.84, respectively. The runoff for the 5-year and 100-year storm event are 0.39-cfs and 0.81-cfs, respectively. Runoff on site will flow off site through sheet flow to the west of the property towards Perry Street R.O.W. Once in the Right-Of-Way the flow is captured by an existing public storm sewer infrastructure.

BASIN P-3 – Basin P-3 is 0.06 acres and consists the newly proposed Conservatory and Wine and Charcuterie restaurant. The impervious value for the basin is 62%. The 5-year and 100-year runoff coefficients are 0.53 and 0.72, respectively. The runoff for the 5-year and 100-year storm event are 0.15-cfs and 0.38-cfs, respectively. Runoff on site will flow south into the 4th Street R.O.W. Once in the Right-Of-Way the flow is captured by an existing public storm sewer infrastructure.

DEVELOPED RUNOFF SUMMARY TABLE							
DESIGN POINT	TRIBUTARY BASIN	AREA (AC)	PERCENT IMPERVIOUS	COEFFICIENT		TOTAL RUNOFF	
				C5	C100	Q5 (CFS)	Q100 (CFS)
1	P-1	0.23	92%	0.78	0.86	0.87	1.74
	P-2	0.11	86%	0.73	0.84	0.39	0.81
	P-3	0.06	62%	0.53	0.72	0.15	0.38
Total Proposed Parcel		0.40	86%	0.73	0.83	1.41	2.94

As described above, in the existing condition the 0.40-acre parcel is 74% impervious and produces 1.21 cfs and 2.62 cfs in the 5-year and 100-year storm events respectively. In the developed condition, the 0.40-acre project site is 86% impervious and produces 1.41 cfs and 2.94 cfs in the 5-year and 100-year storm events respectively. Although there is a slight increase of both imperviousness and resultant flow from the redevelopment, due to reseeding and updating the existing conditions to newer landscape standards, the amount of flow off-site will be negligible. Additionally, a majority of flows on-site will be directly piped into existing infrastructure, reducing the total sheet flow coming off site. All the main walks through the site have been proposed as pavers to allow additional infiltration in order the soil below instead of running off-site. Therefore, compared to the existing conditions of poorly maintained paver walks and rockscape areas have been improved and no negative effects will result downstream of the existing conditions.

Stormwater Quality Design Four Step Process

The proposed development and subsequent lot developments will follow the "Four Step Process" as mandated by the Drainage Criteria Manual as follows:

Step 1: Reduce Runoff Volume to the Maximum Extent Practicable

Runoff has been limited to the maximum extent practicable by utilizing a paver system and roof drain connections to underground storm sewer and reduce the amount of runoff.

Step 2: Provide Water Quality Capture Volume and Flood Control Detention Via Full-Spectrum Detention

Due to existing site size and minimal increase to the developed runoff water quality and detention modifications are not required. Additionally, a majority of flows on-site will be directly piped into existing infrastructure, reducing the total sheet flow coming off site. All the main walks through the site have been proposed as pavers to allow additional infiltration in order the soil below instead of running off-site.

Step 3: Utilize Stream Channel Stabilization Techniques

There are no drainageways adjacent to this project site or onsite.



501 S Cherry St
Suite 300
Glendale, CO 80246
www.ees.us.com
303-572-7997

Step 4: Undertake Source Control

During initial construction, erosion control measures (CCMs) including vehicle tracking control, stabilized staging area, construction fence, and silt fence will be in place to provide source control of sediment within the site. During interim conditions, inlet protection and rock socks will be installed at proposed inlets and along the proposed curb and gutter within the site. The final condition will provide permanent seeding of all disturbed areas provided per permanent CCM requirements. No other potential pollutants are anticipated with this site post- construction

In addition to the source control measures associated with construction, there are additional measures to be in place with the developed condition. The trash enclosure located at 411 4th Street will be below the 2nd level limiting any runoff from reaching the trash area. In addition, trench drains will be utilized throughout the site that will have grates that will limit large debris from entering the storm system. The site will also utilize general good housekeeping practices and preventative maintenance.

Respectfully submitted,
Entitlement and Engineering Solutions, Inc

Krysta Houtchens

Krysta Houtchens, P.E.
Project Manager



501 S Cherry St
Suite 300
Glendale, CO 80246
www.ees.us.com
303-572-7997


APPENDIX A

FIRM Map, Hydrologic Soil Map

National Flood Hazard Layer FIRMMette



104°51'49"W 39°22'39"N



0 250 500 1,000 1,500 2,000 Feet 1:6,000

Basemap: USGS National Map: Orthoimagery: Data refreshed October, 2020

Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT

SPECIAL FLOOD HAZARD AREAS		Without Base Flood Elevation (BFE) Zone A, V, A99
		With BFE or Depth Zone AE, AO, AH, VE, AR
		Regulatory Floodway
OTHER AREAS OF FLOOD HAZARD		0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile Zone X
		Future Conditions 1% Annual Chance Flood Hazard Zone X
		Area with Reduced Flood Risk due to Levee. See Notes. Zone X
		Area with Flood Risk due to Levee Zone D
OTHER AREAS		NO SCREEN Area of Minimal Flood Hazard Zone X
		Effective LOMRs
GENERAL STRUCTURES		Area of Undetermined Flood Hazard Zone D
		Channel, Culvert, or Storm Sewer
		Levee, Dike, or Floodwall
OTHER FEATURES		20.2 Cross Sections with 1% Annual Chance Water Surface Elevation
		17.5 Cross Sections with 1% Annual Chance Water Surface Elevation
		Coastal Transect
		Base Flood Elevation Line (BFE)
		Limit of Study
		Jurisdiction Boundary
		Coastal Transect Baseline
MAP PANELS		Digital Data Available
		No Digital Data Available
		Unmapped



The pin displayed on the map is an approximate point selected by the user and does not represent an authoritative property location.

This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on 4/12/2022 at 3:07 PM and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.

Hydrologic Soil Group—Castle Rock Area, Colorado



MAP LEGEND

Area of Interest (AOI)

 Area of Interest (AOI)

Soils

Soil Rating Polygons

 A
 A/D
 B
 B/D
 C
 C/D
 D
 Not rated or not available

Soil Rating Lines

 A
 A/D
 B
 B/D
 C
 C/D
 D
 Not rated or not available

Soil Rating Points

 A
 A/D
 B
 B/D

 C
 C/D
 D
 Not rated or not available

Water Features

 Streams and Canals

Transportation

 Rails
 Interstate Highways
 US Routes
 Major Roads
 Local Roads

Background

 Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:20,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
 Web Soil Survey URL:
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Castle Rock Area, Colorado
 Survey Area Data: Version 14, Aug 31, 2021

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Jul 24, 2018—Nov 19, 2018

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
BtE	Bresser-Truckton sandy loams, 5 to 25 percent slopes	B	0.5	100.0%
Totals for Area of Interest			0.5	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified

Tie-break Rule: Higher



501 S Cherry St
Suite 300
Glendale, CO 80246
www.ees.us.com
303-572-7997

APPENDIX B

Hydrology Calculations (Existing & Developed)

Runoff Coefficients

Corridor / Design Package: South Street Social
 System Name: Existing and Developed Condition

Computed: KMH Date: 4/12/2022
 Checked: KMH Date:

Sub-Basin Data		Total Area (ac)	Composite C			Sub Area (Pavement)				Sub Area (Roof)				Sub Area(Lawns B Group soils) 2-7%,>7%				Sub Area(Gravel)			
Basin ID	Description		C ₅	C ₁₀₀	i	C ₅	C ₁₀₀	i	Area (ac)	C ₅	C ₁₀₀	i	Area (ac)	C ₅	C ₁₀₀	i	Area (ac)	C ₅	C ₁₀₀	i	Area (ac)
H-1	East	0.14	0.74	0.83	87	0.86	0.89	100	0.04	0.76	0.84	90	0.09	0.01	0.44	2	0.00	0.32	0.61	40	0.01
H2	West	0.16	0.50	0.66	60	0.86	0.89	100	0.02	0.76	0.84	90	0.08	0.01	0.44	2	0.04	0.32	0.61	40	0.02
H-3	South	0.10	0.68	0.78	81	0.86	0.89	100	0.02	0.76	0.84	90	0.07	0.01	0.44	2	0.01	0.32	0.61	40	0.00
E-Total	Total Site	0.40	0.62	0.73	74.3	0.86	0.89	100	0.07	0.76	0.84	90	0.24	0.01	0.44	2	0.05	0.32	0.61	40	0.03
P-1	East	0.23	0.78	0.86	92.2	0.86	0.93	100	0.05	0.76	0.84	90	0.18	0.01	0.44	2	0.00	0.32	0.61	40	0.00
P-2	West	0.11	0.73	0.84	85.6	0.86	0.93	100	0.04	0.76	0.84	90	0.06	0.01	0.44	2	0.01	0.32	0.61	40	0.00
P-3	South	0.06	0.53	0.72	62.3	0.86	0.93	100	0.01	0.76	0.84	90	0.03	0.01	0.44	2	0.02	0.32	0.61	40	0.00
P-Total	Total Site	0.40	0.73	0.83	85.9	0.86	0.93	100	0.10	0.76	0.84	90	0.27	0.01	0.44	2	0.03	0.32	0.61	40	0.00

C and I values taken from Table 63 of the UDFCD

Standard Form SF-1 . Time of Concentration

Corridor / Design Package: South Street Social
System Name: Existing and Developed Condition

Urban TOC_{min} = 5 min
Rural TOC_{min} = 10 min

Computed: MRD
Checked: KMH

Date: 6/18/2021
Date:

	SUB-BASIN DATA			INITIAL/OVERLAND FLOW			TRAVEL TIME								Tc CHECK				FINAL Tc
				(t _o)			(t _t)								(Urbanized basins)				(min)
															TOTAL				
Basin ID	Description	Area (ac)	C _s	Length (ft)	Slope (ft/ft)	t _o (min)	Length (ft)	S _w (ft/ft)	Code	Description	Convey Coef (C _v)	Velocity (ft/s)	t _t Travel Time (min)	t _c = t _i + t _t (min)	Urban (Yes /No)	Length (ft)	T _c max (min)	T _c max > t _c	
H-1		0.14	0.74	20	0.022	2.24	0	0	6	Paved areas and shallow paved swales	20.00	0.00	0.00	2.24	YES	20.00	0.17	Regional Tc	5.00
H2		0.16	0.50	20	0.020	3.83	0	0	6	Paved areas and shallow paved swales	20.00	0.00	0.00	3.83	YES	20.00	0.17	Regional Tc	5.00
H-3		0.10	0.68	20	0.020	2.68	0	0	6	Paved areas and shallow paved swales	20.00	0.00	0.00	2.68	YES	20.00	0.17	Regional Tc	5.00
EX-Total		0.40	0.62		0.020	0.00	0	0	6	Paved areas and shallow paved swales	20.00	0.00	0.00	0.00	YES	0.00	0.06	Check	5.00
P-1		0.23	0.78	20	0.013	2.39	0	0	5	Grassed waterway	15.00	0.00	0.00	2.39	YES	20.00	0.17	Regional Tc	5.00
P-2		0.11	0.73	20	0.025	2.22	0	0	6	Paved areas and shallow paved swales	20.00	0.00	0.00	2.22	YES	20.00	0.17	Regional Tc	5.00
P-3		0.06	0.53	20	0.023	3.52	0	0	6	Paved areas and shallow paved swales	20.00	0.00	0.00	3.52	YES	20.00	0.17	Regional Tc	5.00

Velocity from $V = C_v \cdot S_w^{0.5}$, from MHFD Eqn RO-4, C_v from Table 6-5 (See Sheet Design Info)
 $t_o = L/60V$, from MHFD Eqn 6-4
 $t_c \text{ max} = 10 + L/180$, from MHFD Eqn 6-5
Final Tc > 10 min for nonurban watersheds

Code	Description
1	Heavy meadow
2	Tillage/field
3	Short pasture and lawns
4	Nearly bare ground
5	Grassed waterway
6	Paved areas and shallow paved swales
7	Rail Ballast

Standard Form SF-2 . Storm Drainage System Design (Rational Method Procedure)

 Corridor / Design Package: South Street Social
 System Name: Existing and Developed Condition

 Computed: KMH Date: 4/12/2022
 Checked: KMH

 Design Storm: Proposed 5-yr P = 1.43 in

LOCATION		DESIGN POINT	DIRECT RUNOFF							TOTAL RUNOFF				STREET		PIPE		TRAVEL TIME			REMARKS	
			AREA DESIGN	AREA (AC)	RUNOFF COEFF	t _c (MIN)	C.A. (AC)	IN / HR	Q (CFS)	t _c (MIN)	SUM (C*A)(AC)	IN / HR	Q(CFS)	SLOPE(%)	STREETFLOW (C)	DESIGNFLOW (C)	SLOPE(%)	PIPE SIZE(in)	LENGTH(FT)	VELOCITY(FPS)		t _t (MIN)
	(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	(11)	(12)	(13)	(14)	(15)	(16)	(17)	(18)	(19)	(20)	(21)	(22)
H-1	East		H-1	0.14	0.74	5.00	0.101	4.85	0.49					1	1	1	1	1	1	1		
H2	West		H2	0.16	0.50	5.00	0.082	4.85	0.40					1	1	1	1	1	1	1		
H-3	South		H-3	0.10	0.68	5.00	0.067	4.85	0.32													
E-Total	Total Site	1	E-Total	0.40						5.00	0.250	4.85	1.21									
P-1	East		P-1	0.23	0.78	5.00	0.180	4.85	0.87					2	2	2	2	2	2	2		
P-2	West		P-2	0.11	0.73	5.00	0.080	4.85	0.39													
P-3	South		P-3	0.06	0.53	5.00	0.032	4.85	0.15													
P-Total	Total Site		P-Total	0.40						5.00	0.292	4.85	1.41									

Proposed 100-yr P = 2.60 in

LOCATION		DESIGN POINT	DIRECT RUNOFF							TOTAL RUNOFF				STREET		PIPE		TRAVEL TIME			REMARKS	
			AREA DESIGN	AREA (AC)	RUNOFF COEFF	t _c (MIN)	C.A. (AC)	IN / HR	Q (CFS)	t _c (MIN)	SUM (C/A)(AC)	IN / HR	Q(CFS)	SLOPE(%)	STREETFLOW (C)	DESIGNFLOW (C)	SLOPE(%)	PIPE SIZE(IN)	LENGTH(FT)	VELOCITY(FPS)		t _t (MIN)
	(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	(11)	(12)	(13)	(14)	(15)	(16)	(17)	(18)	(19)	(20)	(21)	(22)
H-1	East		H-1	0.14	0.83	5.00	0.114	8.82	1.00					1	1	1	1	1	1			
H2	West		H2	0.16	0.66	5.00	0.107	8.82	0.95					1	1	1	1	1	1			
H-3	South	2	H-3	0.10	0.78	5.00	0.077	8.82	0.68													
E-Total	Total Site	2	E-Total	0.40						5.00	0.298	8.82	2.62									
P-1	East		P-1	0.23	0.86	5.00	0.198	8.82	1.74					1	1	1	1	1	1			
P-2	West		P-2	0.11	0.84	5.00	0.092	8.82	0.81													
P-3	South		P-3	0.06	0.72	5.00	0.043	8.82	0.38													
P-Total	Total Site		P-Total	0.40						5.00	0.333	8.82	2.94									

- (1) Basin Description linked to C-Value Sheet
 (2) Basin Design Point
 (3) Enter the Basin Name from C-Value Sheet
 (4) Basin Area linked to C-Value Sheet
 (5) Composite C linked to C-Value Sheet
 (6) Time of Concentration linked to C-Value Sheet

- (7) =Area x Runoff Coeff
 (8) = $28.5 \cdot P / (10 + t_c)^{0.786}$
 (9) =C.A. x IN/HR
 (10) =Column 6 + Column 21
 (11) Add the Basin Areas (7) to get the combined basin AC
 (12) = $28.5 \cdot P / (10 + \text{Column } 10)^{0.786}$

- (13) Sum of Qs
 (14) Additional Street Overland Flow
 (15) Additional Street Overland Flow
 (16) Design Pipe Flow
 (17) Pipe Slope
 (18) Pipe Size

- (19) Additional Flow Length
 (20) Velocity
 (21) =Column 19 / Column 20 / 60



501 S Cherry St
Suite 300
Glendale, CO 80246
www.ees.us.com
303-572-7997

APPENDIX C

MS4 Compliance Summary

Permanent Water Quality Determination Worksheet (Taken from 2019 SDDTCM Sections 13.1.4 and 13.1.5)

Project:		CRW#	Applicant:
Section	Questions	Response	Check those that apply
Instructions			
1	Non-applicable Sites		
	Will the project result in a temporary disturbance of greater than one acre?	No	☒
		Yes	☐
	Is the project part of a larger common plan of development or sale where multiple separate and distinct construction activities may be taking place at different times on different schedules, but remain related and are within 1/4 mile of each other? (A common plan of development will generally be documented on a site development plan, master plan, or equivalent, for the property/project)	No	☒
		Yes	☐
	Is the project within the Cherry Creek Watershed?	Yes	☐
		No	☒
2	Applicable Site Types and Exclusions by Variance		
	Does the project have more than 35% impervious area on the existing site?	No	☐
		Yes	☐
	Does the project have greater than 75% impervious area on the existing site?	No	☐
		Yes	☐
	Will 100% of the runoff from the existing and proposed site be captured and treated for permanent water quality?	Yes	☐
		No	☐
	Do any other water quality exclusions apply to the site?	No	☐
		Yes	☐
3	Applicable Sites with Other Exclusions by Variance		
3.1	Category 1: Roadways, bridges and trails only		
3.1.1	Is the project a bike or pedestrian trail?	Yes	☐
		No	☐
	Is the trail for a roadway?	Yes	☐
		No	☐
3.1.2	Is the project primarily used for parking or access to parking?	Yes	☐
		No	☐
3.1.3	Does the project add impervious area?	No	☐
		Yes	☐

3.1.4	Does the project add more than 8.25 feet of paved width at any location to the existing roadway?	No	☐	Project is excluded. Submit variance for <u>Roadway Redevelopment Sites Excluded from Permanent Water Quality Requirements</u> .
		Yes	☐	Proceed to next line.
	Does the project add more than one acre of paved area per mile to an existing roadway?	No	☐	Project is excluded. Submit variance for <u>Roadway Redevelopment Sites Excluded from Permanent Water Quality Requirements</u> .
		Yes	☐	Proceed to next line.
	Does the project increase the width by two times or more, on average, of the original roadway area?	No	☐	Existing areas of site are excluded only. Submit variance for <u>Existing Roadway Surfaces Only Excluded from Permanent Water Quality Requirements</u> .
		Yes	☐	This exclusion does not apply. Permanent water quality is required.
3.2	Category 2: Non-residential and non-commercial projects only			
3.2.1	Is the project associated with oil and gas exploration, production, processing, or treatment operations or transmission facilities, including activities necessary to prepare a site for drilling and the movement and placement of drilling equipment?	Yes	☐	Project is excluded. Submit variance for <u>Oil and Gas Exploration Sites Excluded from Permanent Water Quality Requirements</u> .
		No	☐	Proceed to 3.2.2.
3.2.2	Is the project for stream stabilization?	Yes	☐	Project is excluded. Submit variance for <u>Stream Stabilization Sites Excluded from Permanent Water Quality Requirements</u> .
		No	☐	Proceed to 3.2.3.
3.2.3	Is the project for installation or maintenance of underground utilities or infrastructure that does not permanently alter the terrain, ground cover, or drainage patterns from those present prior to the construction activity including activities to install, replace or maintain utilities under roadways or other paved areas that return the surface to the same condition?	Yes	☐	Project is excluded. Submit variance for <u>Aboveground and Underground Utilities Excluded from Permanent Water Quality Requirements</u> .
		No	☐	Proceed to 3.2.4.
3.2.4	Is the project on undeveloped land (land with no human-made structures such as buildings or pavement) that will remain undeveloped after the project?	Yes	☐	Project is excluded. Submit variance for <u>Sites with Land Disturbances to Undeveloped Land that will Remain Undeveloped Excluded from Permanent Water Quality Requirements</u> .
		No	☐	Proceed to 3.2.5.
3.2.5	Will the post-project condition result in surface water discharge during the 80th percentile storm runoff event?	No	☐	Project is excluded. Submit study along with variance for <u>Non-residential and Non-commercial Infiltration Conditions Excluded from Permanent Water Quality Requirements</u> .
		Yes	☐	This exclusion does not apply. Permanent water quality is required.
3.3	Category 3: Residential and Commercial projects			
3.3.1	Is the project a single-family residential lot, or agricultural zoned lands, greater than or equal to 2.5 acres in size per dwelling unit?	Yes	☐	Proceed to next line.
		No	☐	Proceed to 3.3.2.
	Is the project site greater than 10% impervious?	No	☐	Project is excluded. Submit variance for <u>Large Lot Single Family Sites Excluded from Permanent Water Quality Requirements</u> .
		Yes	☐	Proceed to next line.
	Is the project site greater than 20% impervious?	Yes	☐	This exclusion does not apply. Permanent water quality is required.
		No	☐	Proceed to next line.
	Will the post-project condition result in surface water discharge during the 80th percentile storm runoff event?	No	☐	Project is excluded. Submit study along with variance for <u>Large Lot Single Family Sites Excluded from Permanent Water Quality Requirements</u> .
		Yes	☐	This exclusion does not apply. Permanent water quality is required.

3.3.2	Will 100% of the runoff from the residential or commercial site be captured?	Yes	☐	This exclusion does not apply. Permanent water quality is required.
		No	☐	Proceed to next line.
	Is all or a portion of the site undeveloped or will it remain undeveloped after construction?	Yes	☐	This portion of the project is excluded. Submit variance for <u>Sites with Land Disturbance to Undeveloped Land that will Remain Undeveloped Excluded from Permanent Water Quality Requirements</u> . Proceed to next line.
		No	☐	Proceed to next line.
	Is the remaining untreated impervious area greater than 20% of the site?	Yes	☐	This exclusion does not apply. Permanent water quality is required.
		No	☐	Proceed to next line.
	Is the remaining untreated impervious area greater than one acre?	Yes	☐	This exclusion does not apply. Permanent water quality is required.
		No	☐	Proceed to next line.
	Is it practicable to capture runoff from portions of the site that will not drain to a control measure?	No	☐	Document justification demonstrating that it is not practicable to capture runoff from this portion of the site in the drainage report . No further action is needed.
		Yes	☐	This exclusion does not apply. Permanent water quality is required.



501 S Cherry St
Suite 300
Glendale, CO 80246
www.ees.us.com
303-572-7997

APPENDIX D

Permanent Water Quality Certification



Summary of Water Quality Conformance to MS4 Permit

The purpose of this worksheet is to document conformance with the Town of Castle Rock's MS4 permit with regard to permanent water quality on land disturbance projects.

Project Name Perry Street Social

Project Owner Perry Street Collective LLC

Project Location NEC of 4th Street and Perry Street

ToCR Project Number SDP21-0046

Total Site Area 0.40 acres **acres**

Total Size of Common Plan of Development 0.40 Acres **acres**

Check all that apply:

☒ **Project within Plum Creek Basin**

☐ **Project within Cherry Creek Basin**

Estimated construction completion date September 2022

1. The water quality control measure(s) for applicable development sites shall meet one of the following base design standards as per the SDDTCM Section 14.4. Please select all design standards that were applied to meet conformance with the MS4 on this site.

- ☐ WQCV standard
- ☐ Pollutant removal standard
- ☐ Runoff reduction standard
- ☐ Applicable site draining to regional WQVC control measure (accepts drainage prior to discharging to WOTS)
- ☐ Applicable site draining to regional WQVC control facility (with receiving pervious area control measure upstream of WOTS)
- ☒ Constrained redevelopment sites standard
 - Imperviousness of existing site 0.32 / 0.40 (Imp. Ac/Site Ac) = 74.3 %
 - Variance required TCV No. _____
- ☐ Existing control measure with WQCV per previous criteria standards
 - Reference Construction Permit No. _____
- ☐ Cherry Creek Basin only, choose one: ☐ Tier 1 ☐ Tier 2 ☐ Tier 3
- ☒ No control measures provided (See Permanent WQ Worksheet for applicability)

Summary of Water Quality Conformance to MS4 Permit

2. Was an exclusion to water quality applied as per SDDTCM Section 13.1.5? ☐ Yes ☒ No

i. If yes, please select all that apply, provide total excluded impervious area(s) and submit variance, as applicable: TCV No. _____

☐ Pavement management site

Excluded impervious area: _____ acres

☐ Excluded roadway redevelopment

Excluded impervious area: _____ acres

☐ Excluded existing roadway areas

Excluded impervious area: _____ acres

☐ Above ground and below ground utilities

☐ Large lot single family home

☐ Non-residential and non-commercial infiltration

Excluded impervious area: _____ acres

☐ Land disturbance for land to remain undeveloped

Excluded impervious area: _____ acres

☐ Stream Stabilization Sites

Excluded impervious area: _____ acres

☐ Trails

Excluded impervious area: _____ acres

☐ Oil and Gas Exploration

3. For Development and Redevelopment sites, following any exclusions claimed above, was any portion of the site excluded up to 20% of the site and not to exceed one acre? ☐ Yes ☒ No

If yes, complete the following:

Excluded area: _____ acres

Total Site area: _____ acres, _____ % site excluded

4. For Constrained sites, was any portion of the site excluded up to 50% of the site and not to exceed 50% of the impervious area? ☐ Yes ☒ No

If yes, complete the following:

Excluded area: _____ acres

Excluded impervious area: _____ acres

Total Site area: _____ acres, _____ % site excluded

Total Impervious area: _____ acres, _____ % impervious excluded




501 S Cherry St
Suite 300
Glendale, CO 80246
www.ees.us.com
303-572-7997

APPENDIX E

Drainage Maps

PERRY STREET SOCIAL DISTRICT - SITE DEVELOPMENT PLAN LOT 4A, BLOCK 11 OF THE TOWN OF CASTLE ROCK

LOCATED IN THE NORTHEAST QUARTER OF SECTION 11,
TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE 6TH P.M.
TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO
SDP21-0046



PERRY STREET (PUBLIC)
80' R.O.W.

HISTORIC RUNOFF SUMMARY TABLE							
DESIGN POINT	TRIBUTARY BASIN	AREA (AC)	PERCENT IMPERVIOUS	COEFFICIENT		TOTAL RUNOFF	
				C5	C100	Q5 (CFS)	Q100 (CFS)
1	H-1	0.14	87%	0.74	0.83	0.49	1.00
	H-2	0.16	60%	0.50	0.66	0.40	0.95
	H-3	0.10	81%	0.68	0.78	0.32	0.68
Total Existing Parcel		0.40	74%	0.62	0.73	1.21	2.62




EXISTING INLET
GR=6199.44
INV IN=6196.04 (SE)
INV IN=6195.94 (E)
INV OUT=6192.64 (W)

4TH STREET (PUBLIC)
80' R.O.W.

EXISTING MANHOLE
RIM=6200.74
INV IN=6195.14 (N)
INV OUT=6194.98 (W)

HISTORIC DRAINAGE LEGEND

- PROPERTY BOUNDARY
- EXISTING EASEMENT
- EXISTING MAJOR CONTOUR
- EXISTING MINOR CONTOUR
- HISTORIC BASIN DELINEATION
- EXISTING SANITARY SEWER
- EXISTING WATER
- EXISTING STORM SEWER
- EXISTING UNDERGROUND ELECTRIC
- EXISTING UNDERGROUND COMMUNICATION
- EXISTING GAS
- EXISTING STORM INLET AND MANHOLE
- HISTORIC DRAINAGE FLOW ARROWS



CALL UTILITY NOTIFICATION
CENTER OF COLORADO
1-800-922-1987 or 811

CALL 3-BUSINESS DAYS (NOT INCLUDING INITIAL
DAY OF CONTACT) IN ADVANCE BEFORE YOU DIG.
GRADE, OR EXCAVATE FOR THE MARKING OF
UNDERGROUND MEMBER UTILITIES.

SITE DEVELOPMENT PLAN
LOT 4A BLOCK 11 TOWN OF CASTLE ROCK
TOWN OF CASTLE ROCK PROJECT NO. SDP21-0046

REVISION		DATE
No.	BY	

**PRELIMINARY
NOT FOR
CONSTRUCTION**

EES
ENTITLEMENT AND
ENGINEERING
SOLUTIONS, INC.
501 S Cherry St, Suite 300
Denver, CO 80246
303-572-7997 www.ees.us.com

SITE DEVELOPMENT PLAN
PERRY STREET SOCIAL DISTRICT
410 PERRY STREET, CASTLE ROCK, CO 80104
EXISTING DRAINAGE MAP


PROJECT NO: PER001.01
DESIGNED BY: MRD
DRAWN BY: MRD
DATE: 08/27/2021

DR-01

8/9/2022 5:13 PM P:\PERRY STREET SOCIAL DISTRICT\CD, CASTLE ROCK - PERRY STREET SOCIAL - PERRY STREET SOCIAL (4TH & PERRY)\08 CAD\EXHIBITS\PROPOSED DRAINAGE MAP.DWG © 2022. ALL RIGHTS RESERVED.


SITE DEVELOPMENT PLAN PERRY STREET SOCIAL DISTRICT

LOT 4A, BLOCK 11 OF THE TOWN OF CASTLE ROCK
LOCATED IN THE NORTHEAST QUARTER OF SECTION 11, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE 6TH P.M.
TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO
SDP21-0046



PERRY STREET (PUBLIC)

80' R.O.W.



HISTORIC DRAINAGE LEGEND

- PROPERTY BOUNDARY
- EXISTING EASEMENT
- EXISTING MAJOR CONTOUR
- EXISTING MINOR CONTOUR
- HISTORIC BASIN DELINEATION
- EXISTING SANITARY SEWER
- EXISTING WATER
- EXISTING STORM SEWER
- EXISTING UNDERGROUND ELECTRIC
- EXISTING UNDERGROUND COMMUNICATION
- EXISTING GAS
- EXISTING STORM INLET AND MANHOLE
- HISTORIC DRAINAGE FLOW ARROWS
- DESIGN POINT
- BASIN DESIGNATION
- 5-YEAR RUNOFF COEFFICIENT
- 100-YEAR RUNOFF COEFFICIENT
- BASIN AREA IN ACRES

PROPOSED RUNOFF SUMMARY TABLE							
DESIGN POINT	TRIBUTARY BASIN	AREA (AC)	PERCENT IMPERVIOUS	COEFFICIENT		TOTAL RUNOFF	
				C5	C100	Q5 (CFS)	Q100 (CFS)
1	P-1	0.23	92%	0.78	0.86	0.87	1.74
	P-2	0.11	86%	0.73	0.84	0.39	0.81
	P-3	0.06	62%	0.53	0.72	0.15	0.38
Total Proposed Parcel		0.40	86%	0.73	0.83	1.41	2.94



CALL UTILITY NOTIFICATION
CENTER OF COLORADO
1-800-922-1987 or 811

CALL 3-BUSINESS DAYS (NOT INCLUDING INITIAL DAY OF CONTACT) IN ADVANCE BEFORE YOU DIG. GRADE, OR EXCAVATE FOR THE MARKING OF UNDERGROUND MEMBER UTILITIES.

Know what's below.
Call before you dig.

SITE DEVELOPMENT PLAN
LOT 4A BLOCK 11 TOWN OF CASTLE ROCK
TOWN OF CASTLE ROCK PROJECT NO. SDP21-0046

DATE

BY

REVISION

No.

PRELIMINARY
NOT FOR
CONSTRUCTION



EES
ENTITLEMENT AND
ENGINEERING
SOLUTIONS, INC.
501 S Cherry St, Suite 300
Denver, CO 80246
303-572-7997 www.ees.us.com

SITE DEVELOPMENT PLAN

PERRY STREET SOCIAL DISTRICT

410 PERRY STREET, CASTLE ROCK, CO 80104

PROPOSED DRAINAGE MAP

PROJECT NO: PER001.01

DESIGNED BY: KMH

DRAWN BY: KMH

DATE: 08/27/2021

DR-02