

MILLER'S LANDING

AN AMENDMENT TO THE INTERCHANGE OVERLAY PLANNED DEVELOPMENT PLAN #1

A PART OF THE EAST HALF OF SECTION 10, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE 6TH PRINCIPAL MERIDIAN,
TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

INTERCHANGE OVERLAY (IO) RESIDENTIAL USE RESTRICTION

ALL RESIDENTIAL USES ARE PROHIBITED WITHIN THE MILLER'S LANDING INTERCHANGE OVERLAY PLANNED DEVELOPMENT. ANY REFERENCES TO RESIDENTIAL USES OR RESIDENTIAL DESIGN STANDARDS IN THE INTERCHANGE OVERLAY DEVELOPMENT STANDARDS ARE NOT APPLICABLE TO THE MILLER'S LANDING TO PLANNED DEVELOPMENT PLAN.

GENERAL NOTES:

- THE PURPOSE OF THIS PLANNED DEVELOPMENT PLAN AMENDMENT IS TO REZONE THE PROPERTY TO INTERCHANGE OVERLAY TO ALLOW FOR RESIDENTIAL DEVELOPMENT.
- THE MINERAL RIGHTS ASSOCIATED WITH THIS DEVELOPMENT HAVE NOT BEEN SEVERED.
- THE DEVELOPABLE PORTION OF THIS SITE DOES NOT LIE IN THE 100-YEAR FLOOD PLAIN. NO STRUCTURES SHALL BE PERMITTED IN THE APPROVED 100-YEAR FLOOD PLAIN.
- A LOMR IS NOT ANTICIPATED BUT WILL BE SUBMITTED AT THE TIME OF SITE DEVELOPMENT PLAN, IF NECESSARY.
- UNDER INTERCHANGE OVERLAY ZONING, THIS DEVELOPMENT IS NOT SUBJECT TO THE TOWN OF CASTLE ROCK SKYLINE/RIDGELINE PROTECTION REGULATIONS.
- DEPENDING ON USES, THIS DEVELOPMENT PLAN MAY BE IMPACTED BY THE TOWN OF CASTLE ROCK RESIDENTIAL/NON-RESIDENTIAL INTERFACE REGULATIONS. ANY INTERFACE AREAS MUST ADHERE TO CHAPTER 17.50 OF THE TOWN OF CASTLE ROCK MUNICIPAL CODE REGARDING MITIGATION PROCEDURES.
- THIS DEVELOPMENT PLAN IS NOT IMPACTED BY SPECIES PROTECTED BY THE U.S. FISH & WILDLIFE SERVICE.
- THIS SITE IS WITHIN THE TOWN OF CASTLE ROCK BLUE WATER PRESSURE ZONE.
- ALL-WEATHER (CONCRETE OR ASPHALT) SURFACED ACCESS ROADS CAPABLE OF WITHSTANDING THE IMPOSED LOADS OF FIRE APPARATUS (75,000 LBS.) AND ALL REQUIRED FIRE HYDRANTS SHALL BE INSTALLED AND MADE SERVICEABLE PRIOR TO AND DURING ALL CONSTRUCTION.
- RIGHT-OF-WAY FOR INGRESS AND EGRESS FOR EMERGENCY VEHICLES IS GRANTED OVER, ACROSS, ON AND THROUGH ANY AND ALL PRIVATE ROADS AND DRIVES.
- THE PD ZONING REGULATIONS ARE THE INTERCHANGE OVERLAY PLANNED DEVELOPMENT ORDINANCE AND THE CURRENT INTERCHANGE OVERLAY PLANNED DEVELOPMENT STANDARDS.

LEGAL DESCRIPTION:

PARCEL ONE:

A PARCEL OF LAND SITUATED IN THE COUNTY OF DOUGLAS, STATE OF COLORADO AND IS DESCRIBED AS FOLLOWS:

LOT 2, BLOCK 7, CITADEL STATION FILING NO. 6, COUNTY OF DOUGLAS STATE OF COLORADO, LESS AND EXCEPT THE FOLLOWING WHICH WAS RELEASED BY PARTIAL RELEASE RECORDED NOVEMBER 12, 2008 AT RECEPTION # 2008075749,

A PARCEL OF LAND BEING A PORTION OF THE NORTHEAST 1/4 OF SECTION 10, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE 6TH P.M., IN DOUGLAS COUNTY, COLORADO, ALSO BEING A PORTION OF LOT 2, BLOCK 7, CITADEL STATION FILING NO. 6, SAID PARCEL BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGINNING AT THE CENTER ¼ CORNER OF SAID SECTION 10, A 3 ½ ALUMINUM CAP (LS 12046) ALSO BEING THE TRUE POINT OF BEGINNING;

- THENCE SOUTH 89°27'29" EAST ALONG THE SOUTH LINE OF THE NORTHEAST ¼ OF SAID SECTION 1 A DISTANCE OF 1,303.43 FEET;
- THENCE ON THE ARC OF A NON-TANGENT CURVE TO THE LEFT HAVING A DISTANCE OF 263.73 FEET, SAID CURVE HAS A RADIUS OF 864.50 FEET, A CENTRAL ANGLE OF 17°28'53", AND A LONG CHORD THAT BEARS NORTH 80°43'05" WEST A DISTANCE OF 262.74 FEET;
- THENCE NORTH 89°27'31" WEST A DISTANCE OF 548.00 FEET;
- THENCE ON THE ARC OF A CURVE TO THE RIGHT A DISTANCE OF 655.56 FEET, SAID CURVE HAS A RADIUS OF 500.50 FEET, A CENTRAL ANGLE OF 75°02'48", AND A LONG CHORD THAT BEARS NORTH 51°56'07" WEST A DISTANCE OF 609.69 FEET TO A POINT ON THE SOUTHERLY LINE OF OUTLOT B OF SAID CITADEL STATION FILING NO. 6;
- THENCE ALONG SAID LINE SOUTH 70°14'23" WEST A DISTANCE OF 21.53 FEET TO A POINT ON THE WEST LINE OF THE NORTHEAST ¼ OF SAID SECTION;
- THEN ALONG SAID LINE SOUTH 00°35'37" EAST A DISTANCE OF 403.88 FEET TO THE TRUE POINT OF BEGINNING.

PARCEL TWO:



A PARCEL OF LAND IN THE SOUTHEAST ¼ OF SECTION 10, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE 6TH P.M., IN DOUGLAS COUNTY, COLORADO, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

COMMENCING AT THE EAST ¼ CORNER OF SAID SECTION 10, A 2 ½" ALUMINUM CAP (LS 6935), THENCE WESTERLY ALONG THE NORTH LINE OF THE SOUTHEAST ¼ OF SAID SECTION 10, NORTH 89°27'29" WEST, A DISTANCE OF 587.50 FEET TO THE TRUE POINT OF BEGINNING;

- THENCE ALONG SAID NORTH 89° 27'29" WEST, A DISTANCE OF 725.68 FEET;
- THENCE ON THE ARC OF A NON-TANGENT CURVE TO THE RIGHT HAVING A DISTANCE OF 214.59 FEET, SAID CURVE HAS A RADIUS OF 864.50 FEET, A CENTRAL ANGLE OF 14°13'19", AND A DISTANCE OF 214.04 FEET;
- THENCE NORTH 32°14'41" EAST, A DISTANCE OF 6.00 FEET;
- THENCE SOUTH 57°45'19" EAST, A DISTANCE OF 380.82 FEET;
- THENCE NORTH 83°29'12" EAST, A DISTANCE OF 33.31 FEET;
- THENCE NORTH 32°14'41" EAST, A DISTANCE OF 274.89 FEET;
- THENCE ON THE ARC OF A CURVE TO THE LEFT A DISTANCE OF 53.16 FEET TO THE TRUE POINT OF BEGINNING, SAID CURVE HAS A RADIUS OF 790.00 FEET, A CENTRAL ANGLE OF 3°51'20", AND A LONG CHORD THAT BEARS NORTH 30°10'01" EAST, A DISTANCE OF 53.15 FEET;

COUNTY OF DOUGLAS, STATE OF COLORADO.

VICINITY MAP



SHEET INDEX:

- COVER SHEET
- 2-13 INTERCHANGE OVERLAY PLANNED DEVELOPMENT ZONING REGULATIONS
- 14-15 PLANNED DEVELOPMENT PLAN
- 16 PHASING PLAN

LAND USE SUMMARY TABLE

TOTAL SITE AREA = 48.17 AC

LAND USE	PERMITTED USE	ACRES PROVIDED (AC)	PERCENTAGE OF PROPERTY
PA1 - IOD	IOD	40.9	84.9%
PLANNING AREA TOTAL		40.9	84.9%
OPEN SPACE DEDICATED (OSD)	OPEN SPACE DEDICATED (OSD)	2.9	6.0%
OPEN SPACE PRIVATE (OSP)	OPEN SPACE PRIVATE (OSP)	4.4	9.1%
OPEN SPACE TOTAL		7.3	15.1%
PUBLIC LAND DEDICATION (PLD)		13.5 - SEE NOTE 4 BELOW	
TOTAL		48.2	100%
<i>POTENTIAL ROW DEDICATION</i>		<i>(3.7)</i>	<i>(7.7%)</i>

TABLE NOTES:

- THE MAJOR LAND USE CLASSIFICATIONS INCLUDING PUBLIC AND PRIVATE OPEN SPACE, RIGHT-OF-WAYS, DENSITIES, MAXIMUM AND MINIMUM LOT SIZES, MAXIMUM GROSS FLOOR AREA OR FLOOR AREA RATIO (FAR), NUMBER AND TYPE OF DWELLING UNITS AND NUMBER OF RESIDENTIAL LOTS WILL COMPLY WITH THE INTERCHANGE OVERLAY ZONE DISTRICT AND MILLER'S LANDING PD ORDINANCE.
- A MINIMUM OF 15% OF THE SITE WILL BE OPEN SPACE. THE FINAL LOCATION, DESIGN, AND ORIENTATION OF THE OPEN SPACE WILL BE DETERMINED DURING THE SITE PLAN AND PLATTING PROCESS.
- A TWENTY PERCENT (20%) CHANGE OR ADJUSTMENT TO THE ACREAGE OR BOUNDARIES OF OPEN SPACE AREAS AND/OR PLANNING AREAS MAY BE MADE WITH THE SITE DEVELOPMENT PLAN / PLAT.
- THE TOWN MAY CONSIDER CASH-IN-LIEU OF PLD. SEE THE MILLER'S LANDING DEVELOPMENT AGREEMENT.
- POTENTIAL DEDICATED RIGHT OF WAY ACREAGE IS SUBJECT TO FINAL DESIGN AND CONFIGURATION, TO BE DETERMINED AT FINAL PLAT.

MAXIMUM GROSS FLOOR AREA / UNITS PER USE TABLE

RETAIL	OFFICE / COMMERCIAL	MAXIMUM RESIDENTIAL
460,000 GFA	125,000 GFA	900 UNITS

VESTING

THIS MILLER'S LANDING INTERCHANGE OVERLAY PLANNED DEVELOPMENT PLAN INCLUSIVE OF THE EMBEDDED PD ZONING REGULATIONS CONSTITUTES A SITE SPECIFIC DEVELOPMENT PLAN PURSUANT TO CHAPTER 17.08 OF THE CASTLE ROCK MUNICIPAL CODE AND §24-68-101, *ET SEQ.*, C.R.S., AND ESTABLISHES VESTED PROPERTY RIGHTS THAT MAY EXTEND THROUGH DECEMBER 31, 2036, TO UNDERTAKE AND COMPLETE THE DEVELOPMENT AND USE OF THE PROPERTY ACCORDING WITH THIS PLANNED DEVELOPMENT PLAN.

OWNERSHIP CERTIFICATION:

THE UNDERSIGNED ARE ALL THE OWNERS OF CERTAIN LANDS IN THE TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS AND STATE OF COLORADO DESCRIBED HEREIN.

CCD MILLERS LANDING LLC

SIGNED THIS ____ DAY OF _____, 20____

NOTARY BLOCK

SUBSCRIBED AND SWORN TO BEFORE ME THIS ____ DAY OF _____,

20____ BY _____ AS _____
OF FENWAY PARTNERS, LLC

WITNESS MY HAND AND OFFICIAL SEAL.

NOTARY PUBLIC

MY COMMISSION EXPIRES: _____.

TITLE CERTIFICATION:

I, _____, AN AUTHORIZED REPRESENTATIVE OF FIDELITY NATIONAL TITLE COMPANY, A TITLE INSURANCE COMPANY LICENSED TO DO BUSINESS IN THE STATE OF COLORADO, HAVE MADE AN EXAMINATION OF THE PUBLIC RECORDS AND STATE THAT ALL OWNERS, MORTGAGEES AND LIENHOLDERS OF THE PROPERTY ARE LISTED IN THE CERTIFICATE OF OWNERSHIP AND LIENHOLDER SUBORDINATION CERTIFICATE.

AUTHORIZED REPRESENTATIVE

TITLE COMPANY

SIGNED THIS ____ DAY OF _____, 20____.

NOTARY BLOCK

SUBSCRIBED AND SWORN TO BEFORE ME THIS ____ DAY OF _____,

BY _____ AS AUTHORIZED REPRESENTATIVE
OF _____.

WITNESS MY HAND AND OFFICIAL SEAL.

NOTARY PUBLIC

MY COMMISSION EXPIRES: _____.

SURVEYOR'S CERTIFICATE:

I, _____, A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF COLORADO, DO HEREBY CERTIFY THAT THE SURVEY AND LEGAL DESCRIPTION REPRESENTED BY THIS INTERCHANGE OVERLAY PLANNED DEVELOPMENT PLAN WAS MADE UNDER MY SUPERVISION AND THE MONUMENTS SHOWN THEREON ACTUALLY EXIST AND THIS INTERCHANGE OVERLAY PLANNED DEVELOPMENT PLAN ACCURATELY REPRESENTS THAT SURVEY.

REGISTERED LAND SURVEYOR DATE

PLANNING COMMISSION RECOMMENDATION:

THIS INTERCHANGE OVERLAY PLANNED DEVELOPMENT PLAN WAS RECOMMENDED FOR APPROVAL BY THE PLANNING COMMISSION OF THE TOWN OF CASTLE ROCK, COLORADO ON THE ____ DAY OF _____, 20____.

CHAIR DATE

ATTEST:

DIRECTOR OF DEVELOPMENT SERVICES DATE

TOWN COUNCIL APPROVAL:

THIS INTERCHANGE OVERLAY PLANNED DEVELOPMENT PLAN WAS APPROVED BY THE TOWN COUNCIL OF THE TOWN OF CASTLE ROCK, COLORADO, ON THE ____ DAY OF _____, 20____.

MAYOR DATE

ATTEST:

TOWN CLERK DATE

DOUGLAS COUNTY CLERK AND RECORDER'S CERTIFICATE:

THIS INTERCHANGE OVERLAY PLANNED DEVELOPMENT PLAN WAS FILED FOR RECORD IN THE OFFICE OF THE COUNTY CLERK AND RECORDER OF DOUGLAS COUNTY AT _____ ON THE ____ DAY OF _____, 20____ AT RECEPTION NO. _____.

DOUGLAS COUNTY CLERK AND RECORDER

BY: _____

PLANNER:

NORRIS DESIGN
Planning | Landscape Architecture | Project Presentation

1101 Bannock Street
Denver, Colorado 80204
P 303.892.1186
F 303.892.1186
www.norris-design.com

OWNER/APPLICANT:

P3 ADVISORS, LLC

115 WILCOX STREET
SUITE 206
CASTLE ROCK, CO 80104
847-323-5277

ENGINEER:
CORE CONSULTANTS

3473 South Broadway
Englewood, CO 80113
303-703-4444

DATE:

10/16/20 01
05/14/21 01R

SHEET TITLE:

COVER
SHEET

SHEET
1 OF 16

MILLER'S LANDING INTERCHANGE OVERLAY
PLANNED DEVELOPMENT PLAN AMENDMENT #1

PROJECT NO. PDP20-000#

MILLER'S LANDING

AN AMENDMENT TO THE INTERCHANGE OVERLAY PLANNED DEVELOPMENT PLAN #1

A PART OF THE EAST HALF OF SECTION 10, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE 6TH PRINCIPAL MERIDIAN,
TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

TOWN OF CASTLE ROCK, CO

Interchange Overlay
Development Standards

PUBLISHED ON April 21, 2010 - BY THE TOWN OF CASTLE ROCK'S
DEVELOPMENT SERVICES



TABLE OF CONTENTS		
Interchange Overlay Development Standards		
I.	AUTHORITY AND PROCESS	3
II.	PURPOSE AND INTENT	3
III.	VARIANCES	3
IV.	INTERCHANGE OVERLAY DISTRICT	4
	A. APPLICATION AND DESCRIPTION	4
	B. BUILDING SITUATION	4
	C. PROPOSED PERMITTED USES	7
V.	PARKING STANDARDS	8
	A. PARKING PLACEMENT	8
	B. REQUIRED PARKING	8
	C. SHARED PARKING	9
VI.	ROADWAY HIERARCHY AND STREET STANDARDS	9
	A. STANDARDS	9
	B. PUBLIC FRONTAGE	9
	C. ROADWAY HIERARCHY TABLE	10
	D. ROADWAY HIERARCHY STANDARDS	10
	E. ROADWAY CROSS SECTIONS	11
	F. UNDERGROUND UTILITIES	12
VII.	STREETSCAPE AND LANDSCAPE	13
	A. STREETSCAPE STANDARDS	13
VIII.	DESIGN STANDARDS	18
	A. DESIGN STATEMENT	18
	B. SITE DESIGN AND LAYOUT	18
	C. PARKING AND LOT DESIGN	21
	D. ARCHITECTURAL DETAIL	23
	E. BUILDING MASSING AND SCALE	25
	F. BUILDING MATERIALS AND COLORS	27
	G. SIGNAGE	28
	H. LIGHTING	28
	I. WALLS AND FENCES	29
IX.	DEFINITION OF TERMS	31
X.	EXAMPLE SHARED PARKING CALCULATION	34

Blank Page

Town of Castle Rock, Colorado

1

2

PLANNER:



NORRIS DESIGN
Planning | Landscape Architecture | Project Presentation

1101 Bannock Street
Denver, Colorado 80204
P 303.892.1166
F 303.892.1186
www.norris-design.com

OWNER/APPLICANT:

P3 ADVISORS, LLC

115 WILCOX STREET
SUITE 206
CASTLE ROCK, CO 80104
847-323-5277

ENGINEER:

CORE CONSULTANTS

3473 South Broadway
Englewood, CO 80113
303-703-4444

DATE:

10/16/20 01

05/14/21 01R

SHEET TITLE:

IO PD ZONING
REGULATIONS

SHEET

2 OF 16

MILLER'S LANDING

AN AMENDMENT TO THE INTERCHANGE OVERLAY PLANNED DEVELOPMENT PLAN #1

A PART OF THE EAST HALF OF SECTION 10, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE 6TH PRINCIPAL MERIDIAN,
TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

SECTION I. AUTHORITY AND PROCESS

SECTION II. PURPOSE AND INTENT

SECTION III. VARIANCES

Interchange Overlay Development Standards

I. AUTHORITY AND PROCESS

This Code, together with all future amendments, shall be known as the Town of Castle Rock, Colorado, Interchange Overlay Development Standards (IODS). This Code is referenced in Chapter 17.16 of the Town of Castle Rock Municipal Code, pursuant to the powers conferred upon the Town of Castle Rock by the Colorado Revised Statutes. All reference in this document to the "Purpose and Intent" of the Interchange Overlay Development Standards shall rely on Chapter 17.16 of the Municipal Code for direction.

II. PURPOSE AND INTENT

This document, together with the amended municipal code, provides a flexible planning tool that enables development at strategic locations, through the use of enhanced design standards and incentives, to meet the following goals, all formed around the Town's 2020 Vision Statements' Four Cornerstones of, TOWN IDENTITY, COMMUNITY PLANNING, COMMUNITY SERVICES and LOCAL ECONOMY;

- The creation of a unique identity and image for 'gateway' areas into the Town.
- Strengthening of the Town's tax base by the expansion of economic activity through diversity and balance of housing, services, and employment.
- Generation of additional employment opportunities.
- Encourage the development/re-development of economically underutilized land.
- Protect natural features.
- Create pedestrian/non-motorized connectivity, through the implementation of an interconnected framework of transit, pedestrian, bicycle systems, trails and green corridors .
- Establish the Town as a stand-alone, self-supporting, economic business center.
- Ensure high-quality new development in the form of high intensity and high quality, both in land use and architecture to provide a mixture of employment, retail, and civic uses. A residential component shall be encouraged.
- Incorporate buildings and streetscapes that contribute to the physical definition of streets, alleys, sidewalks and bikeways.
- The use of energy conservation features and 'green' building techniques.

III. VARIANCES

- See Chapter 17.16 of the Town's Municipal Code.

SECTION IV. INTERCHANGE OVERLAY DISTRICT

Interchange Overlay Development Standards

IV. INTERCHANGE OVERLAY DISTRICT

A. APPLICATION AND DESCRIPTION

- The following areas, which are proposed and preferred for high quality, high intensity commercial development, are allowed to utilize the IODS upon the adoption by the Town Council of a zoning map amendment.
 - Meadows/Founders
 - Woffensberger
 - Plum Creek
 - And Other Areas Approved By Town Council

10

General Character:

Building Placement:

Intensity:


Shops mixed with townhouses, larger Apartment houses, Commercial Activity, Offices, workplace, and civic buildings; predominantly attached buildings, trees within the public right-of-way; substantial pedestrian activity

Shallow setbacks or none; buildings oriented to street defining a street wall.

Controlled by building height and parking standards.

B. BUILDING SITUATION

1. SETBACKS



PREFERRED SETBACKS - PRINCIPAL BUILDING	
Front Setback Principal (P)	0 ft. min.
Front Setback Secondary (S)	0 ft. min.
Side Setback	0 ft. min.
Rear Setback	3 ft. min.

SECTION IV. INTERCHANGE OVERLAY DISTRICT

Interchange Overlay Development Standards

2. PRIVATE FRONTAGE

	SECTION	PLAN		
	LOT PRIVATE FRONTAGE	R.O.W. PUBLIC FRONTAGE	LOT PRIVATE FRONTAGE	R.O.W. PUBLIC FRONTAGE
Forecourt: a Frontage where a portion of the facade is close to the Frontage Line and the central portion is set back. This type should be distributed sporadically amongst other Frontage types. Large trees within the forecourts may overhang the sidewalks to provide additional shade.				
Stoop: a Frontage where the facade is aligned close to the Frontage Line with the first story elevated from the sidewalk sufficiently to secure privacy for the windows. The entrance is usually an exterior stair and landing.				
Shopfront: a Frontage where the facade is aligned close to the Frontage Line with the building entrance at sidewalk grade. This type is conventional for retail use. It has a substantial glazing on the sidewalk level and an awning can overlap the sidewalk with a right of way encroachment permit.				
Gallery: a Frontage where the facade is aligned close to the Frontage line with an attached cantilevered shed or a lightweight colonnade overlapping the sidewalk with a right of way encroachment permit. This type is conventional for retail use. The gallery shall be no less than 10 feet wide and should overlap the sidewalk to within 2 feet of the curb.				
Arcade: a Frontage where the facade is a colonnade that overlaps the sidewalk, while the facade at sidewalk level remains at the Frontage Line. This type is conventional for retail use. The arcade shall be no less than 12 feet wide and should overlap the sidewalk to within 2 feet of the curb.				

PLANNER:

1101 Bannock Street
Denver, Colorado 80204
P 303.892.1166
F 303.892.1186
www.norris-design.com

OWNER/APPLICANT:

P3 ADVISORS, LLC

115 WILCOX STREET
SUITE 206
CASTLE ROCK, CO 80104
847-323-5277

ENGINEER:

CORE CONSULTANTS

3473 South Broadway
Englewood, CO 80113
303-703-4444

DATE:

10/16/20 01

05/14/21 01R

SHEET TITLE:

IO PD ZONING
REGULATIONS

SHEET

3 OF 16

A PART OF THE EAST HALF OF SECTION 10, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE 6TH PRINCIPAL MERIDIAN,
TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

Interchange Overlay Development Standards

Rearyard: A buildi

A blue rectangle divided horizontally by a dashed line, with a question mark in each half.

Height restrictions are set by Chapter 17.16 of the Castle Rock municipal code and/or Town Council approved IO PD. Height will be measured from the dirt grade to the top of the roof.

Interchange Overlay Development Standards

1. These permitted uses show

By Right		CIVIC BUILDINGS		LIGHT INDUSTRIAL	
RESIDENTIAL					
Mixed Use Block	■	Bus Shelter	■	Manufacturing	■
Apartment Building	■	Convention Center	■	Laboratory Facility	■
Live/Work Unit	■	Conference Center	■	Fabrication	■
Row House	■	Recreation Center	■	Wholesaling	■
		Fountain or Public Art	■	Research and Development	■
		Library	■		
LODGING		Live Theater	■		
Hotel	■	Movie Theater	■	OTHER	
Inn	■	Museum	■	Gasoline Station	■
Bed & Breakfast	■	Outdoor Auditorium	■	Drive-Through Facility	■
		Parking Structure	■	Shopping Center	■
OFFICE		Passenger Terminal	■	Shopping Mall	■
Office Building	■	College and Dormitory	■	Childcare Center	■
Live/Work Unit	■	Sports Stadium	■		
Flex Building	■	Surface Parking Lot	■		
		Religious Assembly	■		
RETAIL					


a. Uses outside of the c

Use By Special Review	☐
-----------------------	--------------------------

Use By Special Review		☐
OTHER		
Cemetery		☐
Electric Substation		☐
Wireless Cell Tower		☐
Car Sales		☐

Interchange Overlay Development Standards

A. PARKING PLACEME



☒ Parking setback area. Minimum 10 feet.

1. Parking shall be accessed by alleys or rear lanes, when such are available.
2. Open parking areas shall be masked from the Frontage by a building or streetscreen.
3. Bicycle racks shall be provided for of all buildings.

USE	PARKING
Residential	2 / dwelling
Office (non-medical)	4 / 1000 sq. ft.
Retail	3.5 / 1000 sq. ft
Hotel/Lodging	1 / Bedroom
Restaurant	1/3 seats
Medical Office	4.5 / 1000 sq. ft.

The standard parking requirements for a Mixed-use development may be reduced

1. The standard parking requirements for a Mixed-use development may be reduced by a calculation of shared parking requirements for the development, utilizing an accumulation factor table based upon the proportions contained in the following table to access peak period parking requirement.
2. The total aggregate reduction in the minimum-parking requirement for uses shall not exceed 20 percent of the standard conventional parking requirement or as approved by the Development Services Director. Car parking stalls located in front of residential garages or within individual residential unit garages or allocated or designated parking spaces shall not be included in any shared parking calculation.
3. On-street parking that is directly adjacent to the lot frontage may be counted as part of the parking provision.



NORRIS DESIGN
Planning | Landscape Architecture | Project Promotion

1101 Bannock Street
Denver, Colorado 80204
P 303.892.1166
F 303.892.1186
www.norris-design.com

P3 ADVISORS LLC

45 MILL CREEK STREET

115 WILCOX STREET
SUITE 206
CASTLE ROCK, CO 80104
847-323-5277

CORE CONSULTANTS

3473 South Broadway

3473 South Broadway
Englewood, CO 80113
303-703-4444

01

5/14/21 01R

ORD ZONING

IO PD ZONING REGULATIONS

SHEET 1

4 OF 16

MILLER'S LANDING

AN AMENDMENT TO THE INTERCHANGE OVERLAY PLANNED DEVELOPMENT PLAN #1

A PART OF THE EAST HALF OF SECTION 10, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE 6TH PRINCIPAL MERIDIAN,
TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

SECTION V. PARKING STANDARDS
SECTION VI. ROADWAY HIERARCHY AND STREET STANDARDS
Interchange Overlay Development Standards

C. SHARED PARKING CALCULATION (TABLE A)

USE	WEEKDAY	EVENING	NIGHT	WEEKEND
Residential	45%	75%	100%	100%
Office (non-medical)	100%	40%	5%	10%
Retail	95%	100%	5%	100%
Hotel/Lodging	95%	75%	100%	100%
Restaurant	100%	100%	15%	100%
Medical Office	100%	90%	10%	80%

NOTE: Other uses not listed above will determine their parking requirements through the IO PD process.

- Table A is used to calculate the demand based on the appropriate % of the conventional parking requirement at specified periods of the day. The highest resultant Mixed-use accumulation is used to determine the maximum shared parking demand. An example on how to apply the shared parking calculation can be found at Section X of this document.

VI. ROADWAY HIERARCHY AND STREET STANDARDS

A. STANDARDS

- Unless specifically modified herein, the design and construction of all streets, alleys, sidewalks and bikeways shall conform to the Town's Public Works Regulations and the Town's Transportation Master Plan.
- Cul-de-sacs are not recommended.

B. PUBLIC FRONTAGE

- The Public Frontage contributes to the character of each Interchange Overlay District, and includes the sidewalk, curb, planter, bike lanes and street trees.
- The spacing for planting in the Public Frontages may be adjusted to accommodate specific site conditions, such as the spacing of trees to avoid visually obscuring the shopfronts.
- The Public Frontage shall include trees and understory planting materials of various species, shall conform to the Town of Castle Rock's water conservation standards, Landscape Regulations, and the streetscape standards.
- The introduced landscape shall consist primarily of native species requiring minimal irrigation, fertilization and maintenance.

Town of Castle Rock, Colorado

9

SECTION VI. ROADWAY HIERARCHY AND STREET STANDARDS
Interchange Overlay Development Standards

C. ROADWAY HIERARCHY (TABLE B)

REQUIRED STANDARDS	ARTERIAL	COLLECTOR	LOCAL	ALLEY
ROW minimum	122	84	56	25
FL to FL minimum	80	50	26	20 (note)
Design Speed	40	30	20	5
Number of Travel Lanes (min-max)	4 - 6	2 - 4	2	2
Travel Lane Minimum	12	11	11	10
Travel Lane (with angled parking)	X	X	11	X
Median minimum	18	14	OPTIONAL**	X
Turn Lane minimum	12	12	OPTIONAL	X
On-Street Parking (parallel)	X	8	8	X
On-Street Parking (angled)	X	X	17	X
Bike Lane minimum	5	5	5*	X
Streetscape area minimum	10	8	6	X
Sidewalk minimum	10	8	8	X
Curb Extensions with parking	X	YES	YES	X
Corner Radii minimum	25 (R)	20 (R)	20 (R)	X
Exclusive Left Turn Lane Allowed	YES (R)	YES (R)	YES (R)	X
Pedestrian Islands	YES (R)	YES (R)	YES (R)	X


D. ROADWAY HIERARCHY STANDARDS

- Unless specifically modified herein, the design and construction of all streets, alleys, sidewalks and bikeways shall conform to the Town's Public Works Regulations and the Town's Transportation Master Plan.
- Table B is used in conjunction with the attached roadway design cross sections, the roadway design cross sections may be specified based on the parameters of the roadway hierarchy Table B.
- Each type of roadway hierarchy (ARTERIAL, COLLECTOR, LOCAL) may only connect to a roadway type within that specification or to a roadway type in a directly adjoining specification (excepting ALLEY).
ARTERIAL can connect with COLLECTOR.
COLLECTOR can connect with ARTERIAL and LOCAL.
LOCAL can connect to COLLECTOR.
ALLEY can connect to COLLECTOR and LOCAL.
- (R) Indicates that roundabout integration is encouraged as an alternative design solution. The final design of any roundabout will be subject to traffic volume and intensity of land use and sign-off by the Town's Public Works division.
- ALLEY may have inverted crowns and not flowlines.
- Refer to Cross Sections for the following:
* Bike lanes are required on COLLECTOR and LOCAL roads that intersect with COLLECTOR roads.
* Bike lanes not permitted between diagonal parking and drive lanes.
** Median required on LOCAL roads that intersect with COLLECTOR roads.
- Narrow street sections with on street parking will have to comply with Fire Department emergency access requirements.
- The appropriate sight-line/sight-triangle will need to be accommodated at intersections where buildings are in proximity to the back edge of the sidewalk.


10

Town of Castle Rock, Colorado

SECTION VI. ROADWAY HIERARCHY AND STREETS STANDARDS
E. INTERCHANGE OVERLAY DISTRICT ROADWAY CROSS SECTIONS



Town of Castle Rock, Colorado



11

PLANNER:

NORRIS DESIGN
Planning | Landscape Architecture | Project Presentation

1101 Bannock Street
Denver, Colorado 80204
P 303.892.1166
F 303.892.1186
www.norris-design.com

OWNER/APPLICANT:

P3 ADVISORS, LLC

115 WILCOX STREET
SUITE 206
CASTLE ROCK, CO 80104
847-323-5277

ENGINEER:

CORE CONSULTANTS

3473 South Broadway
Englewood, CO 80113
303-703-4444

DATE:

10/16/20 01

05/14/21.01R

SHEET TITLE:

IO PD ZONING
REGULATIONS

SHEET

5 OF 16

MILLER'S LANDING

AN AMENDMENT TO THE INTERCHANGE OVERLAY PLANNED DEVELOPMENT PLAN #1

A PART OF THE EAST HALF OF SECTION 10, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE 6TH PRINCIPAL MERIDIAN,
TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

SECTION VI. ROADWAY HIERARCHY AND STREET STANDARDS

Interchange Overlay Development Standards

F. UNDERGROUND UTILITIES

1. Underground utilities shall conform with the Town of Castle Rock's Public Works Regulations unless otherwise provided.

ALLEY

2. Alleys may be utilized in tandem with a parallel local street for the provision of underground wet utilities. Typically, only one utility shall be permitted within an alley. This shall be limited to either storm or sanitary sewer. If two wet utilities are required within an alley, there shall be a maximum diameter of 18" for each pipe.

SECTION VII. STREETSCAPE AND LANDSCAPE

Interchange Overlay Development Standards

A. STREETSCAPE STANDARDS

1. GENERAL
- a. Unless specifically modified herein, the design of streetscapes shall conform to the Town's Landscape Regulations and/or approved IO PD.
- b. Continuous planters shall be provided along all streets without on street parking.
- c. Intermittent planters shall be utilized along commercial streets with parallel on street parking.
- d. The widths of the planters shall be determined by the street section in accordance with these standards.
- e. Permitted Tree Types/Species, that are suitable for urban streetscapes.
- i. Acer platanoides 'Columnar' (Columnar Norway Maple)
- ii. Quercus robur 'Fastigita' (Columnar English Oak)
- iii. Gleditsia triacanthos inermis 'Skyline' (Thornless Common Honeylocust)
- iv. Pyrus calleryana 'Aristocrat' (Aristocrat Pear)
- v. Pyrus calleryana 'Redspire' (Redspire Pear)
- vi. Others as approved by the Public Works department.

2. STREETSCAPE PLANTER TYPE:

Photos are intended to represent examples of streetscape types and are not to scale.

a. Continuous Planter

The streetscape element of the Public Frontage that includes a continuous landscape area for the length of a block, unbroken by any area of non-living material.



SECTION VII. STREETSCAPE AND LANDSCAPE

Interchange Overlay Development Standards

b. Intermittent Planter

The streetscape element of the Public Frontage, generally located along commercial streets or in areas with parallel parking, that provides for alternating areas of landscape and non-living landscape elements. The landscape areas shall be a minimum of 7 feet in length, alternated with areas of non-living landscape elements (such as pavers or stone) that shall be a maximum of 7 feet in length, located so as to allow ease of ingress and egress from parked cars.



PLANNER:

NORRIS DESIGN
Planning | Landscape Architecture | Project Presentation

1101 Bannock Street
Denver, Colorado 80204
P 303.892.1166
F 303.892.1186
www.norris-design.com

OWNER/APPLICANT:

P3 ADVISORS, LLC

115 WILCOX STREET
SUITE 206
CASTLE ROCK, CO 80104
847-323-5277

ENGINEER:

CORE CONSULTANTS

3473 South Broadway
Englewood, CO 80113
303-703-4444

DATE:

10/16/20 01

05/14/21 01R

SHEET TITLE:

IO PD ZONING
REGULATIONS

SHEET

6 OF 16

MILLER'S LANDING

AN AMENDMENT TO THE INTERCHANGE OVERLAY PLANNED DEVELOPMENT PLAN #1

A PART OF THE EAST HALF OF SECTION 10, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE 6TH PRINCIPAL MERIDIAN,
TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

SECTION VIII. DESIGN STANDARDS

Interchange Overlay Development Standards

VIII. DESIGN STANDARDS

A. DESIGN STATEMENT

1. The depictions of Private Frontages are graphic only and are not intended to identify plant species, median or sidewalk spacing, or soil preparation. Reference the Town of Castle Rock Landscape Regulations or the streetscape standards.

B. SITE DESIGN AND LAYOUT

1. Buildings shall be sited and designed so as to frame and preserve views, as well as frame gateways along the corridors.
2. Buildings shall be designed to take up natural grade transitions and contours. Where this cannot occur, stepped retaining walls with landscaping shall be used.
3. Buildings shall be compatible in terms of scale, lot size, massing, building placement and orientation.
4. Orientation of new buildings shall take into account adjacent buildings and the angle of the sun in order to minimize ice build up on pedestrian or vehicular ways.
5. In a town center, where storefronts are typical, the building fronts shall be located at the property line to define the sidewalk edge and create a sense of vitality for the public sidewalk.
6. Buildings shall be located along the perimeter of a development with internal roadways and parking screened by buildings from the public roads. The importance of spaces between buildings should be recognized, and these spaces should have a planned and useful shape and not simply be left over areas.



7. Facades shall be built parallel to a rectilinear Principal Frontage line or to the tangent of a curved Principal Frontage line, and shall include a portion of the structure at the setback line.

18

Town of Castle Rock, Colorado

SECTION VIII. DESIGN STANDARDS

Interchange Overlay Development Standards

8. Large clear windows, prominent entryways, awnings and canopies should be used.



9. Buildings shall have their primary orientation toward the street rather than the parking area.



10. Pedestrian walkways from the public sidewalk to the main building entrance shall be provided.
11. In the absence of a building facade along any part of a Frontage Line, a streetscreen shall be built parallel with the facade. Streetscreens shall have openings no larger than necessary to allow automobile and pedestrian access.

Town of Castle Rock, Colorado

19

SECTION VIII. DESIGN STANDARDS

Interchange Overlay Development Standards

12. Developments can be set back from the property line to allow for outdoor dining areas, patios, plazas, and entranceways as long as the facade continuity is not interrupted. Buildings that are placed immediately adjacent to the sidewalk should promote visibility and pedestrian orientation with plazas or other pedestrian areas.



13. Trash and outdoor storage areas, mechanical equipment and similar areas shall be screened and shall be substantially obscured from the street. Attractive fences or walls shall be used to screen dumpsters and trash enclosures.



20

Town of Castle Rock, Colorado

PLANNER:

NORRIS DESIGN
Planning | Landscape Architecture | Project Presentation

1101 Bannock Street
Denver, Colorado 80204
P 303.892.1166
F 303.892.1186
www.norris-design.com

OWNER/APPLICANT:

P3 ADVISORS, LLC

115 WILCOX STREET
SUITE 206
CASTLE ROCK, CO 80104
847-323-5277

ENGINEER:

CORE CONSULTANTS

3473 South Broadway
Englewood, CO 80113
303-703-4444

DATE:

10/16/20 01

05/14/21 01R

SHEET TITLE:

IO PD ZONING
REGULATIONS

SHEET

8 OF 16

MILLER'S LANDING

AN AMENDMENT TO THE INTERCHANGE OVERLAY PLANNED DEVELOPMENT PLAN #1


A PART OF THE EAST HALF OF SECTION 10, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE 6TH PRINCIPAL MERIDIAN,
TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

SECTION VIII. DESIGN STANDARDS

Interchange Overlay Development Standards

- 
14. Roof-mounted mechanical equipment shall be concealed from street level public view by screening in a manner consistent with the character of the building.

15. Service areas and loading docks shall be screened or landscaped and should not be accessed directly from the street. Where feasible, service access and loading areas should be accessible from alleys or from parking lots located at the rear of buildings.



- C. PARKING AND LOT DESIGN**

 - Shared parking between adjacent businesses and/or developments is encouraged.
 - Vehicular access to a parking area should be provided from an alley or side street, where feasible, not from a primary shopping street.
 - Ground floor businesses are encouraged to permit access for patrons from the parking areas located at the rear of the building. Business signs and decorative lighting at this entry should be oriented to the pedestrian.
 - Parking lots shall provide a well-defined pedestrian circulation system within the site. Protected pedestrian walkways should directly link to entrances and the internal circulation of the buildings and to parking areas, and also to other buildings.
 - Trees, shrubs and ground covers shall be used in islands to break up large expanses of paving and provide shade, in conformance with the Town's Landscape Regulations. Water-efficient landscaping shall be used.

Town of Castle Rock, Colorado

21

SECTION VIII. DESIGN STANDARDS

Interchange Overlay Development Standards

- 
6. The landscape character of the streetscape should be extended into surface parking lots by introducing large canopy trees. The planting of shade trees in parking lot islands is required.



7. The preferred parking configuration is to have large-scale parking areas for a building or buildings located behind the building and be screened from view of adjacent properties with landscaping and decorative fencing. Where possible, car park screening shall follow the existing building line.
- 
8. Parking areas should be separated from buildings by either walkways and/or landscaped strips. Parking with head-in orientation is acceptable where it can be shown

22

Town of Castle Rock, Colorado

SECTION VIII. DESIGN STANDARDS

Interchange Overlay Development Standards

- that the sidewalks are sufficiently wide to create a pleasant pedestrian area, the parking layout assists in reducing traffic speeds yet does not produce hazardous situations, and the overall character is beneficial to the pedestrian.
9. Access to parking structures should minimize disruption to storefront continuity and not conflict with pedestrian safety.

10. Where applicable, the design of decked parking and parking structures should be integrated with surrounding development in order to create a continuous, attractive streetscape.



- D. ARCHITECTURAL DETAIL**

 - Development that is visible from, or adjacent to roads, open space and residential areas shall have well designed façades on all sides. This is considered a "360 degree" design treatment.



Town of Castle Rock, Colorado

23

PLANNER:



NORRIS DESIGN
Planning | Landscape Architecture | Project Presentation

1101 Bannock Street
Denver, Colorado 80204
P 303.892.1166
F 303.892.1186
www.norris-design.com

OWNER/APPLICANT:

P3 ADVISORS, LLC

115 WILCOX STREET
SUITE 206
CASTLE ROCK, CO 80104
847-323-5277

ENGINEER:

CORE CONSULTANTS

3473 South Broadway
Englewood, CO 80113
303-703-4444

DATE:

10/16/20 01

05/14/21 01R

SHEET TITLE:

IO PD ZONING
REGULATIONS

SHEET

9 OF 16

MILLER'S LANDING

AN AMENDMENT TO THE INTERCHANGE OVERLAY PLANNED DEVELOPMENT PLAN #1

A PART OF THE EAST HALF OF SECTION 10, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE 6TH PRINCIPAL MERIDIAN,
TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

SECTION VIII. DESIGN STANDARDS

Interchange Overlay Development Standards

2. All development which is located within 10ft of a public street shall provide at minimum 50% of its ground floor length and twenty-five percent (25%) of the area of the ground level wall area, which is defined as the area up to the finished ceiling height of the fronting space or fifteen feet (15') above finished grade, whichever is less, as windows, display areas or doorways. Required windows shall allow views into lobbies or similar areas of activity, pedestrian entrances, or display windows. Required windows shall provide a lower sill no more than three feet (3') above grade; except where interior floor levels prohibit such placement, the sill may be located not less than two feet (2') above the finished floor level to a maximum sill height of five feet (5') above exterior grade. The size and scale of windows should be varied. Sills and mullions should be used to continue and emphasize a specific architectural style. Features such as recessed windows, pilasters, definition of floor lines, corner quoins, cornices, and parapets should be used to create shadows and visual interest.



3. The different elements of a building's facade should be emphasized by use of color, arrangement of facade elements, or a change of materials.
4. Clear, transparent windows shall be used for all ground floor retail uses. Darkly tinted windows and mirrored windows which block two way visibility are prohibited as ground floor windows
6. The use of awnings is encouraged and awnings should fit in proportion to the module of the individual storefront rather than extending beyond a single bay.
7. Recessed entries to individual storefronts are required, as it creates a transition from the sidewalk to the interior of a Commercial building.

SECTION VIII. DESIGN STANDARDS

Interchange Overlay Development Standards



8. Awnings, arcades, and galleries may encroach the sidewalk to within two feet of the curb providing that the structures clear the sidewalk vertically by at least 8 feet.
9. Parapets shall be used to screen flat roofs and shall be designed as an architectural feature. A distinctive cornice can be used to emphasize a roofline in the design of a building.
10. Buildings at corners shall have special roof shapes in order to emphasize their corner location
11. Roof overhangs at pedestrian entries provide protection for shoppers and are encouraged.
12. Roofing materials shall be of a color and material consistent with the architectural character of the building and should convey a sense of permanence and quality.

E. BUILDING MASSING AND SCALE

1. Corner locations on a block are highly visible and shall be designed with visually prominent elements and variation in height. Corner entryways are encouraged, and alcoves, canopies, or other means of shelter should be provided at corner intersections.



SECTION VIII. DESIGN STANDARDS

Interchange Overlay Development Standards

2. Expression lines shall be utilized for buildings three stories or greater in height.
3. Variation in the building façade by vertical or horizontal articulation, window and entry variations, patios, plazas or other landscaped pedestrian areas is encouraged. Strong vertical elements such as windows, pilasters, columns, stairs, and towers shall be used where feasible to identify individual Commercial spaces.
4. Variations in roofline and building height can effectively break up massing and provide visual interest. Variations in rooflines can include gables, dormers and well-defined parapets.



5. The primary entrances to the building should be clearly identified with a canopy or awning, or treatments on the public sidewalk could also be used to define the major entries.
6. Large volumes or planes shall be broken up into smaller ones in order to reduce the visual scale of a building. The mass of a building shall be varied in form or divided to emphasize the various interior building functions.



7. The upper stories of a building shall be distinguished by using offsets or changes of material.
8. The sidewalk in front of a building shall be designed with elements that create a pedestrian friendly environment. Design elements shall be used to visually reduce the mass of the building.

PLANNER:

**NORRIS DESIGN**
Planning | Landscape Architecture | Project Presentation

1101 Bannock Street
Denver, Colorado 80204
P 303.892.1166
F 303.892.1186
www.norris-design.com

OWNER/APPLICANT:

P3 ADVISORS, LLC

115 WILCOX STREET
SUITE 206
CASTLE ROCK, CO 80104
847-323-5277

ENGINEER:

CORE CONSULTANTS

3473 South Broadway
Englewood, CO 80113
303-703-4444

DATE:

10/16/20 01

05/14/21 01R

SHEET TITLE:

IO PD ZONING
REGULATIONS

SHEET

10 OF 16

MILLER'S LANDING


AN AMENDMENT TO THE INTERCHANGE OVERLAY PLANNED DEVELOPMENT PLAN #1

A PART OF THE EAST HALF OF SECTION 10, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE 6TH PRINCIPAL MERIDIAN,
TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

SECTION VIII. DESIGN STANDARDS

Interchange Overlay Development Standards

- F. BUILDING MATERIALS AND COLOR**
- Building or accent colors shall not be bright or intense nor should highly reflective surfaces be utilized. Colors of the building materials should reflect those found in the natural landscape, such as soft greens, muted reds and pinks, warm grays and brown tones.
 - Materials such as stone, brick, pre-cast concrete, cast stone and architectural metals should be combined to enrich the appearance of a building and highlight architectural features.



- Building materials and texture on the ground floor add to the pedestrian experience and quality finish materials shall be used. Compatible materials shall be used on all sides of a building.
- Within a development, the materials, texture and color of materials of the individual storefronts should be varied. Contrasting colors for architectural details, awnings, and at entrances shall be used to create interesting architectural features.



- Large areas of white or cool grays, and reflective glass curtain wall systems may be permitted by variance.
- Bright corporate colors may be permitted by variance.

Town of Castle Rock, Colorado

27

SECTION VIII. DESIGN STANDARDS

Interchange Overlay Development Standards

- G. SIGNAGE**
- Hanging signs can use a wide variety of colors and icons to create a unique character and are encouraged.



- Signs shall have a minimum clearance of eight feet above the sidewalk for public safety.
- Signs shall be incorporated into the architecture of the building.
- Internally illuminated signs are not recommended.
- All permanent external signage should be designed and located in the landscape so as to be compatible with the building design and scale.

- H. LIGHTING**
- Innovative, decorative, and attractive light fixtures are encouraged and shall be used throughout the development. These fixtures shall fit the style of the building and respect the Town's character.



Town of Castle Rock, Colorado

28

SECTION VIII. DESIGN STANDARDS

Interchange Overlay Development Standards

- Pedestrian-oriented light fixtures shall be incorporated into the design of open spaces and should be complementary to the existing light standards on the sidewalks.



- Lighting of the development shall complement the building design. Floodlights can be incorporated into the design of the building facade and shall be cut-off fixtures with reduced glare.
- Lighting that is non-IREA approved shall be maintained privately and not by the Town.
- Use of LED lighting technologies are encouraged.

- I. WALLS AND FENCES**
- Large expanses of blank retaining walls are not permitted. Variations in the color of the wall, materials and landscaping are all to be used, singly or in combination, to improve the appearance of a wall.
 - Retaining walls shall be distributed throughout the site rather than be designed as high perimeter walls. (Terracing may be an option on a case by case review.)
 - Landscape pockets along walls or fences are encouraged. These should be a design element that is repeated frequently along the length of a wall.

Town of Castle Rock, Colorado

29

PLANNER:

NORRIS DESIGN
Planning | Landscape Architecture | Project Presentation

1101 Bannock Street
Denver, Colorado 80204
P 303.892.1166
F 303.892.1186
www.norris-design.com

OWNER/APPLICANT:

P3 ADVISORS, LLC

115 WILCOX STREET
SUITE 206
CASTLE ROCK, CO 80104
847-323-5277

ENGINEER:

CORE CONSULTANTS

3473 South Broadway
Englewood, CO 80113
303-703-4444

DATE:

10/16/20 01

05/14/21 01R

SHEET TITLE:

IO PD ZONING
REGULATIONS

SHEET

11 OF 16

MILLER'S LANDING

AN AMENDMENT TO THE INTERCHANGE OVERLAY PLANNED DEVELOPMENT PLAN #1

A PART OF THE EAST HALF OF SECTION 10, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE 6TH PRINCIPAL MERIDIAN,
TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

SECTION III. DESIGN STANDARDS

Interchange Overlay Development Standards



4. Walls comprised of two or more retaining walls are required to include landscaping at the base, the terrace between walls, and at the top of a retaining wall. Trees or shrubs shall be planted in indentations in the wall or landscaped areas in front of the wall.
5. Retaining walls shall be designed to blend in with the adjacent buildings or structures unless shielded from public view by adjacent buildings or structures.
6. A decorative cap, railing or some similar element shall be placed at the top of a retaining wall.

SECTION IX. DEFINITION OF TERMS

Interchange Overlay Development Standards

VIII. DEFINITIONS

This Article provides definitions for terms in this Code that are technical in nature or that otherwise may not reflect a common usage of the term. If a term is not defined in this Article, then it is located within the Town of Castle Rock's Municipal Code. If the definition is not located within the Town of Castle Rock's Municipal Code the Town of Castle Rock's Development Services Director will determine its meaning and intent.

Apartment: a residential unit sharing a building and a lot with other units and/or uses; may be for rent, or for sale as a condominium.

Block Perimeter: A total measurement of the boundaries of all sides of a unit of contiguous lots or parcels bounded by roadways or other barriers.

Building Situation: the placement of a building on its lot.

By Right: characterizing a proposal or component of a proposal for a IOZ PD that complies with the Interchange overlay zoning development standards and is permitted and processed administratively, without public hearing.

Code: Town of Castle Rock's Interchange Overlay Zoning Development Standards.

Commercial: the term collectively defining workplace, Office, retail, and lodging functions.

Configuration: the form of a building, based on its massing, Private Frontage, and height.

Corridor: a lineal geographic system incorporating transportation and/or greenway trajectories.

Edgeward Building: a building that occupies the center of its lot with setbacks on all sides.

Effective Parking: the amount of parking required for Mixed-Use after adjustment by the shared parking factor.

Encroachment: any structural element that breaks the plane of a vertical or horizontal regulatory limit, extending into a setback, into the Public Frontage, or above a height limit.

Expression Line: a line which breaks up the façade of a building over 3 stories which extends across the major part of the width of a façade and is expressed by a variation in material or by a limited projection such as a molding or balcony. (Syn: transition line.)


Flex Building: A building that includes a mixture of light industrial, office and retail spaces, including the opportunities for warehouse or light manufacturing operations, related office and a showroom/retail space in a shopfront type building.

SECTION IX. DEFINITION OF TERMS

Interchange Overlay Development Standards

Frontage: the area between a building facade and the vehicular lanes, inclusive of its built and planted components. Frontage is divided into Private Frontage and Public Frontage.

Frontage Line: a lot line bordering a Public Frontage. Facades facing Frontage Lines define the public realm and are therefore more regulated than the elevations facing other lot lines.



Function: the use or uses accommodated by a building and its lot.

Gateway: An entrance that defines the Town's boundaries and points of entry from major streets, alleys, sidewalks and bikeways and can consist of an ensemble of streets, buildings, natural features and landscapes, bridges, and special elements such as signage and public art. Gateways can provide a strong sense of identity and arrival to the Town. The major gateways into Castle Rock along major streets, alleys, sidewalks and bikeways should convey the Town's identity by utilizing characteristic design elements that reflect Castle Rock's character and heritage.

Green: a civic space type for unstructured recreation, spatially defined by landscaping rather than building Frontages.

Greenway: an open space corridor in largely natural conditions which may include trails for bicycles and pedestrians.

IO: Interchange Overlay District refers to Chapter 17.16 of the Town's municipal code.

IO PD: Interchange Overlay Planned Development that has been approved by the Town of Castle Rock's Town Council.

Interchange Overlay District (IOD): is identified in the Town's adopted 2020 Comprehensive Master Plan, as amended, that is one of four existing or proposed interchanges along I-25 as locations for gateways into the town where higher intensity and high quality economic development should occur through zoning initiatives. An outline zoning overlay of existing zoning entitlements that is voluntary and implemented through the IOZ PD process.

Landscape Regulations: those regulations, criteria, manuals and other documents that govern landscaping.

PLANNER:



1101 Bannock Street
Denver, Colorado 80204
P 303.892.1166
F 303.892.1186
www.norris-design.com

OWNER/APPLICANT:

P3 ADVISORS, LLC

115 WILCOX STREET
SUITE 206
CASTLE ROCK, CO 80104
847-323-5277

ENGINEER:
CORE CONSULTANTS

3473 South Broadway
Englewood, CO 80113
303-703-4444

DATE:

10/16/20 01

05/14/21 01R

SHEET TITLE:

IO PD ZONING
REGULATIONS

SHEET
12 OF 16

MILLER'S LANDING

AN AMENDMENT TO THE INTERCHANGE OVERLAY PLANNED DEVELOPMENT PLAN #1

A PART OF THE EAST HALF OF SECTION 10, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE 6TH PRINCIPAL MERIDIAN,
TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

SECTION IX. DEFINITION OF TERMS

Interchange Overlay Development Standards

Light Industrial: A land use that consists of activities such as manufacturing, research and development, processing, fabrication, wholesaling, and/or storage. A retail component may be permitted in conjunction with these activities.

Liner Building: a building specifically designed to mask a parking lot or a parking structure from a Frontage.

Live-Work Unit: a Mixed-use unit consisting of a Commercial and residential function. The Commercial function may be anywhere in the unit. It is intended to be occupied by a business operator who lives in the same structure that contains the Commercial activity or industry. (See *Work-Live*)

Manufacturing: premises available for the creation, assemblage and/or repair of artifacts, using table-mounted electrical machinery or artisan's equipment, and including their retail sale.

Mixed-use: multiple functions separated horizontally or vertically within the same or multiple buildings.

Office: premises available for the transaction of general business but excluding retail and Manufacturing uses.

Parking Structure: a building containing of one or more stories of parking above grade.

Plaza: a civic space type designed for civic purposes and Commercial activities. They are generally paved and spatially defined by building Frontages.

Pocket Park: an open space area centrally located within identified pedestrian shed, owned and maintained by an HOA or other private entity, designed and equipped for the recreation of children that includes playground equipment and open plan areas.

Principal Building: the main building on a lot, usually located toward the Frontage.

Principal Entrance: the main point of access for pedestrians into a building.

Principal Frontage: On corner Lots, the Private Frontage designated to bear the address and Principal Entrance to the building, and the measure of minimum lot width.

Private Frontage: the privately held Layer between the Frontage Line and the Principal Building facade.

Public Works Regulations: those regulations, criteria, manuals and other documents that govern public works infrastructure.

Recess Line: a line prescribed for the full width of a facade, above which there is a stepback of a minimum distance, such that the height to this line (not the overall building height) effectively defines the enclosure of the enfronting public space.

Transportation Master Plan: the master plan that governs all transportation elements and design criteria.

SECTION X. EXAMPLE SHARED PARKING CALCULATION

Interchange Overlay Development Standards

SHARED PARKING CALCULATION EXAMPLE

The example described here calculates the shared parking requirement for a mixed use development that comprises of the following:

60 Residential Units (peak parking demand primarily at night time and weekend)
5000 sq.ft of Office space (peak parking demand primarily at weekday)
10000 sq.ft of Retail space (peak parking demand primarily at weekend, weekday and evening)
75 bed Hotel (peak parking at night and weekend)
100 seat Restaurant.
500 sq.ft Medical Office (peak parking spread throughout the week)

The shared parking calculation takes into account the peak parking required for a combination of uses at any one time. In this example we can see that the peak parking requirement is at the Weekend (269 spaces). In normal parking code circumstances each use would be calculated separately, giving a parking requirement of 287 spaces. The shared parking code allows a maximum reduction of 20% (or as approved by the Development Services Director) if the shared peak parking warrants that. In this case the peak parking requirement shows a 6.3% reduction from normal requirements.

Interchange Overlay Zoning Development Parking Standards						
	Unit	Standard	Weekday	Evening	Night	Weekend
Residential (units)	60	120	54	90	120	120
Office (sq. ft)	5000	20	20	8	1	2
Retail	10000	35	34	35	2	35
Hotel (rooms)	75	75	72	57	75	75
Restaurant (seats)	100	34	34	34	6	34
Medical Office (sq. ft)	500	3	3	3	1	3
		Required	287	217	227	205
Standard Requirement	287					
Maximum Reduction (20%)	230					
Peak Demand	269	reduction				
IOZ Requirement	269	6.3%				

PLANNER:



1101 Bannock Street
Denver, Colorado 80204
P 303.892.1166
F 303.892.1186
www.norris-design.com

OWNER/APPLICANT:

P3 ADVISORS, LLC

115 WILCOX STREET
SUITE 206
CASTLE ROCK, CO 80104
847-323-5277

ENGINEER:
CORE CONSULTANTS

3473 South Broadway
Englewood, CO 80113
303-703-4444


DATE:

10/16/20 01
05/14/21 01R

SHEET TITLE:
IO PD ZONING
REGULATIONS

SHEET
13 OF 16

A PART OF THE EAST HALF OF SECTION 10, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE 6TH PRINCIPAL MERIDIAN,
TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO




CHECKED BY: MB, AH
DRAWN BY: TK

MILLER'S LANDING



AN AMENDMENT TO THE INTERCHANGE OVERLAY PLANNED DEVELOPMENT PLAN #1

A PART OF THE EAST HALF OF SECTION 10, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE 6TH PRINCIPAL MERIDIAN,
TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO



- NOTES**
1. PHASING WILL BE COMPLETED IN A LOGICAL MANNER WITH THE EXTENSION OF INFRASTRUCTURE AS DEVELOPMENT OCCURS OVER TIME.
 2. INTERSECTIONS AND ACCESS POINTS SHOWN AS ARROWS ARE CONCEPTUAL ONLY. THE EXACT NUMBER AND LOCATIONS OF ACCESS POINTS ARE TO BE ESTABLISHED AT THE TIME OF PLAT. SOME ACCESS POINTS MAY BE REMOVED AND OTHERS MAY BE ADDED. INTERSECTION AND ROADWAY DESIGN WILL BE CONSISTENT WITH THE INTERCHANGE OVERLAY DEVELOPMENT STANDARDS AND APPLICABLE TOWN STANDARDS.
 3. EXISTING INTERIOR LOT LINES WILL BE REPLACED AS NECESSARY WITH FUTURE PLATS.
 4. CLASSIFICATION OF ALL ROADS INTERNAL TO THIS PDP WILL BE DETERMINED WITH THE SITE DEVELOPMENT PLAN, BASED ON TRAFFIC STUDIES, AS APPROPRIATE.
 5. PROPOSED UTILITIES, GRADING, AND DRAINAGE WILL BE DETERMINED AT TIME OF SITE DEVELOPMENT PLAN AND PLAT. REFER TO GRADING/DRAINAGE REPORTS FOR ADDITIONAL INFORMATION.
 6. THE FINAL CONFIGURATION OF PRAIRIE HAWK DRIVE WILL BE DETERMINED AT TIME OF SITE DEVELOPMENT PLAN / PLAT BASED ON THE TIA, AS APPROPRIATE.
 7. ALL UTILITY POINTS OF CONNECTION, LOCATIONS AND SIZES ARE CONCEPTUAL AND WILL BE DETERMINED WITH DETAILED UTILITY SYSTEM CALCULATIONS DURING CONSTRUCTION PLAN SUBMITTALS.
 8. OSD=OPEN SPACE DEDICATED; OSP=OPEN SPACE PRIVATE

- LEGEND**
- PROPERTY BOUNDARY
 - PLANNING AREA BOUNDARY
 - CONCEPTUAL OSP - OSD BOUNDARY
 - CONCEPTUAL TRAIL ALIGNMENT
 - EXISTING WATER LINE
 - EXISTING STORM SEWER LINE
 - EXISTING SANITARY SEWER LINE
 - CONCEPTUAL DRAINAGE PATTERN
 - PROPOSED WATER LINE
 - PROPOSED SANITARY SEWER LINE



MILLER'S LANDING INTERCHANGE OVERLAY
PLANNED DEVELOPMENT PLAN AMENDMENT #1

PROJECT NO. PDP20-000#

PLANNER:

NORRIS DESIGN
Planning | Landscape Architecture | Project Presentation

1101 Bannock Street
Denver, Colorado 80204
P 303.892.1186
F 303.892.1186
www.norris-design.com

OWNER/APPLICANT:

P3 ADVISORS, LLC

115 WILCOX STREET
SUITE 206
CASTLE ROCK, CO 80104
847-323-5277

ENGINEER:

CORE CONSULTANTS

3473 South Broadway
Englewood, CO 80113
303-703-4444

DATE:

10/16/20 01
05/14/21 01R

SHEET TITLE:

PD PLAN


SHEET
15 OF 16

CHECKED BY: MB, AH
DRAWN BY: TK

MILLER'S LANDING

AN AMENDMENT TO THE INTERCHANGE OVERLAY PLANNED DEVELOPMENT PLAN #1

A PART OF THE EAST HALF OF SECTION 10, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE 6TH PRINCIPAL MERIDIAN,
TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO



- GENERAL NOTES:
- PHASES MAY BE DEVELOPED IN ANY SEQUENCE OR CONCURRENTLY. THE PHASES SHOWN ARE THE PATH OF PROGRESSION ANTICIPATED AT THIS TIME.
 - INSTALLATION OF PUBLIC IMPROVEMENTS WILL OCCUR IN A FASHION TO SUPPORT AND SERVE THE DEVELOPMENT AS IT OCCURS.
 - DEVELOPMENT OF SUB-PHASES WITHIN EACH PHASE MAY BE DETERMINED AT TIME OF CONSTRUCTION DOCUMENTS.
 - TURNAROUND AREAS PER TOWN CRITERIA SHALL BE PROVIDED WHEN ROADWAYS TERMINATE AT A PHASE LINE OR INTERIM TERMINUS.
 - PRAIRIE HAWK DRIVE IMPROVEMENTS BY THIS DEVELOPMENT TERMINATE ON THE NORTH AT THE CONNECTION TO TOPEKA WAY AND ON THE SOUTH AT THE CONNECTION TO THE WEST PLUM CREEK PARKWAY IMPROVEMENTS.
 - AMENDMENTS TO THIS PHASING PLAN MAY BE APPROVED ADMINISTRATIVELY AS DETERMINED BY THE DEVELOPMENT SERVICES DIRECTOR.


- PHASING NOTES:
- PHASE 1
- PRAIRIE HAWK DRIVE FROM WEST PLUM CREEK PARKWAY TO INTERSECTION #1
 - ROADWAYS THAT SUPPORT PHASE 1 OR ANY SUB-PHASE AS SHOWN ON THE CONSTRUCTION PLANS
 - DETENTION A
 - DETENTION B
 - INDUSTRIAL TRIBUTARY IMPROVEMENTS ADJACENT TO PHASE 1
 - REGIONAL TRAIL ADJACENT TO PHASE 1, TEMPORARY TRAIL CROSSING AT THE PRAIRIE HAWK DRIVE ALIGNMENT AREA
 - UTILITIES, OFF-SITE AND ON-SITE, THAT SUPPORT PHASE 1
 - WEST PLUM CREEK PARKWAY IMPROVEMENTS AT THE TIME THEY ARE TRIGGERED BY THE MILLER'S LANDING DEVELOPMENT AGREEMENT

- PHASE 2
- ROADWAYS THAT SUPPORT PHASE 2 OR ANY SUB-PHASE AS SHOWN ON THE CONSTRUCTION PLANS
 - INDUSTRIAL TRIBUTARY IMPROVEMENTS ADJACENT TO PHASE 2
 - REGIONAL TRAIL ADJACENT TO PHASE 2
 - UTILITIES, OFF-SITE AND ON-SITE, THAT SUPPORT PHASE 2
 - WEST PLUM CREEK PARKWAY IMPROVEMENTS AT THE TIME THEY ARE TRIGGERED BY THE MILLER'S LANDING DEVELOPMENT AGREEMENT
 - ROUNDABOUT AT INTERSECTION #3

- PHASE 3
- PRAIRIE HAWK DRIVE FROM INTERSECTION #1 TO TOPEKA WAY
 - ROADWAYS THAT SUPPORT PHASE 3 OR ANY SUB-PHASE AS SHOWN ON THE CONSTRUCTION PLANS
 - UTILITIES, OFF-SITE AND ON-SITE, THAT SUPPORT PHASE 3
 - REGIONAL TRAIL GRADE SEPARATED CROSSING AT PRAIRIE HAWK DRIVE

INTERSTATE 25 OFF-RAMP IMPROVEMENTS TO INCLUDE AN OFF-RAMP RIGHT TURN LANE AND AND ACCELERATION LANE AT THE LENGTH DIRECTED BY AN APPROVED TRAFFIC STUDY AT THE TIME THIS IS TRIGGERED BY THE MILLER'S LANDING DEVELOPMENT AGREEMENT.

- 1 PHASE 1
- 2 PHASE 2
- 3 PHASE 3



PLANNER:

NORRIS DESIGN
Planning | Landscape Architecture | Project Presentation

1101 Bannock Street
Denver, Colorado 80204
P 303.882.1188
F 303.882.1188
www.norris-design.com

OWNER/APPLICANT:

P3 ADVISORS, LLC

115 WILCOX STREET
SUITE 206
CASTLE ROCK, CO 80104
847-323-5277

ENGINEER:

CORE CONSULTANTS

3473 SOUTH BROADWAY
ENGLEWOOD, CO 80113
303-703-4444

DATE:

10/16/20 01

05/14/21 01R

SHEET TITLE:

CONCEPTUAL
PHASING PLAN

SHEET
16 OF 16