


DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

VICINITY MAP



SHEET INDEX

- SHEET 1.....COVER
- SHEET 2.....OWNERSHIP CERTIFICATION
- SHEET 3-8.....PLANNED DEVELOPMENT PLAN
- SHEET 9.....OPEN SPACE, PUBLIC LAND, AND TRAILS PLAN
- SHEET 10.....NATURAL FEATURES MAP
- SHEET 11.....PHASING PLAN
- SHEET 12.....GRADING & DRAINAGE PLAN
- SHEET 13.....WILDLAND MANAGEMENT PLAN
- SHEET 14-18.....PD ZONING REGULATIONS
- SHEET 19.....ARCHITECTURAL DESIGN STANDARDS
- SHEET 20.....SIGN DESIGN STANDARDS

PURPOSE STATEMENT

THE DAWSON TRAILS PDP IS AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN TO ZONE THE PROPERTY FOR RESIDENTIAL, MIXED USE, COMMERCIAL, INDUSTRIAL, OPEN SPACE, AND PLD.

VESTING

THIS DAWSON TRAILS PLANNED DEVELOPMENT PLAN INCLUSIVE OF THE EMBEDDED PD ZONING REGULATIONS CONSTITUTES A SITE SPECIFIC DEVELOPMENT PLAN PURSUANT TO CHAPTER 17.08 OF THE CASTLE ROCK MUNICIPAL CODE AND §24-68-101, ET SEQ., C.R.S., AND ESTABLISHES VESTED PROPERTY RIGHTS THROUGH DECEMBER 31, 2052, TO UNDERTAKE AND COMPLETE THE DEVELOPMENT AND USE OF THE PROPERTY IN ACCORDANCE WITH THIS PLAN. TOWN COUNCIL MAY APPROVE A ONE TIME TEN-YEAR EXTENSION OF THE VESTING PERIOD, NOT TO EXCEED DECEMBER 31, 2062.

TECHNICAL CRITERIA VARIANCE APPROVAL

TCV22-0031
APPROVED 5/11/2022
APPROVAL ALLOWS FOR REDUCED INTERSECTION SPACING BETWEEN FULL MOVEMENT INTERSECTIONS ALONG DAWSON TRAIL BLVD/PRAIRIE HAWK DR.

LEGAL DESCRIPTION

TWO (2) PARCELS OF LAND IN PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

THE BEARINGS FOR THIS DESCRIPTION ARE BASED ON THE NORTH LINE OF THE SOUTH HALF OF SECTION 28, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH P.M. BEING ASSUMED TO BEAR S89°55'56"E, FROM THE SOUTH 1/16TH CORNER OF SAID SECTIONS 21 & 22, BEING MONUMENTED BY A 1" DIAMETER PIPE WITH A 2" DIAMETER ALUMINUM CAP STAMPED "LS 6935" TO THE SOUTH 1/16TH CORNER OF SAID SECTIONS 20 & 21, BEING MONUMENTED BY A 1" DIAMETER PIPE WITH A 2" DIAMETER ALUMINUM CAP, STAMPED "LS 6935", WITH ALL BEARINGS CONTAINED HEREIN RELATIVE THERETO.

PARCEL 1:
BEGINNING AT THE SOUTH 1/16TH CORNER OF SAID SECTIONS 21 & 22, ALSO BEING A POINT ON THE SOUTH LINE OF TWIN OAKS, A SUBDIVISION PLAT RECORDED AT RECEPTION NO. 161972, IN THE RECORDS OF THE DOUGLAS COUNTY CLERK AND RECORDER'S OFFICE;
THENCE S 89°28'35" E, ALONG THE SOUTH LINE OF SAID TWIN OAKS SUBDIVISION AND ALONG THE NORTH LINE OF THE SOUTH HALF OF SAID SECTION 22, A DISTANCE OF 404.37 FEET TO A POINT ON THE WEST LINE OF THE TWIN OAKS ROAD RIGHT-OF-WAY, AS DEDICATED BY SAID TWIN OAKS SUBDIVISION;
THENCE ALONG THE WEST LINE OF SAID TWIN OAKS DRIVE RIGHT-OF-WAY AND ALONG THE SOUTH LINE OF THE TERRITORIAL ROAD RIGHT-OF-WAY, AS DEDICATED BY SAID TWIN OAKS SUBDIVISION, THE FOLLOWING FOUR (4) COURSES:

- S 02°01'48" E, A DISTANCE OF 52.10 FEET TO THE SOUTH LINE OF SAID TERRITORIAL ROAD RIGHT-OF-WAY;
- N 87°58'41" E, A DISTANCE OF 109.24 FEET TO A POINT OF CURVATURE;
- ALONG THE ARC OF A CURVE TO THE LEFT HAVING A RADIUS OF 245.88 FEET, A CENTRAL ANGLE OF 28°36'44" AND AN ARC LENGTH OF 122.69 FEET;
- N 59°21'57" E, A DISTANCE OF 23.19 FEET TO A POINT ON THE SOUTH LINE OF SAID TWIN OAKS SUBDIVISION;

THENCE S 89°28'35" E, ALONG SAID SOUTH LINE, A DISTANCE OF 174.31 FEET TO THE SOUTHEAST CORNER OF SAID TWIN OAKS SUBDIVISION;
THENCE N 17°17'13" E, ALONG THE EAST LINE OF SAID TWIN OAKS SUBDIVISION, A DISTANCE OF 139.27 FEET TO A POINT ON THE EAST LINE OF SAID TERRITORIAL ROAD RIGHT-OF-WAY AND A POINT OF NON-TANGENT CURVATURE;

- THENCE ALONG THE EAST LINE OF SAID TERRITORIAL ROAD RIGHT-OF-WAY THE FOLLOWING TWO (2) COURSES:
- ALONG THE ARC OF A NON-TANGENT CURVE TO THE LEFT HAVING A RADIUS OF 198.98 FEET, A CENTRAL ANGLE OF 31°52'19" AND AN ARC LENGTH OF 110.69 FEET, SUBTENDED BY A CHORD OF WHICH BEARS N 33°13'23" E, A DISTANCE OF 109.26 FEET;
 - N 17°17'13" E, A DISTANCE OF 534.55 FEET TO A POINT ON THE SOUTH LINE OF THE TERRITORIAL ROAD RIGHT-OF-WAY AS DEDICATED BY THAT DEED RECORDED AT RECEPTION NO. 8816440, SAID DOUGLAS COUNTY RECORDS;

THENCE N 89°40'41" E, ALONG SAID SOUTH LINE, A DISTANCE OF 1599.61 FEET TO A POINT ON THE WEST LINE OF THE BURLINGTON NORTHERN SANTA FE RAILROAD RIGHT-OF-WAY;
THENCE S 15°17'57" W, ALONG SAID WEST LINE, A DISTANCE OF 8875.32 FEET TO THE NORTHEAST CORNER OF THAT PARCEL OF LAND DESCRIBED IN THAT DEED RECORDED AT RECEPTION NO. 2004131453, SAID DOUGLAS COUNTY RECORDS;
THENCE ALONG THE NORTH, WEST AND SOUTH LINES OF SAID PARCEL, THE FOLLOWING THREE (3) COURSES:

- S 89°46'16" W, A DISTANCE OF 678.73 FEET;
- S 00°19'26" W, A DISTANCE OF 600.54 FEET;
- S 89°29'06" E, A DISTANCE OF 515.85 FEET TO A POINT ON THE WEST LINE OF SAID BURLINGTON NORTHERN SANTA FE RAILROAD RIGHT OF WAY;

THENCE S 15°17'57" W, ALONG SAID WEST LINE, A DISTANCE OF 547.53 FEET TO A POINT ON THE EAST LINE OF THE NORTHEAST QUARTER OF SAID SECTION 33; THENCE N 00°02'14" W, ALONG SAID EAST LINE, A DISTANCE OF 226.55 FEET TO A POINT ON THE WEST LINE OF SAID BURLINGTON NORTHERN SANTA FE RAILROAD RIGHT-OF-WAY;
THENCE S 15°19'54" W, ALONG SAID WEST LINE, A DISTANCE OF 789.53 FEET TO A POINT ON THE SOUTH LINE OF THE NORTH HALF OF SAID SECTION 33;
THENCE N 89°35'18" W, ALONG SAID SOUTH LINE, A DISTANCE OF 5123.28 FEET TO THE EAST QUARTER CORNER OF SAID SECTION 32, ALSO BEING THE NORTHEAST CORNER OF KEENE RANCH FILING NO. 1, A SUBDIVISION PLAT RECORDED AT RECEPTION NO. 9523375, SAID DOUGLAS COUNTY RECORDS;
THENCE S 89°21'58" W, ALONG THE NORTH LINE OF SAID KEENE RANCH FILING NO. 1 AND ALONG THE SOUTH LINE OF THE NORTHEAST QUARTER OF SAID SECTION 32, A DISTANCE OF 2414.66 FEET TO THE SOUTHEAST CORNER OF THAT PARCEL OF LAND DESCRIBED IN THAT DEED RECORDED AT RECEPTION NO. 2004051359, SAID DOUGLAS COUNTY RECORDS; THENCE ALONG THE EAST AND NORTH LINES OF SAID PARCEL OF LAND, THE FOLLOWING TWO (2) COURSES:

- N 00°23'12" W, A DISTANCE OF 208.86 FEET TO THE NORTHEAST CORNER OF SAID DEED;
- S 89°18'57" W, A DISTANCE OF 208.54 FEET TO A POINT ON THE WEST LINE OF THE NORTHEAST QUARTER OF SAID SECTION 32, ALSO BEING A POINT ON THE EAST LINE OF SAID KEENE RANCH FILING NO. 1;

THENCE N 00°19'46" W, ALONG THE EAST LINE OF SAID KEENE RANCH FILING NO. 1, ALONG THE EAST LINE OF KEENE RANCH FILING NO. 2, A SUBDIVISION PLAT RECORDED AT RECEPTION NO. 8639479, SAID DOUGLAS COUNTY RECORDS, AND ALONG THE WEST LINE OF THE NORTHEAST QUARTER OF SAID SECTION 32, A DISTANCE OF 2505.77 FEET TO THE NORTH QUARTER CORNER OF SAID SECTION 32, THENCE N 00°39'34" W, ALONG THE EAST LINE OF SAID KEENE RANCH FILING NO. 2 AND ALONG THE WEST LINE OF THE EAST HALF OF SAID SECTION 29, A DISTANCE OF 5308.62 FEET TO THE NORTH QUARTER CORNER OF SAID SECTION 29, BEING THE NORTHEAST CORNER OF SAID KEENE RANCH FILING NO. 2 PLAT, AND THE SOUTHWEST CORNER OF CASTLE MESA SOUTH, A SUBDIVISION PLAT RECORDED AT RECEPTION NO. 145078, SAID DOUGLAS COUNTY RECORDS;
THENCE S 89°02'42" E, ALONG THE NORTH LINE OF THE EAST HALF OF SAID SECTION 29 AND ALONG THE SOUTH LINE OF SAID CASTLE MESA SOUTH SUBDIVISION, A DISTANCE OF 2661.01 FEET TO THE SOUTHEAST CORNER OF SAID CASTLE MESA SOUTH SUBDIVISION, BEING THE SOUTHWEST CORNER OF SAID SECTION 21;

THENCE N 00°02'04" W, ALONG THE EAST LINE OF SAID CASTLE MESA SOUTH SUBDIVISION AND ALONG THE WEST LINE OF THE SOUTH HALF OF THE SOUTH HALF OF SAID SECTION 21, A DISTANCE OF 1322.70 FEET TO THE SOUTH 1/16TH CORNER OF SAID SECTIONS 20 & 21, BEING THE SOUTHWEST CORNER OF SAID TWIN OAKS SUBDIVISION;
THENCE S 89°55'56" E, ALONG THE SOUTH LINE OF SAID TWIN OAKS SUBDIVISION AND ALONG THE NORTH LINE OF THE SOUTH HALF OF THE SOUTH HALF OF SAID SECTION 21, A DISTANCE OF 5286.17 FEET TO THE POINT OF BEGINNING.

LESS AND EXCEPT THE FOLLOWING THREE (3) PARCELS OF LAND:

TWO (2) PARCELS OF LAND, AS DESCRIBED IN SAID DEED RECORDED AT RECEPTION NO. 2004051359, SAID DOUGLAS COUNTY RECORDS, BEING A PORTION OF THE SOUTH HALF OF SECTION 28, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

THE BEARINGS FOR THESE EXCEPTION PARCELS ARE BASED ON THE SOUTH LINE OF SECTION 28, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH P.M. BEING ASSUMED TO BEAR S89°47'47"E, FROM THE SOUTHWEST CORNER OF SAID SECTION 28, BEING MONUMENTED BY A 1" PIPE WITH A 2-1/2" ALUMINUM CAP STAMPED "LS 6935" TO THE SOUTHEAST CORNER OF SAID SECTIONS 28, BEING MONUMENTED BY #6 REBAR WITH A 2-1/2" ALUMINUM CAP, STAMPED "LS 6935", WITH ALL BEARINGS CONTAINED HEREIN RELATIVE THERETO.

COMMENCING AT THE SOUTHWEST CORNER OF SAID SECTION 28, THENCE N 65°29'53" E, A DISTANCE OF 1282.04 FEET TO THE POINT OF BEGINNING;
THENCE N 00°37'44" W, A DISTANCE OF 208.93 FEET;
THENCE S 89°47'24" E, A DISTANCE OF 208.72 FEET;
THENCE N 00°40'40" E, A DISTANCE OF 208.93 FEET;
THENCE N 89°47'27" W, A DISTANCE OF 208.90 FEET TO THE POINT OF BEGINNING;

ALSO EXCEPTING THE FOLLOWING PARCEL

COMMENCING AT THE SOUTHEAST CORNER OF SAID SECTION 28, THENCE N 40°06'19" W, A DISTANCE OF 1765.57 FEET TO THE POINT OF BEGINNING;
THENCE N 89°46'42" W, A DISTANCE OF 208.73 FEET;
THENCE N 00°45'11" W, A DISTANCE OF 208.19 FEET;
THENCE S 89°55'33" E, A DISTANCE OF 208.72 FEET;
THENCE S 00°45'12" E, A DISTANCE OF 208.73 FEET TO THE POINT OF BEGINNING;

LESS AND EXCEPT THE FOLLOWING PARCEL OF LAND:

A TRACT OR PARCEL OF LAND NO. RW-20 OF THE DEPARTMENT OF TRANSPORTATION, STATE OF COLORADO PROJECT NO. 17638 CONTAINING 8,259 SQ. FT. (0.190 ACRES), MORE OR LESS, BEING PART OF TRACT A OF DAWSON RIDGE FILING A, LOCATED IN THE NE 1/4 OF THE SW 1/4 AND SE 1/4 OF THE SW 1/4 IN SECTION 22, TOWNSHIP 8 SOUTH, RANGE 67 WEST, OF THE SIXTH PRINCIPAL MERIDIAN, IN DOUGLAS COUNTY, COLORADO, SAID TRACT OR PARCEL BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

COMMENCING AT THE SOUTHWEST CORNER OF SAID SECTION 22, THENCE N. 49°50'55" E, A DISTANCE OF 1,964.79 FEET TO THE WEST LINE OF SAID TRACT A, SAID POINT ALSO BEING THE TRUE POINT OF BEGINNING;

- THENCE, ALONG SAID WEST LINE, ON THE ARC OF A CURVE TO THE LEFT, A RADIUS OF 1,730.00 FEET, A CENTRAL ANGLE OF 21°44'56", A DISTANCE OF 656.69 FEET, (A CHORD BEARING OF N. 10°32'52" E, A DISTANCE OF 652.76 FEET);
- THENCE, CONTINUING ALONG SAID WEST LINE, N. 00°17'07" W, A DISTANCE OF 114.23 FEET;
- THENCE, CONTINUING ALONG SAID WEST LINE, ON THE ARC OF A CURVE TO THE LEFT, A RADIUS OF 31.00 FEET, A CENTRAL ANGLE OF 86°19'08", A DISTANCE OF 46.71 FEET, (A CHORD BEARING OF N. 47°10'54" W, A DISTANCE OF 42.41 FEET);
- THENCE, CONTINUING ALONG SAID WEST LINE, N. 00°17'07" W, A DISTANCE OF 10.00 FEET TO THE INTERSECTION OF THE SOUTH RIGHT-OF-WAY LINE OF TERRITORIAL ROAD AND THE WEST RIGHT-OF-WAY LINE OF DAWSON RIDGE BOULEVARD;
- THENCE, ALONG SAID WEST RIGHT-OF-WAY LINE, ON THE ARC OF A CURVE TO THE RIGHT, A RADIUS OF 41.00 FEET, A CENTRAL ANGLE OF 86°47'35", A DISTANCE OF 62.11 FEET, (A CHORD BEARING S. 46°55'52" E, A DISTANCE OF 56.34 FEET);
- THENCE, CONTINUING ALONG SAID WEST RIGHT-OF-WAY LINE, S. 00°17'07" E, A DISTANCE OF 114.52 FEET;
- THENCE, CONTINUING ALONG SAID WEST RIGHT-OF-WAY LINE, ON THE ARC OF A CURVE TO THE RIGHT, A RADIUS OF 1,740.00 FEET, A CENTRAL ANGLE OF 21°39'02", A DISTANCE OF 657.50 FEET, (A CHORD BEARING S. 10°29'54" W, A DISTANCE OF 653.59 FEET);
- THENCE N. 85°14'11" W, A DISTANCE OF 10.44 FEET, MORE OR LESS, TO THE TRUE POINT OF BEGINNING.

BASIS OF BEARINGS: ALL BEARINGS ARE BASED ON A LINE BETWEEN THE SOUTHWEST CORNER OF SECTION 22, (BEING A 2.5" ALUMINUM CAP STAMPED "LS 6935 1988") AND THE WEST 1/4 CORNER OF SECTION 22 (BEING A SET 2.5" ALUMINUM CAP STAMPED "WOOLPERT T8S-R67W 1/4 S21 S22 PLS 38486 2018") AS BEING N. 02°26'33" W.

AND LESS AND EXCEPT THAT RETAINED RIGHT-OF-WAY OVER A PORTION OF DAWSON RIDGE BOULEVARD AS DESCRIBED IN ORDINANCE NO. 2021-020 RECORDED OCTOBER 6, 2021 AT RECEPTION NO. 2021114404.

AND LESS AND EXCEPT THOSE RIGHTS-OF-WAY DEDICATED TO THE TOWN OF CASTLE ROCK DESCRIBED IN THOSE DEEDS RECORDED AT RECEPTION NO. 2022020177 AND 2022020178, SAID DOUGLAS COUNTY RECORDS;

PARCEL 2:
COMMENCING AT THE SOUTH 1/16TH CORNER OF SAID SECTIONS 21 & 22, ALSO BEING A POINT ON THE SOUTH LINE OF TWIN OAKS, A SUBDIVISION PLAT RECORDED AT RECEPTION NO. 161972, IN THE RECORDS OF THE DOUGLAS COUNTY CLERK AND RECORDER'S OFFICE;

THENCE N 53°44'53" E, A DISTANCE OF 1331.13 FEET TO A POINT ON THE EAST LINE OF SAID TWIN OAKS PLAT AND A POINT ON THE NORTH LINE OF THE TERRITORIAL ROAD RIGHT-OF-WAY, AS DEDICATED BY THAT DEED RECORDED AT RECEPTION NO. 8816440, SAID DOUGLAS COUNTY RECORDS AND THE POINT OF BEGINNING;

THENCE ALONG THE EAST LINE OF SAID TWIN OAKS PLAT, THE FOLLOWING THREE (3) COURSES:

- N 17°17'13" E, A DISTANCE OF 557.93 FEET;
- S 89°27'27" E, A DISTANCE OF 65.00 FEET;
- N 00°22'15" W, A DISTANCE OF 1329.37 FEET TO THE SOUTHWEST CORNER OF LOT 3, SAID TWIN OAKS PLAT;

THENCE N 03°03'12" W, ALONG THE WEST LINE OF SAID LOT 3, A DISTANCE OF 567.45 FEET TO THE NORTHWEST CORNER OF SAID LOT 3, BEING A POINT OF CURVATURE ON THE SOUTH LINE OF THE BRISCOE LANE RIGHT-OF-WAY, AS DEDICATED BY SAID TWIN OAKS PLAT;
THENCE ALONG THE PORTIONS OF BRISCOE LANE VACATED BY ORDINANCE NO. 88-24, RECORDED IN BOOK 680 AT PAGE 920, SAID DOUGLAS COUNTY RECORDS THE FOLLOWING TWO (2) COURSES:

- N 39°55'38" W, A DISTANCE OF 30.00 FEET TO A POINT OF NON-TANGENT CURVATURE;
- ALONG THE ARC OF A NON-TANGENT CURVE TO THE RIGHT HAVING A RADIUS OF 329.30 FEET, A CENTRAL ANGLE OF 27°16'16" AND AN ARC LENGTH OF 156.74 FEET, SUBTENDED BY A CHORD OF WHICH BEARS N 63°42'30" E, A DISTANCE OF 155.26 FEET;

THENCE N 12°39'22" W, ALONG THE WEST LINE OF LOT 4, SAID TWIN OAKS PLAT, A DISTANCE OF 687.67 FEET TO THE NORTHWEST CORNER OF SAID LOT 4 ALSO BEING THE WEST 1/16TH CORNER OF SAID SECTIONS 15 & 22;
THENCE S 89°31'22" E, ALONG THE SOUTH LINE OF THE SOUTHWEST QUARTER OF SAID SECTION 15, A DISTANCE OF 890.07 FEET TO THE SOUTHWEST CORNER OF THAT PARCEL OF LAND DESCRIBED AS PARCEL E IN THAT DEED RECORDED AT RECEPTION NO. 2019088324, SAID DOUGLAS COUNTY RECORDS;

RECORDS;
THENCE ALONG THE WEST AND NORTH LINES OF PARCELS E, F & G THE FOLLOWING FOUR (4) COURSES:

- N 00°11'34" E, A DISTANCE OF 900.14 FEET;
- S 89°48'26" E, ALONG THE NORTH LINES OF PARCELS E AND F, A DISTANCE OF 1014.77 FEET TO THE SOUTHWEST CORNER OF THAT PARCEL OF LAND DESCRIBED AS PARCEL G;
- N 00°11'34" E, A DISTANCE OF 842.72 FEET;
- S 89°48'26" E, A DISTANCE OF 928.55 FEET TO A POINT ON THE WEST LINE OF THE BURLINGTON NORTHERN SANTA FE RAILROAD RIGHT OF WAY AND A POINT OF NON-TANGENT CURVATURE;

THENCE ALONG THE WEST LINE OF SAID BURLINGTON NORTHERN SANTA FE RAILROAD RIGHT-OF-WAY THE FOLLOWING TWO (2) COURSES:

- ALONG THE ARC OF A NON-TANGENT CURVE TO THE LEFT HAVING A RADIUS OF 5779.58 FEET, A CENTRAL ANGLE OF 05°35'04" AND AN ARC LENGTH OF 563.33 FEET, SUBTENDED BY A CHORD OF WHICH BEARS S 18°04'54" W, A DISTANCE OF 563.11 FEET;
- S 15°17'57" W, A DISTANCE OF 4536.04 FEET TO A POINT ON THE NORTH LINE OF SAID TERRITORIAL ROAD RIGHT-OF-WAY;

THENCE S 89°40'41" W, ALONG SAID NORTH LINE, A DISTANCE OF 1628.83 FEET TO THE POINT OF BEGINNING.

LESS AND EXCEPT THOSE PARCELS OF LAND DESCRIBED AS RW-18 AND RW-18A IN THAT DEED RECORDED AT RECEPTION NO. 2021056802.

SUMMARY TABLE

CHARACTER AREA	PLANNING AREA	LAND USE TYPE	ACREAGE	MAX. DWELLING UNITS	MIN TRANSITION LOT SIZE	MIN. NON-RES AREA (AC)	% OF PROPERTY	MAX BUILDING HEIGHT (1)
WEST	A	SFD	236.5	471	7,700 sf	N/A	11.5%	35'
	B-1	SFD	124.4	484	6,600 sf	N/A	6.0%	35'
	B-2	SFD	58.9	228	6,600 sf	N/A	2.9%	35'
Totals			N/A	419.8	1,183	N/A	20.3%	
CENTRAL	C-1	SFD, SFA, MF, Non-Res	151.9	481	N/A	N/A	7.4%	45'
	C-2	SFD, SFA, MF	187.4	908	N/A	N/A	9.1%	50'
	D	SFD, SFA, MF, Non-Res	206.2	1,938	N/A	N/A	10.0%	60'
	Totals			N/A	545.5	3,327	N/A	26.4%
EAST	E-1	Non-Res	6.5	N/A	N/A	6.5	0.3%	50'
	E-2	SFD, SFA, MF, Non-Res	62.4	400	N/A	N/A	3.0%	60'
	F-1	SFA, MF, Non-Res	41.0		N/A		2.0%	75/90' (1)
	F-2	SFA, MF, Non-Res	33.4	940		45	1.6%	75/90' (1)
	F-3	SFA, MF, Non-Res	81.9		N/A		4.0%	75/90' (1)
	G-1	Non-Res	62.6	0	N/A	66.9	3.0%	75/90' (1)
	G-2	Non-Res	4.3	0	N/A		0.2%	75/90' (1)
	Totals			N/A	292.1	1,340	N/A	14.2%

MAX. DWELLING UNITS - ALL 3 CHARACTER AREAS COMBINED (NOT TO EXCEED) 5,850

MAX. MULTI FAMILY DWELLING UNITS (LOCATED IN C-1, C-2, D, E-2, F-1, F-2, F-3) 2,400

MAX. COMM/NON-RES. SQ. FT. - EAST & CENTRAL CHARACTER AREAS 3,200,000

PLANNING AREAS		
PLANNING AREAS	1,257.4	60.9%
OPEN SPACE (PL-2 & OS)	533.0	25.8%
PUBLIC LAND DEDICATION (PL-1)	227.6	11.0%
ROW (ARTERIAL)	45.7	2.2%
TOTAL PROPERTY (APPROXIMATELY)	2,063.7	100.0%

LAND USE SUMMARY NOTE:
1.) FOR PLANNING AREAS F AND G, VERTICAL MIXED-USE, HOSPITALITY, MEDICAL, OFFICE, AND MULTI-FAMILY RESIDENTIAL USES ARE ALLOWED TO HAVE A MAXIMUM HEIGHT OF 90 FEET PER SECTION 6.11 ON SHEET 17.

PDP STANDARD NOTES

- A SMALL PORTION OF THE MINERAL RIGHTS ASSOCIATED WITH THIS PROPERTY HAVE BEEN SEVERED. FOR THE SMALL PORTION OF SEVERED MINERAL RIGHTS, A WAIVER OF NOTICE BY SUCH HOLDER HAS BEEN RECEIVED AS A PART OF THE AMENDMENT.
- THIS PROPERTY LIES WITHIN FEMA ZONE X, THE UNSHADED AREA OF FIRM MAPS NO. 08035C0282G, 08035C0301G, 08035C0283F, 08035C0284G, AND 08035C0292F, REVISED MARCH 16, 2016. NO STRUCTURES SHALL BE PERMITTED IN THE APPROVED 100-YEAR FLOOD PLAIN. THE SITE ALSO HAS MAJOR DRAINAGEWAYS WITH BASIN AREAS GREATER THAN 130 ACRES ONSITE.
- THIS PROPERTY IS WITHIN THE TOWN OF CASTLE ROCK BLUE, RED AND GREEN WATER PRESSURE ZONES.
- ALL-WEATHER (CONCRETE OR ASPHALT) SURFACED ACCESS ROADS CAPABLE OF WITHSTANDING THE IMPOSED LOADS OF FIRE APPARATUS (75,000 LBS.) AND ALL REQUIRED FIRE HYDRANTS SHALL BE INSTALLED AND MADE SERVICEABLE PRIOR TO AND DURING ALL VERTICAL CONSTRUCTION.
- RIGHT-OF-WAY FOR INGRESS AND EGRESS FOR EMERGENCY VEHICLES IS GRANTED OVER, ACROSS, ON AND THROUGH ANY AND ALL PRIVATE ROADS AND DRIVES.

GENERAL NOTES

- ALL DEVELOPMENT ASSOCIATED WITH THE DAWSON TRAILS PDP SHALL COMPLY WITH ALL FEDERAL, STATE AND TOWN REGULATIONS REGARDING WILDLIFE INCLUDING THE MIGRATORY BIRD ACT AND BURROWING OWL SURVEY IF REQUIRED.
- UPDATED SOILS REPORTS SHALL BE SUBMITTED WITH EACH SITE DEVELOPMENT PLAN AND/OR PLAT.
- ALL EVA ACCESS GATES WILL INCLUDE AN OPTICOM SYSTEM OR OTHER SYSTEM APPROVED BY THE TOWN OF CASTLE ROCK FIRE DEPARTMENT.
- A WILDLAND/URBAN INTERFACE WILDFIRE VEGETATION MANAGEMENT PLAN (PLAN), OR COMPLIANCE LETTER, IS REQUIRED TO BE SUBMITTED FOR EACH PHASE OF THE PLANNED DEVELOPMENT WITH THE FIRST SDP OR CONSTRUCTION DRAWINGS FOR EVALUATION AND APPROVAL BY THE TOWN OF CASTLE ROCK FIRE DEPARTMENT. THE PLAN SHALL BE DEVELOPED BY A DESIGN PROFESSIONAL FAMILIAR WITH WILDFIRE MITIGATION TECHNIQUES AND STANDARDS. REFER TO SHEET 13 AND THE TOWN OF CASTLE ROCK COMMUNITY WILDFIRE PROTECTION PLAN.

APPLICANT:
WESTSIDE INVESTMENT PARTNERS
4100 E. MISSISSIPPI AVE
SUITE 500
DENVER, CO 80246
303-984-9800

ENGINEER & SURVEYOR:
CORE CONSULTANTS, INC.
CORE CONSULTANTS
3473 S. BROADWAY
ENGLEWOOD, CO 80113
303-730-5960

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE:
PDP-01 07/08/2021
PDP-02 12/03/2021
PDP-03 04/13/2022
PDP-04 05/27/2022
PDP-05 06/09/2022

SHEET TITLE:
COVER

SHEET
1 OF 20

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

OWNERSHIP CERTIFICATION:

THE UNDERSIGNED ARE ALL THE OWNERS OF CERTAIN LANDS IN THE TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS AND STATE OF COLORADO DESCRIBED HEREIN.

Andrew R. Klein
ACM DAWSON TRAILS VIII JV LLC

SIGNED THIS 18th DAY OF November, 2022


NOTARY BLOCK

SUBSCRIBED AND SWORN TO BEFORE ME THIS 18 DAY OF November, 2022

BY ANDREW R. KLEIN AS AUTHORIZED SIGNATORY OF ACM DAWSON TRAILS VIII JV LLC, A DELAWARE LIMITED LIABILITY COMPANY

WITNESS MY HAND AND OFFICIAL SEAL.

Blake Amen
NOTARY PUBLIC



MY COMMISSION EXPIRES: 8/12/24

OWNERSHIP CERTIFICATION:

THE UNDERSIGNED ARE ALL THE OWNERS OF CERTAIN LANDS IN THE TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS AND STATE OF COLORADO DESCRIBED HEREIN.

TOWN OF CASTLE ROCK, A MUNICIPAL CORPORATION

BY Jason Gray
MAYOR

ATTEST:

Lisa Anderson
TOWN CLERK

SIGNED THIS 27 DAY OF January, 2023


NOTARY BLOCK

SUBSCRIBED AND SWORN TO BEFORE ME THIS 27th DAY OF FEBRUARY, 2023

BY JASON GRAY AS MAYOR AND BY LISA ANDERSON AS TOWN CLERK.

WITNESS MY HAND AND OFFICIAL SEAL.

Sharon Dahl
NOTARY PUBLIC



MY COMMISSION EXPIRES: 9/30/2024

TITLE CERTIFICATION:

I, JOE BELONGIA, AN AUTHORIZED REPRESENTATIVE OF FIDELITY NATIONAL TITLE INSURANCE COMPANY LICENSED TO DO BUSINESS IN THE STATE OF COLORADO, HAVE MADE AN EXAMINATION OF THE PUBLIC RECORDS AND STATE THAT ALL OWNERS, MORTGAGES AND LIENHOLDERS OF THE PROPERTY ARE LISTED IN THE CERTIFICATE OF OWNERSHIP AND LIENHOLDER SUBORDINATION CERTIFICATE.

Joe Belongia
AUTHORIZED REPRESENTATIVE

Fidelity National Title Company
TITLE COMPANY

SIGNED THIS 23rd DAY OF November, 2022

NOTARY BLOCK


SUBSCRIBED AND SWORN TO BEFORE ME THIS 23rd DAY OF November, 2022

BY JOE BELONGIA AS AUTHORIZED REPRESENTATIVE

OF Fidelity National Title Company

WITNESS MY HAND AND OFFICIAL SEAL.

Robert Matthews
NOTARY PUBLIC



MY COMMISSION EXPIRES: 6/4/2023

LIENHOLDER SUBORDINATION CERTIFICATE:

THE UNDERSIGNED ARE ALL THE MORTGAGEES AND LIENHOLDERS OF CERTAIN LANDS IN THE TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS AND STATE OF COLORADO DESCRIBED HEREON. THE UNDERSIGNED BENEFICIARY OF THE LIEN CREATED BY THE INSTRUMENT RECORDED MAY 6, 2021 AT RECEPTION NO. 2021059176, DOUGLAS COUNTY, COLORADO, AS MODIFIED BY INSTRUMENT RECORDED APRIL 5, 2022 AT RECEPTION NO. 2022024399 AND INSTRUMENT RECORDED OCTOBER 6, 2022 AT RECEPTION NO. 2022065718, SUBORDINATES THE SUBJECT LIEN TO THE TERMS, CONDITIONS AND RESTRICTIONS OF THIS DOCUMENT.

Gregory W. Brown
SWQ LLC, A COLORADO LIMITED LIABILITY COMPANY

SIGNED THIS 30 DAY OF November, 2022

NOTARY BLOCK

SUBSCRIBED AND SWORN TO BEFORE ME THIS 30 DAY OF

NOVEMBER, 2022 BY GREGORY W. BROWN

AS MANAGER OF SWQ LLC
WITNESS MY HAND AND OFFICIAL SEAL.

Joanne E. Colley
NOTARY PUBLIC

MY COMMISSION EXPIRES: AUGUST 14, 2023

LIENHOLDER SUBORDINATION CERTIFICATE:

THE UNDERSIGNED ARE ALL THE MORTGAGEES AND LIENHOLDERS OF CERTAIN LANDS IN THE TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS AND STATE OF COLORADO DESCRIBED HEREON. THE UNDERSIGNED BENEFICIARY OF THE LIEN

CREATED BY THE INSTRUMENT RECORDED OCTOBER 6, 2022 AT RECEPTION NO. 2022065715, DOUGLAS COUNTY, COLORADO, SUBORDINATES THE SUBJECT LIEN TO THE TERMS, CONDITIONS AND RESTRICTIONS OF THIS DOCUMENT.

Patrick Riley
FIRST BANK, A COLORADO BANKING COMPANY

SIGNED THIS 28th DAY OF November, 2022

NOTARY BLOCK

SUBSCRIBED AND SWORN TO BEFORE ME THIS 28th DAY OF

November, 2022 BY Patrick Riley

AS Executive Vice President OF Firstbank
WITNESS MY HAND AND OFFICIAL SEAL.

Cliff Riva
NOTARY PUBLIC


MY COMMISSION EXPIRES: May 22, 2025

SURVEYOR'S CERTIFICATE:

I, Miles Small, A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF COLORADO, DO HEREBY CERTIFY THAT THE SURVEY AND LEGAL DESCRIPTION REPRESENTED BY THIS PLANNED DEVELOPMENT PLAN WAS MADE UNDER MY SUPERVISION AND THE MONUMENTS SHOWN THEREON ACTUALLY EXIST AND THIS PLANNED DEVELOPMENT PLAN ACCURATELY REPRESENTS THAT SURVEY.

Miles Small
REGISTERED LAND SURVEYOR

11-25-22
DATE



PLANNING COMMISSION RECOMMENDATION:

THIS PLANNED DEVELOPMENT PLAN WAS RECOMMENDED FOR APPROVAL BY THE PLANNING COMMISSION OF THE TOWN OF CASTLE ROCK, COLORADO ON THE

11th DAY OF AUGUST, 2022

Cliff Riva
CHAIR

January 4, 2023
DATE

ATTEST:

Assistant Director of Development Services

1/4/2023
DATE

TOWN COUNCIL APPROVAL:

THIS PLANNED DEVELOPMENT PLAN WAS APPROVED BY THE TOWN COUNCIL OF THE TOWN OF CASTLE ROCK, COLORADO, ON THE

6th DAY OF September, 2022


Jeffrey
MAYOR

1-17-2023
DATE

ATTEST:

Robbie Schenker
TOWN CLERK

1-17-2023
DATE




DOUGLAS COUNTY CLERK AND RECORDER'S CERTIFICATE:

THIS PLANNED DEVELOPMENT PLAN WAS FILED FOR RECORD IN THE OFFICE OF THE COUNTY CLERK AND RECORDER OF DOUGLAS

COUNTY AT 2:41 pm ON THE 8th DAY OF February, 2023 AT RECEPTION NO. 2023005659

DOUGLAS COUNTY CLERK AND RECORDER

BY: Debra



PLANNER/LANDSCAPE ARCHITECT
NORRIS DESIGN
1101 Bannock Street
Denver, Colorado 80204
P 303.852.1166
www.norris-design.com

ENGINEER & SURVEYOR:
CORE CONSULTANTS, INC.
CORE CONSULTANTS
3473 S. BROADWAY
ENGLEWOOD, CO 80113
303-730-5960

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE:
PDP-01 07/08/2021
PDP-02 12/03/2021
PDP-03 04/13/2021
PDP-04 05/27/2022
PDP-05 06/09/2022

SHEET TITLE:
OWNERSHIP CERTIFICATION

SHEET
2 OF 20

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

APPLICANT:



WESTSIDE INVESTMENT PARTNERS
 4100 E. MISSISSIPPI AVE
 SUITE 500
 DENVER, CO 80246
 303-984-9800

ENGINEER & SURVEYOR:



CORE CONSULTANTS, INC.
 CORECONSULTANTS.COM
 CORE CONSULTANTS
 3473 S. BROADWAY
 ENGLEWOOD, CO 80113
 303-730-5960



DAWSON TRAILS
 PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
 (AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)


OPEN SPACE AND PUBLIC LAND SUMMARY

	ACREAGE	% OF TOTAL
PUBLIC LAND		
PL-1 (DEDICATED TO TOWN)	227.6	11.0%
OPEN SPACE		
PL-2 (DEDICATED TO TOWN)	462.2	22.4%
OSP (PRIVATE)	70.8	3.4%
SUBTOTAL	533.0	25.8%
FUTURE OPEN SPACE (1)	215.0	10.4%
OPEN SPACE TOTAL	748.0	36.2%
OPEN SPACE AND PUBLIC LAND TOTAL	975.6	47.3%


NOTE: (1) FUTURE OPEN SPACE DESIGNATION (PL-1, PL-2, OSP) TO BE DETERMINED AT TIME OF PLAT.

LEGEND

- PROPERTY BOUNDARY
- PLANNING AREA BOUNDARY
- CHARACTER AREA BOUNDARY
- MAJOR DRAINAGEWAY
- TRANSITION ZONE
- MODERATE SKYLINE
- MINOR SKYLINE
- 100 YEAR FLOODPLAIN (TOWN OF CASTLE ROCK)
- 100 YEAR FLOODPLAIN (FEMA)
- PROPOSED ARTERIAL RIGHT OF WAY
- FUTURE COLLECTOR RIGHT OF WAY
- 5' NATURAL SURFACE TRAIL
- 10' HARD SURFACE TRAIL



CHECKED BY: MB, SW
 DRAWN BY: DJ, JR





DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

KEY MAP



LEGEND

	PROPERTY BOUNDARY		TRANSITION ZONE		PROPOSED ARTERIAL RIGHT OF WAY
	PLANNING AREA BOUNDARY		MODERATE SKYLINE		FUTURE COLLECTOR RIGHT OF WAY
	CHARACTER AREA BOUNDARY		MINOR SKYLINE		5' NATURAL SURFACE TRAIL
	MAJOR DRAINAGEWAY		100 YEAR FLOODPLAIN (TOWN OF CASTLE ROCK)		10' HARD SURFACE TRAIL
			100 YEAR FLOODPLAIN (FEMA)		



DAWSON TRAILS PLANNED DEVELOPMENT PLAN | PROJECT NO. PDP21-0001

PLANNER/LANDSCAPE ARCHITECT
NORRIS DESIGN
Planning | Landscape Architecture | Branding
1101 Bannock Street
Denver, Colorado 80204
P 303.892.1166
www.norris-design.com

APPLICANT:

WESTSIDE INVESTMENT PARTNERS
4100 E. MISSISSIPPI AVE
SUITE 500
DENVER, CO 80246
303-984-9800
ENGINEER & SURVEYOR:
CORE
CORE CONSULTANTS, INC.
LIVEYOURCORE.COM
CORE CONSULTANTS
3473 S. BROADWAY
ENGLEWOOD, CO 80113
303-730-5960



DAWSON TRAILS
PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE:
PDP-01 07/08/2021
PDP-02 12/03/2021
PDP-03 04/13/2022
PDP-04 05/27/2022
PDP-05 06/09/2022

SHEET TITLE:
PD PLAN

SHEET
4 OF 20



CHECKED BY: MB, SW
DRAWN BY: DJ, JR.

DAWSON TRAILS


PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

KEY MAP




NORTH



LEGEND

- | | | | | | |
|--|-------------------------|--|---|--|--------------------------------|
| | PROPERTY BOUNDARY | | TRANSITION ZONE | | PROPOSED ARTERIAL RIGHT OF WAY |
| | PLANNING AREA BOUNDARY | | MODERATE SKYLINE | | FUTURE COLLECTOR RIGHT OF WAY |
| | CHARACTER AREA BOUNDARY | | MINOR SKYLINE | | 5' NATURAL SURFACE TRAIL |
| | MAJOR DRAINAGEWAY | | 100 YEAR FLOODPLAIN (TOWN OF CASTLE ROCK) | | 10' HARD SURFACE TRAIL |
| | | | 100 YEAR FLOODPLAIN (FEMA) | | |



PLANNER/LANDSCAPE ARCHITECT

NORRIS DESIGN
 Planning | Landscape Architecture | Branding
 1101 Bannock Street
 Denver, Colorado 80204
 P 303.892.1166
 www.norris-design.com

APPLICANT:

WESTSIDE INVESTMENT PARTNERS
 4100 E. MISSISSIPPI AVE
 SUITE 500
 DENVER, CO 80246
 303-984-9800

ENGINEER & SURVEYOR:

CORE
 CORE CONSULTANTS, INC.
 CORE CONSULTANTS
 3473 S. BROADWAY
 ENGLEWOOD, CO 80113
 303-730-5960



DAWSON TRAILS
 PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
 (AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE:
 PDP-01 07/08/2021
 PDP-02 12/03/2021
 PDP-03 04/13/2022
 PDP-04 05/27/2022
 PDP-05 06/09/2022

SHEET TITLE:
 PD PLAN

SHEET
 5 OF 20

CHECKED BY:
 MB, SW
 DRAWN BY:
 DJ, JR




DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS


(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

KEY MAP



LEGEND



PLANNER/LANDSCAPE ARCHITECT
NORRIS DESIGN
 Planning | Landscape Architecture | Branding
 1101 Bannock Street
 Denver, Colorado 80204
 P 303.892.1166
 www.norris-design.com

APPLICANT:

WESTSIDE INVESTMENT PARTNERS
 4100 E. MISSISSIPPI AVE
 SUITE 500
 DENVER, CO 80246
 303-984-9800

ENGINEER & SURVEYOR:

CORE CONSULTANTS INC.
 CORE CONSULTANTS
 3473 S. BROADWAY
 ENGLEWOOD, CO 80113
 303-730-5960


DAWSON TRAILS

DAWSON TRAILS
 PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
 (AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE:
 PDP-01 07/08/2021
 PDP-02 12/03/2021
 PDP-03 04/13/2022
 PDP-04 05/27/2022
 PDP-05 06/09/2022

SHEET TITLE:
 PD PLAN

SHEET
 6 OF 20



CHECKED BY:
 MB, SW
 DRAWN BY:
 DJ, JR



DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)


TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

KEY MAP



LEGEND

- | | | | | | |
|--|-------------------------|--|---|--|--------------------------------|
| | PROPERTY BOUNDARY | | TRANSITION ZONE | | PROPOSED ARTERIAL RIGHT OF WAY |
| | PLANNING AREA BOUNDARY | | MODERATE SKYLINE | | FUTURE COLLECTOR RIGHT OF WAY |
| | CHARACTER AREA BOUNDARY | | MINOR SKYLINE | | 5' NATURAL SURFACE TRAIL |
| | MAJOR DRAINAGEWAY | | 100 YEAR FLOODPLAIN (TOWN OF CASTLE ROCK) | | 10' HARD SURFACE TRAIL |
| | | | 100 YEAR FLOODPLAIN (FEMA) | | |



PLANNER/LANDSCAPE ARCHITECT

NORRIS DESIGN
 Planning | Landscape Architecture | Branding
 1101 Bannock Street
 Denver, Colorado 80204
 P 303.892.1168
 www.norris-design.com

APPLICANT:

WESTSIDE INVESTMENT PARTNERS
 4100 E. MISSISSIPPI AVE
 SUITE 500
 DENVER, CO 80246
 303-984-9800

ENGINEER & SURVEYOR:

CORE
 CORE CONSULTANTS, INC.
 3473 S. BROADWAY
 ENGLEWOOD, CO 80113
 303-730-5960

DAWSON TRAILS

DAWSON TRAILS
 PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
 (AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE:
 PDP-01 07/08/2021
 PDP-02 12/03/2021
 PDP-03 04/13/2022
 PDP-04 05/27/2022
 PDP-05 06/09/2022

SHEET TITLE:
 PD PLAN

SHEET
 7 OF 20

CHECKED BY: MB, SW
 DRAWN BY: DJ, JR

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
 TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

PLANNER/LANDSCAPE ARCHITECT
 NORRIS DESIGN
 Planning | Landscape Architecture | Branding
 1101 Bannock Street
 Denver, Colorado 80204
 P 303.892.1166
 www.norris-design.com



APPLICANT:
 WESTSIDE INVESTMENT PARTNERS
 4100 E. MISSISSIPPI AVE
 SUITE 500
 DENVER, CO 80246
 303-984-9800
 ENGINEER & SURVEYOR:
 CORE CONSULTANTS
 CORE CONSULTANTS INC.
 LIVEYOURCORE.COM
 CORE CONSULTANTS
 3473 S. BROADWAY
 ENGLEWOOD, CO 80113
 303-730-5960




DAWSON TRAILS
 PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
 (AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE:
 PDP-01 07/08/2021
 PDP-02 12/03/2021
 PDP-03 04/13/2022
 PDP-04 05/27/2022
 PDP-05 06/09/2022

SHEET TITLE:
 PD PLAN
 SHEET
 8 OF 20



LEGEND	
	PROPERTY BOUNDARY
	PLANNING AREA BOUNDARY
	CHARACTER AREA BOUNDARY
	MAJOR DRAINAGEWAY
	TRANSITION ZONE
	MODERATE SKYLINE
	MINOR SKYLINE
	100 YEAR FLOODPLAIN (TOWN OF CASTLE ROCK)
	PROPOSED ARTERIAL RIGHT OF WAY
	FUTURE COLLECTOR RIGHT OF WAY
	5' NATURAL SURFACE TRAIL
	10' HARD SURFACE TRAIL
	100 YEAR FLOODPLAIN (FEMA)



CHECKED BY: MB, SW
 DRAWN BY: DJ, JR

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

PLANNER/LANDSCAPE ARCHITECT
 NORRIS DESIGN
 Planning | Landscape Architecture | Branding
 1101 Bannock Street
 Denver, Colorado 80204
 P 303.862.1166
 www.norris-design.com

APPLICANT:
 WESTSIDE INVESTMENT PARTNERS
 4100 E. MISSISSIPPI AVE SUITE 500
 DENVER, CO 80246
 303-984-9800

ENGINEER & SURVEYOR:
 CORE
 CORE CONSULTANTS, INC.
 CORECONSULTANTS.COM
 CORE CONSULTANTS
 3473 S. BROADWAY
 ENGLEWOOD, CO 80113
 303-730-5960


DAWSON TRAILS

DAWSON TRAILS
 PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
 (AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE:
 PDP-01 07/08/2021
 PDP-02 12/03/2021
 PDP-03 04/13/2022
 PDP-04 05/27/2022
 PDP-05 06/09/2022

SHEET TITLE:
 OPEN SPACE PLD. & TRAILS PLAN

SHEET
 9 OF 20



- NOTES**
- TRAILS SHOWN ON THIS PLAN EXHIBIT REPRESENT CONCEPTUAL ALIGNMENTS THAT WILL BE FINALIZED DURING THE SITE DEVELOPMENT PLAN/PLAT/CDS PROCESS FOR EACH PHASE OF THE PROJECT. THESE ALIGNMENTS REPRESENT A CONNECTED PEDESTRIAN SYSTEM THAT INCLUDES BOTH TRAILS THROUGH OPEN SPACE AREAS AND TRAILS/SIDEWALKS ADJACENT TO ROADS AND STREETS. CONNECTIONS TO EACH PLANNING AREA WILL BE MADE TO FACILITATE ACCESS, AS APPROPRIATE. SOME TRAIL ALIGNMENTS MAY CHANGE SIGNIFICANTLY BASED ON TOPOGRAPHY/SLOPE/GRADING/DRAINAGE, EXISTING VEGETATION, CONSTRUCTABILITY, AND OTHER FACTORS CONSIDERED AT THE TIME THEY ARE DESIGNED/ENGINEERED.
 - TRAIL AND OPEN SPACE IMPROVEMENTS WILL BE CONSTRUCTED IN A PHASED MANNER IN ACCORDANCE WITH THE DEVELOPMENT AGREEMENT AND IN COORDINATION WITH PLATTING/CDS AND ASSOCIATED CONSTRUCTION TIMING OF IMPROVEMENTS WITHIN THOSE SUBDIVISION FILINGS. GENERALLY, AS PRIVATE DEVELOPMENT AREAS ARE PLANNED/ENGINEERED, REQUIRED IMPROVEMENTS ASSOCIATED WITH ADJACENT PL-1, PL-2 AND OSP (OPEN SPACE) AREAS THAT ARE BEING PLATTED WILL BE COORDINATED AND PLANNED/DESIGNED/ENGINEERED TO THE LEVEL REQUIRED BASED ON TOWN APPROVAL, PERMITTING OR CONSTRUCTION TIMING NEEDS.
 - ATTACHED AND DETACHED SIDEWALKS ARE NOT INCLUDED IN THE TRAIL SYSTEM.
 - PRIVATE OPEN SPACE RECLASSIFICATION PERMITTED WITH TOWN APPROVAL. A LIMITED AMOUNT (MAXIMUM 20 ACRES) OF LAND DEPICTED AS PL-1 AND/OR PL-2 IN THIS PDP SHALL BE PERMITTED TO BE RECLASSIFIED AS PRIVATE OPEN SPACE (OSP). RECLASSIFICATION OF ANY FUTURE OSP TRACTS WILL BE COORDINATED WITH THE TOWN, AS APPROPRIATE, DURING THE SITE DEVELOPMENT PLAN / PLAT STAGE OF THE DEVELOPMENT REVIEW PROCESS AS MORE DETAIL IS KNOWN TO DETERMINE WHERE THESE SITES SHOULD BE LOCATED. ANY PORTION OF THE POTENTIAL 20 ACRES THAT ARE NOT RECLASSIFIED AND PLATTED AS OSP SHALL REMAIN AS PL-1 OR PL-2 AND SHALL BE PLATTED/DEDICATED TO THE TOWN. REPLACEMENT OF RECLASSIFIED ACREAGE IS NOT REQUIRED.
 - EXISTING VEGETATION TO BE RETAINED WILL BE DESIGNATED ON SITE DEVELOPMENT PLANS.

OPEN SPACE AND PUBLIC LAND SUMMARY

	ACREAGE	% OF TOTAL
PUBLIC LAND		
PL-1 (DEDICATED TO TOWN)	227.6	11.0%
OPEN SPACE		
PL-2 (DEDICATED TO TOWN)	462.2	22.4%
OSP (PRIVATE)	70.8	3.4%
SUBTOTAL	533.0	25.8%
FUTURE OPEN SPACE (1)	215.0	10.4%
OPEN SPACE TOTAL	748.0	36.2%
OPEN SPACE AND PUBLIC LAND TOTAL	975.6	47.3%

NOTE: (1) FUTURE OPEN SPACE DESIGNATION (PL-1, PL-2, OSP) TO BE DETERMINED AT TIME OF PLAT.

PARCEL SUMMARY

PUBLIC LAND	ACREAGE	% OF PROPERTY
PL-1.01	4.5	0.2%
PL-1.02	8.0	0.4%
PL-1.03	12.0	0.6%
PL-1.04	12.2	0.6%
PL-1.05	13.0	0.6%
PL-1.06	7.5	0.4%
PL-1.07	44.1	2.1%
PL-1.08	5.0	0.2%
PL-1.09	12.0	0.6%
PL-1.10	109.3	5.3%
PL-1 TOTAL	227.6	11.0%

OPEN SPACE	ACREAGE	% OF PROPERTY
PL-2.01	382.9	18.6%
PL-2.02	31.2	1.5%
PL-2.03	0.9	0.0%
PL-2.04	6.5	0.3%
PL-2.05	8.4	0.4%
PL-2.06	4.4	0.2%
PL-2.07	27.0	1.3%
PL-2.08	0.9	0.0%
PL-2 TOTAL	462.2	22.4%


OSP (PRIVATE)	ACREAGE	% OF PROPERTY
OSP-1	8.5	0.4%
OSP-2	4.1	0.2%
OSP-3	17.3	0.8%
OSP-4	3.9	0.2%
OSP-5	4.5	0.2%
OSP-6	11.7	0.6%
OSP-7	16.8	0.8%
OSP-8	4.0	0.2%
OSP TOTAL	70.8	3.4%

FUTURE OPEN SPACE (1)	215.0	10.4%
OPEN SPACE TOTAL	748.0	36.2%
OPEN SPACE & PUBLIC LAND TOTAL	975.6	47.3%

NOTE: (1) FUTURE OPEN SPACE DESIGNATION (PL-1, PL-2, OSP) TO BE DETERMINED AT TIME OF PLAT.

LEGEND

- PROPERTY BOUNDARY
- PLANNING AREA BOUNDARY
- CHARACTER AREA BOUNDARY
- PROPOSED ARTERIAL RIGHT OF WAY
- FUTURE COLLECTOR RIGHT OF WAY
- PROPOSED PLD
- PROPOSED OPEN SPACE (PL-2 AND OSP)
- HIGHPOINTS
- 100 YEAR FLOODPLAIN (TOWN OF CASTLE ROCK)
- 100 YEAR FLOODPLAIN (FEMA)
- 5' NATURAL SURFACE TRAIL
- 10' HARD SURFACE TRAIL
- MAJOR DRAINAGEWAY
- REGIONAL DETENTION POND (APPROXIMATE LOCATION)



CHECKED BY: MB, SW
 DRAWN BY: DJ, JR

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
 TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

PLANNER/LANDSCAPE ARCHITECT

NORRIS DESIGN
 Planning | Landscape Architecture | Branding

1101 Bannock Street
 Denver, Colorado 80204
 P. 303.892.1166
 www.norris-design.com

APPLICANT:



WESTSIDE INVESTMENT PARTNERS
 4100 E. MISSISSIPPI AVE
 SUITE 500
 DENVER, CO 80246
 303-984-9800


ENGINEER & SURVEYOR:



CORE CONSULTANTS, INC.
 CORECONSULTANTS.COM
CORE CONSULTANTS
 3473 S. BROADWAY
 ENGLEWOOD, CO 80113
 303-730-5960




DAWSON TRAILS
 PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
 (AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)



LEGEND

- | | | | | | |
|--|---------------------|--|------------------------|--|---|
| | PROPERTY BOUNDARY | | HIGH HABITAT * | | MAJOR DRAINAGEWAY |
| | HISTORIC RAILROAD | | LOW HABITAT * | | 100 YEAR FLOODPLAIN (TOWN OF CASTLE ROCK) |
| | EXISTING VEGETATION | | -ELEV. 6755 HIGHPOINTS | | 100 YEAR FLOODPLAIN (FEMA) |

* NOTE: SOURCE DOCUMENT IS DOUGLAS COUNTY 2040 COMPREHENSIVE MASTER WILDLIFE RESOURCES MAP PLAN



- DATE:
- PDP-01 07/08/2021
 - PDP-02 12/03/2021
 - PDP-03 04/13/2022
 - PDP-04 05/27/2022
 - PDP-05 06/09/2022

SHEET TITLE:
 NATURAL FEATURES MAP

SHEET
 10 OF 20

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

NORRIS DESIGN
Planning | Landscape Architecture | Consulting
1101 Bannock Street
Denver, Colorado 80204
P 303.892.1166
www.norris-design.com

APPLICANT:
WESTSIDE INVESTMENT PARTNERS
4100 E. MISSISSIPPI AVE
SUITE 500
DENVER, CO 80246
303-984-9800

ENGINEER & SURVEYOR:
CORE
CORE CONSULTANTS, INC.
LIVEYOURCORE.COM
CORE CONSULTANTS
3473 S. BROADWAY
ENGLEWOOD, CO 80113
303-730-5960

DAWSON TRAILS


DAWSON TRAILS
PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

NOT FOR CONSTRUCTION

DATE:
PDP-01 07/08/2021
PDP-02 12/03/2021
PDP-03 04/13/2022
PDP-04 05/27/2022
PDP-05 06/09/2022

SHEET TITLE:
GRADING & DRAINAGE PLAN

SHEET
12 OF 20




LEGEND

- 5225 EXISTING MAJOR CONTOUR
- 5205 EXISTING MINOR CONTOUR
- BNSF RAILWAY TRACKS
- PLANNING AREA BOUNDARY
- MAJOR DRAINAGEWAY
- OFF-SITE DRAINAGE BASIN
- ON-SITE DRAINAGE BASIN
- MAJOR DRAINAGE BASIN DIVIDE
- OFF-SITE FLOW ARROW
- ON-SITE FLOW ARROW
- PROPOSED REGIONAL POND
- 100-YEAR FEMA FLOODPLAIN
- 100-YEAR TOWN FLOODPLAIN

NOTES:

1. DRAINAGE BASINS AND POND LOCATIONS ARE APPROXIMATE.
2. POND CONFIGURATIONS AND LOCATIONS ARE CONCEPTUAL AND MAY CHANGE DUE TO FIELD CONDITIONS AND/OR FINAL SITE CONFIGURATIONS.
3. THE SITE LIES WITH THE UNSHADED X PORTION OF THE FEMA 100-YEAR FLOODPLAIN.
4. TOWN 100-YEAR FLOODPLAINS ASSOCIATED WITH THE SOUTH DAWSON, NORTH DAWSON, GAMBLE RIDGE, GAMBLE RIDGE NORTH, AND UNNAMED TRIBUTARIES WILL BE RE-EVALUATED BY A FLOODPLAIN MODIFICATION STUDY.
5. EFFORTS WILL BE MADE TO STABILIZE, PROTECT, AND PRESERVE THE MAJOR DRAINAGEWAYS ON-SITE. IMPACTS WILL BE LIMITED TO IMPROVEMENTS IN THE AREAS OF DISCHARGES FROM THE PROPOSED DETENTION FACILITIES AND AS IDENTIFIED IN THE MASTER DRAINAGE PLANS FOR THE DRAINAGEWAYS. THE IMPROVEMENTS WILL CONFORM TO THE TOWN OF CASTLE ROCK STORM DRAINAGE DESIGN AND TECHNICAL CRITERIA MANUAL. THESE IMPROVEMENTS WILL BE DESIGNED TO MITIGATE EROSION AND PRESERVE THE NATURAL CHARACTER AND HISTORICAL DRAINAGE PATTERNS TO THE GREATEST EXTENT FEASIBLE.
6. THE INTERCHANGE AT TERRITORIAL ROAD, CRYSTAL VALLEY PARKWAY, AND I-25 (CVI) IS A TOWN, COUNTY AND STATE PROJECT. CHANNEL IMPROVEMENTS FOR THE GAMBLE RIDGE MAJOR DRAINAGEWAY THROUGH THE SITE WILL BE PART OF THE CVI PROJECT.



CHECKED BY: MB, SW
DRAWN BY: DJ, JR

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

APPLICANT:



WESTSIDE INVESTMENT PARTNERS
4100 E. MISSISSIPPI AVE
SUITE 500
DENVER, CO 80246
303-984-9800

ENGINEER & SURVEYOR:

CORE
CORE CONSULTANTS, INC.
LIVEYOURCORE.COM
CORE CONSULTANTS
3473 S. BROADWAY
ENGLEWOOD, CO 80113
303-730-5960



DAWSON TRAILS
PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE:
PDP-01 07/08/2021
PDP-02 12/03/2021
PDP-03 04/13/2022
PDP-04 05/27/2022
PDP-05 06/09/2022

SHEET TITLE:
WILDLAND
MANAGEMENT
PLAN

SHEET
13 OF 20

WILDLAND/URBAN INTERFACE WILDFIRE VEGETATION MANAGEMENT PLAN:

THIS PROPERTY HAS VARYING DEGREES OF COVERAGE BY MULTIPLE VEGETATIVE TYPES, THUSLY FIRE MITIGATION SHALL BE APPROPRIATELY CONSIDERED AS DEVELOPMENT MOVES FORWARD. WILDFIRE MITIGATION IS THE IMPLEMENTATION OF VARIOUS MEASURES DESIGNED TO MINIMIZE THE DESTRUCTIVE EFFECTS FROM A WILDFIRE. AT THE TIME OF SITE DEVELOPMENT PLAN, THE APPLICANT SHALL WORK WITH THE TOWN OF CASTLE ROCK FIRE DEPARTMENT TO CREATE A FINAL AND IMPLEMENTABLE URBAN/WILDLAND INTERFACE AREA VEGETATION MANAGEMENT PLAN. BELOW ARE SUGGESTED PRACTICES THAT DEVELOPERS, BUILDERS AND HOMEOWNERS CAN IMPLEMENT TO HELP MITIGATE FIRE RISK FOR RESIDENCES.

A. WITHIN 30 FEET OF A STRUCTURE (BUILDING ENVELOPE AND IMMEDIATE AREA)

1. CREATE A "DEFENSIBLE SPACE" TO REDUCE THE LIKELIHOOD OF A DAMAGING WILDFIRE IN THE IMMEDIATE VICINITY OF THE HOME. DEFENSIBLE SPACE IS THE AREA WHERE VEGETATION HAS BEEN DESIGNED, INSTALLED AND MAINTAINED TO REDUCE THE POSSIBILITY OF FIRE SPREADING BETWEEN THE LANDSCAPE AND THE BUILDING.
2. IF NATIVE VEGETATION HAS BEEN SUCCESSFULLY RETAINED IN THIS AREA, PRUNE TREE CANOPIES FROM THE GROUND UP TO A MINIMUM HEIGHT OF 10 FEET. REMOVE ANY SMALL OR SUPPRESSED STEMS IN THE UNDER STORY OF DOMINANT TREES. DO NOT REMOVE MORE THAN 1/3RD OF LIVE BRANCHES FROM CONIFERS.
3. WHEN PRESENT, THIN ANY SHRUBS, PARTICULARLY GAMBEL OAK, GROWING BELOW THE CANOPY OF LARGER RETAINED TREES.
4. PRUNE RETAINED CONIFEROUS TREES TO MINIMIZE CROWN OVERLAP; ISOLATE INDIVIDUAL TREES BY PRUNING BACK CANOPIES TO CREATE A SEPARATION BETWEEN TREES.
5. THIN DENSE, CONTINUOUS GAMBEL OAK STANDS AND PRUNE TALLER SPECIMENS UP FROM THE GROUND TO CREATE A MORE OPEN, TREE-LIKE FORM. REMOVE SECTIONS OF LARGE BUT LOW GROWING STANDS TO CREATE DISCONTINUOUS ISLANDS OF VEGETATION.
6. INSTALL A CONTINUOUS NON-IRRIGATED ROCK MULCH BED OR OTHER NON-COMBUSTIBLE MATERIAL FOR A MINIMUM OF 5 FEET AROUND THE PERIMETER OF THE BUILDING.
7. MINIMIZE FOUNDATION-TYPE PLANTINGS, ESPECIALLY ADJACENT TO COMBUSTIBLE SIDING. KEEP ALL SHRUB PLANTINGS A MINIMUM OF 5 FEET FROM THE FOUNDATION. EXCLUDE MORE COMBUSTIBLE SHRUB SPECIES (CONIFEROUS EVERGREENS LIKE JUNIPER, ARBORVITAE, SPRUCE, PINE AND FIR) AND SPACE SHRUBS TO CREATE LOW, NON-CONTINUOUS PLANTINGS NEAR THE BUILDING.
8. PLANT ONLY DECIDUOUS TREE AND SHRUB SPECIES WITHIN 15 FEET OF STRUCTURES. PROVIDE IRRIGATION AS REQUIRED FOR THE SUCCESSFUL ESTABLISHMENT AND LONG-TERM HEALTH OF NEW TREES.
9. PLANT TREES FAR ENOUGH AWAY FROM THE BUILDING THAT, AT MATURITY, TREE CANOPIES WILL NOT OVERHANG THE ROOF.
10. PLANT SOD OR SEED WITH LOW-GROWING GRASS SEED MIXES.
11. PROVIDE IRRIGATION TO TURF AND NATIVE GRASSES WITHIN THIS AREA TO PREVENT SUMMER DORMANCY.
12. MAINTAIN NATIVE GRASS HEIGHT TO A MAXIMUM OF 6 INCHES.
13. PLANT WILDFLOWERS ONLY IF THEY WILL BE IRRIGATED AND WILL BE CUT BACK TO A MAXIMUM HEIGHT OF 8 INCHES AT THE END OF GROWING SEASON (FOLLOWING SEED PRODUCTION).
14. DISPOSE OF ALL SLASH OR PLANT TRIMMINGS OUTSIDE OF THIS ZONE (OFF SITE).

B. BETWEEN 30 FEET AND 150 FEET FROM STRUCTURES AND ROADWAYS (TREE AND SHRUB PRESERVATION AREA) NOTE: THE EXTENT OF THIS ZONE IS AFFECTED BY SLOPE AND IS GREATER WHEN STRUCTURES OR ROADWAYS ARE AT THE TOP OF THE SLOPE AND WHEN SLOPES ARE RELATIVELY STEEP. SLOPE IS LESS CRITICAL WHEN STRUCTURES ARE AT THE BASE OF A SLOPE OR ON LEVEL GROUND.

1. CLEAR SMALL DIAMETER, SNOW BENT, DISEASED, DAMAGED, OR SUPPRESSED STEMS IN THE UNDER STORY OF LARGER PINE TREES.
2. PRUNE TO RAISE THE CANOPY OF LARGE, EXISTING TREES TO 12 FEET ABOVE GROUND LEVEL.

3. THIN SHRUBS GROWING DIRECTLY BENEATH LARGER TREES PER SECTION A, NOTE 2 ABOVE.
4. REMOVE ANNUALLY, DEAD STEMS AND BRANCHES FROM SHRUBS AND TREES.
5. SPACE NEWLY PLANTED CONIFEROUS TREES (>20' TALL AT MATURITY) AT LEAST 20-30 FEET APART TO PROVIDE A MINIMUM OF 10 FEET BETWEEN CROWNS AT MATURITY. IF PINION PINE GROUPINGS (CLUMPS OF TWO OR MORE OF THE SAME SPECIES), AND CONIFEROUS SHRUB GROUPINGS ARE PLANTED, PROVIDE 20-30 FEET BETWEEN GROUPINGS. DECIDUOUS TREES AND SHRUBS ARE NOT SUBJECT TO THIS GUIDANCE WHEN PLANTED AS PART OF AN IRRIGATED AND MAINTAINED LANDSCAPE.
6. PRUNE THE BRANCHES OF SMALLER OR NEWLY PLANTED TREES AS THEY GROW, UP TO A HEIGHT OF 8-12 FEET ABOVE THE GROUND. DO NOT OVER PRUNE THE CROWNS OF SMALLER TREES.
7. TRIM OR MOW NATIVE GRASSES AND WILDFLOWERS MID-SUMMER AND IN THE FALL OR SPRING TO MAXIMUM HEIGHT OF 6 INCHES.
8. DISPOSE OF ALL SLASH OR PLANT TRIMMINGS OFF SITE, BY CHIPPING, OR OTHER MECHANICAL TREATMENTS.

C. BEYOND 150 FEET OF THE STRUCTURE AND OPEN SPACES (PRESERVATION / ENVIRONMENTALLY SENSITIVE AREA)

1. CLEAR SMALLER UNDERSTORY TREES AND SHRUBS PER SECTION B, NOTE 1 ABOVE.
2. UNDERTAKE SELECTIVE THINNING TO IMPROVE HEALTH AND APPEARANCE OF WOODED AND NATIVE BRUSH AREAS.
3. REMOVE SMALLER TREES IN CROWDED STANDS TO INCREASE TREE SPACING.
4. PROVIDE SEPARATION BETWEEN GAMBEL OAK CLUMPS TO BREAK UP HORIZONTAL CONTINUITY OF FUELS AND REDUCE CROWN FIRE POTENTIAL.
5. TRIM OR MOW NATIVE GRASSES ALONG TRAILS TO ALLOW POTENTIAL USE AS PRE-CONSTRUCTED FIRE LINES. THESE MOWN AREAS SHOULD BE 8 FEET WIDE ON BOTH SIDES OF TRAILS. ANY SHRUB CLUMPS RETAINED WITHIN 20 FEET OF TRAILS SHOULD PRUNED TO REDUCE LADDER FUELS AND MAINTAINED IN A MITIGATED CONDITION.
6. RETAIN AN INCREASED NUMBER OF STANDING DEAD TREES PER ACRE FOR WILDLIFE HABITAT UNLESS THEY POSE A THREAT TO UTILITIES OR HUMAN USE.
7. SLASH OR PLANT TRIMMINGS MAY BE DISPOSED OF WITHIN THIS AREA IF TREATED AND REDUCED TO A MAXIMUM DEPTH OF 6 INCHES. IF CHIPPED, MULCH DEPTH SHOULD NOT EXCEED 4 INCHES IN DEPTH.

D. STRUCTURAL WILDFIRE GUIDELINES

1. ALL ROOFS SHALL HAVE CLASS A FIRE RATING.
2. DECKING MATERIAL SHALL HAVE A CLASS B OR HIGHER FIRE RATING.
3. ANY FENCING CONNECTED TO STRUCTURES SHALL USE NON-COMBUSTIBLE MATERIALS WITHIN 5 FEET OF STRUCTURES OR DECKS.
4. ALL VENTS (FOUNDATION, SOFFIT, EAVE, ETC.) SHALL HAVE 1/8TH INCH OR SMALLER OPENING SIZES.
5. GUTTERS SHALL BE NON-COMBUSTIBLE OR HAVE CLASS A FIRE RATING.

E. MAINTENANCE OF FIRE MITIGATION


1. FIRE MITIGATION ON PRIVATE LOTS IS THE RESPONSIBILITY OF THE PROPERTY OWNER.
2. FIRE MITIGATION UNDERTAKEN BY THE DEVELOPER ON OPEN SPACES OR COMMON AREAS SHALL BE MAINTAINED BY THE HOMEOWNERS ASSOCIATION (HOA) OR ALTERNATIVELY BY A SPECIAL DISTRICT (SD), AS MAY BE DETERMINED AT THE TIME OF CONVEYANCE.
3. PLANTED VEGETATION ALONG ALL THOROUGHFARES SHALL BE MAINTAINED TO MANAGE RISK OF CROWN FIRE OR FLAME INTRUSION (IMPINGEMENT) INTO THE PUBLIC RIGHT-OF-WAY.
4. THE HOA OR SD (IF APPLICABLE) SHALL ESTABLISH PROCEDURES FOR RESIDENTS TO IMPLEMENT OR MAINTAIN WILDFIRE MITIGATION MEASURES PER C.R.S 38-33.3-106.5 (A.K.A. SB-100, HOMEOWNER BILL OF RIGHTS).

GENERAL NOTES:

1. A WILDLAND/URBAN INTERFACE WILDFIRE VEGETATION MANAGEMENT PLAN SHALL BE COMPLETED AND SUBMITTED TO THE TOWN OF CASTLE ROCK WITH EACH SITE DEVELOPMENT PLAN, OR SITE DEVELOPMENT PLAN AMENDMENT.
2. MITIGATION REQUIREMENTS SHALL BE COMPLETED AS ESTABLISHED IN THE DEVELOPMENT AGREEMENT.

Unofficial Copy

CHECKED BY: MB, SW
DRAWN BY: DJ, JR



DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

APPLICANT:



WESTSIDE INVESTMENT PARTNERS
4100 E. MISSISSIPPI AVE SUITE 500
DENVER, CO 80246
303-984-9800

ENGINEER & SURVEYOR:

CORE CONSULTANTS INC
CORE CONSULTANTS
3473 S. BROADWAY
ENGLEWOOD, CO 80113
303-730-5960



DAWSON TRAILS
PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

PD ZONING REGULATIONS

SECTION 1 | PURPOSE

The purpose of the Dawson Trails Planned Development Plan (PDP) and Zoning Regulations contained herein is to establish standards for the development and improvement of the property. The standards contained in these Zoning Regulations are intended to carry out the goals of this planned community.

SECTION 2 | GENERAL PROVISIONS

- Adoption**
The Zoning Regulation and the Dawson Trails Planned Development Plan have been adopted by the Town Council by Ordinance No. 2022-017, on the 6th day of September 2022 and have been incorporated therein; pursuant to Section 17.32 of Title 17 Zoning of the Town of Castle Rock Municipal Code, after appropriate public notice and hearings.
- Applicability**
The Dawson Trails Planned Development Plan and Zoning Regulations shall run with the land and bind owners of record and successors in interest to the property.
- Maximum Level of Development**
The total number of dwelling or total commercial, industrial, or other non-residential square footage within the established planning areas are the maximum allowed for platting and development. The maximum number of dwelling units approved for development within the Dawson Trails Planned Development (PD) is 5,850. The maximum non-residential square footage approved for development in the Dawson Trails PD is 3,200,000.
- Relationship to Town of Castle Rock Regulations**
All Town ordinances and regulation, as the same are amended from time to time, shall apply to, and be enforceable in this Dawson Trails PD. All references herein to the Town technical criteria (Criteria) shall mean in effect at the time of the approval of the Dawson Trails Planned Development Plan and Zoning Regulations, and as the Code and Criteria are amended. Accordingly, such Town ordinances and regulations shall govern and control over any conflicting provisions in the PD Zoning Regulations, unless such conflicting provision is vested as an express development right under the applicable Development Agreement.

The standard zoning requirements of the Town zoning ordinance, including off-street parking, landscaping, site development, accessory, and temporary uses, use by special review and variance processes, unless expressly varied in these zoning regulations, shall apply to the Dawson Trails PD. The PD Zoning Regulations shall not preclude the application of Town ordinances, including revisions thereto, which are of general application throughout the Town, unless such application would conflict with an express vested property right (see Chapter 17.08, CRMC).
- Development Agreement**
In addition to these regulations, certain provision of the development of the Dawson Trails PD are controlled by an agreement between the Town of Castle Rock and the Property Owners. This agreement provides for a vesting of the property rights set forth in the Dawson Trails Planned Development Plan and establishes a Water Bank for Dawson Trails. This agreement, entitled the Dawson Trails Development Agreement, between Dawson Trails I LLC and Dawson Trails II LLC, and the Town of Castle Rock (the "Development Agreement"), was adopted by the Town of Castle Rock on the 6th day of September 2022, by Resolution No. 2022-018. In the event of a conflict between the terms of these PD Zoning Regulations and the Development Agreement, the Development Agreement shall control.

SECTION 3 | GENERAL PROJECT DESCRIPTION

- Overall Development Plan**
The Dawson Trails PD consists of approximately 2,063.7 acres with zoning that allows a maximum of 5,850 residential dwelling units as well as provisions for a wide range of commercial, office, industrial uses. A maximum of 3.2 million square feet of non-residential uses is permitted in Dawson Trails PD. This development plan transitions from lower density residential planning areas located in the western portions of the PD to higher density mixed-use areas located in the eastern portions of the PD.

The location of the PD property is within a designated "gateway" to Castle Rock, being situated at the southern-most boundary of the Town, west of Interstate 25 (I-25). The general character of the Dawson Trails neighborhood is shaped by an interconnected network of open space, trails, and parks. Public land dedication will be used for local and regional public facilities which may include neighborhood and regional parks, schools, and other public facilities. Roads and planning areas are planned and located to minimize impacts to existing topography and mature vegetation with preservation of many topographic high points and other natural features being incorporated into the overall design.

This development plan provides approximately 533 acres of interconnected open space which accommodates wildlife movement and habitat and includes a diversity of topography and existing foliage. All development within Dawson Trails PD is subject to and must comply with the Migratory Bird Treaty Act. No federal or state protected species were found inhabiting the property.

3.2 Character Areas and Planning Areas

- Intent**
The Dawson Trails PDP is organized into three (3) Character Areas, according to similarities in land use and development characteristics of the Planning Areas. The West Character Area generally consists of low density single-family detached residential uses on the west and north sides of the 'ridge', as well as significant interconnected open space corridors and areas. The Central Character Area contains a wide range of residential housing types and includes opportunities for supporting neighborhood commercial uses, and key open space corridors and parks on the east side of the ridge while transitioning to the flatter terrain. The East Character Area has a general character of being a commerce, employment, and mixed-use areas with a broad range of land uses, including higher density residential uses.
- West Character Area**
The West Character Area (West) is comprised of single-family detached residences and neighborhood support amenities such as a clubhouse, community center, or other similar uses. This Character Area generally serves as the transition from the Central Character Area to the existing single-family detached residential lots located in Douglas County. The West consists of the lowest residential densities in Dawson Trails. This area also preserves large areas of key open space and natural corridors with mature vegetation, and establishes a significant natural transition buffer where adjacent County residential properties. Only single-family detached residential homes are permitted in the West. Commercial land uses are not permitted. The West Character Area is comprised of three (3) Planning Areas totaling a maximum of 1,183 dwelling units.
 - Planning Area A is the westernmost development area in the Dawson Trails PD, separated from the adjacent County residential properties by a large open space buffer area. The western edges of this Planning Area conform to the existing topography and to preserve much of the physical characteristics and mature vegetation. Development in this Planning Area will consist of lower density single-family detached residential uses. A Transition Zone, with additional development standards area required, exists where Planning Area boundaries are adjacent to existing Douglas County residential development, a Transition Zone exists where additional development standards are required (See Section 6.10).
 - Planning Areas B-1 and B-2 establish the northernmost and southeastern portions of the West Character Area. These Planning Areas are closest to the existing Twin Oaks single-family detached residential subdivision (north) and the existing Keene Ranch single-family detached residential subdivision (south). As with Planning Area A, development will be characterized by single-family detached residential. The edges of these Planning Areas are established in this PD Plan to be sensitive to existing topography and other physical characteristics of the property. Transition Zone development standards, as defined within the PD, apply to some edges of these Planning Areas (See Section 6.10).
- Central Character Area**
The Central Character Area (Central) acts as a transition area between the lower density West Character Area and the higher density/intensity East Character Area. This Character Area allows higher density residential uses as well as non-residential uses, primarily in the eastern portion and away from, the West Character Area and closer to the East Character Area and Dawson Trails Boulevard. All residential development in the Central Area include a wide range of housing types including single-family attached and detached as well as multi-family. This Character Area will include a well-connected series of neighborhood pods, potential neighborhood commercial, and both locally and regionally oriented land uses, parks, and other open space and amenities. The Central Character Area is comprised of three (3) Planning Areas totaling a maximum of 3,327 dwelling units and limited density transfers allowed.
 - Planning Area C-1 is primarily a residential land use area, with some permitted neighborhood commercial and other low intensity residential uses supporting as a use by special review, anticipated to occur along collector roads and around intersections. Based on land use types permitted and associated development standards, the intensity of uses and density of residential development will generally decrease from east to west within the Planning Area.
 - Planning Area C-2 is similar to Planning Area C-1 but permits slightly higher residential densities. The southern portion of this Planning Area generally permits lower levels of density, due to the proximity of the Town/County boundary.
 - Planning Area D is an area that permits a wide range of residential uses, mixed-uses, and a wide range of commercial and other non-residential uses. Both horizontal and vertically mixed land uses are appropriate and permitted. The most intense land uses and residential densities will likely occur along the major north-south arterial (Dawson Trails Boulevard) located along the eastern boundary of the Planning Area.
- East Character Area**
The East Character Area (East) is influenced by its proximity to and visibility from Interstate 25, the Crystal Valley Interchange, and Dawson Trails Boulevard. Accordingly, the type of development occurring here will tend to be higher density, mixed use (both vertical and horizontal mixed-use) as well as a wide range of non-residential uses. Residential neighborhood and commercial site design in the East will strive to create pedestrian friendly connections and provide access via a variety of modes of transportation.

Residential development in the East is anticipated to include denser and more compact housing types such as condominiums, townhouses, apartments, and high density clustered single-family detached and attached units. A maximum of 1,340 dwelling units and limited transfer of units between planning areas is allowed.

Office buildings, retail stores, restaurants, service commercial, light industrial and other similar uses will provide employment, shopping, and local and regional destinations in this Character Area. Large format retailers, also known as "big-box" stores are appropriate in Planning Areas E-2, F-1, F-2, and F-3, along with other uses.

The East Character Area is comprised of seven (7) Planning Areas, and development standards included in this PD create a logical transition to the adjacent Central Character Area. Land uses allowed among the Planning Areas are similar, with the exception of Planning Areas G-1 and G-2, which allows light and flex industrial uses and prohibits residential uses.

A. Planning Area E-1 is a mixed-use parcel, located within the I-25/Crystal Valley Interchange area and is adjacent to the Twin Oaks single-family detached residential subdivision located in Douglas County, to the west. The proximity to adjacent commercial or mixed-use Planning Areas allows for similar development opportunities, but at a lower intensity. Development standards, which establish appropriate buffer areas and lower profile buildings, serve to guide development and site planning of this Planning Area. The western boundary of his Planning Area has an existing buffer agreement, which is filed with the Douglas County Clerk and Recorder, Reception Number 8625692 and labeled on the PDP. This agreement requires a 100-foot-wide buffer in this area.

B. Planning Area E-2 in the PDP is a mixed-use parcel that is more centrally positioned in the Dawson Trails neighborhood. This Planning Area is categorized as a Pedestrian Oriented Area and has the potential to include a pedestrian-oriented cluster of uses and will provide opportunities to shop, work, live, and recreate. Pedestrian Oriented Areas beyond the one described in Planning Area E-2 may also be developed in other areas of Dawson Trails. The Pedestrian Oriented Area will include the following:

- Include either a publicly accessible and activated square/green/plaza OR a publicly accessible and activated "main street" at least one (1) block in length with buildings fronting with entries / pedestrian access oriented onto the space or street and incorporating typical urban design elements such as on-street parking (parallel or head-in), street trees for shade, decorative/enhanced paving, lighting/street furnishings, and other elements to help establish and define the public realm of the place/street.
- Uses include all non-residential and residential uses permitted in Planning Area E-2.
- Enhanced elements to support pedestrian connectivity may include crosswalks, outdoor dining, pedestrian-scaled lighting (poles and/or bollards), dedicated bicycle parking in key locations, or similar improvements.
- Development patterns in a Pedestrian Oriented Area in this portion of Planning Area E-2 should prioritize pedestrians by placing entrances at sidewalks, providing landscaping along main routes, and allowing on-street parking to help encourage slower vehicular traffic. As a primary design principal for this gathering place/mains street is to be pedestrian-oriented, the transportation network in these areas should also provide safe crossings for pedestrians and cyclists and may include mid-block crossings where necessary. Additional guidelines and standards can be found in the Dawson Trails Architectural Guidelines.

- Planning Areas F-1, F-2 and F-3 are proximate to the proposed I-25 interchange and provide the widest range of land uses within Dawson Trails. These Planning Areas are likely to contain more auto-oriented and destination type land uses while providing safe connections for cyclists and pedestrians.
- Planning Areas G-1 and G-2 provide for a similar range of land uses as in the other portions of the East Character Area but does not permit residential land uses.

SECTION 4 | DEFINITIONS

In addition to the standard definitions found in the Town of Castle Rock Zoning Ordinance (Title 17), as amended, the following definitions of terms shall apply to this PD.

Accessory Structure means a detached subordinate building, the use of which is customarily incidental to that of the main building or to the main use of the land and which is located on the same lot with the main building or use.

Adult Day Care Facility means a facility that provides services under an adult day-care program on a daily or regular basis but not overnight to four or more elderly or handicapped persons who are not related by blood, marriage, or adoption to the owner of the facility.

Attached or Detached Private Garages means an accessory building or portion of a dwelling which is fully enclosed and used for the sheltering of permitted vehicles and storage of household equipment incidental to the residential occupancy. This definition shall not include a carport or other open shelter.

Driveway Easements means an easement placed upon a common or shared driveway, benefiting the two or more property owners which utilize such drive for access.

Funeral Home means (a) an establishment that holds, cares for, or prepares human remains prior to final disposition, including a crematory or embalming room; (b) an establishment that holds itself out to the general public as providing funeral goods and services; (c) an establishment that provides funeral or memorial services to the public for compensation.

Industrial, Flex means industrial buildings which allow for a wide range of office and warehouse uses. Flex buildings usually contain a larger percentage of office space than a typical distribution warehouse building and can be easily adapted to fit the spatial needs of the tenant.

Large Animal Clinic and Hospital means a clinic and/or hospital that provides medical care for large animals, including but not limited to equine, ruminant, and other livestock. This may include services such as herd checks, administering medicines, checkups, and surgeries.

Master Developer means the Master Developer for Dawson Trails PDP and/or its assigns of all or certain phases of the project that will be the entity responsible for providing the spine infrastructure, including roads, sewer, and water for the project. The Master Developer shall form or amend the Service Plan for any required quasi-governmental metropolitan district, the property owner's association, and design review committees

Non-Residential means development containing commercial, retail, industrial, and institutional uses. Residential and residential amenities such as pools, clubhouses, public schools (K-12) and public facilities are not considered to be non-residential uses.

Office, Flex means buildings that are designed and marketed as suitable for offices but with space available that is able to accommodate bulk storage, showroom manufacturing, assembly, retail or similar operations. Generally, flex space has storefront type windows in the office area of the space.

Residential:

Clustered Dwelling means single family or multi-family, attached, or detached, dwelling units which are grouped more tightly together on one lot as a means to preserve nearby open space that would otherwise be distributed amongst privately owned lots.

Condominium means a type of multi-family Dwelling. The unit is individually owned, each owner receives a recordable deed to the individual unit purchased, including the right to sell, mortgage, etc., that unit and sharing in joint ownership of any common grounds, passageways, etc.

Dwelling or Dwelling Unit means any building or portion thereof which is used as the private residence or sleeping place of one or more human beings, but not including hotels, motels, tourist courts, clubs, hospitals, or similar uses.

Green Court means a group of single family, attached or detached, dwelling units which are accessed on the rear by either a private drive or an alley. Green Court dwellings may either be on individual lots or a commonly owned lot. Typically included is a common, shared, open space area which dwellings front upon, and which is maintained by either a private homeowner's association or other similar entity.

Motor Court means a group of single family, attached or detached, dwelling units which are accessed by a common, shared driveway.

Multifamily means buildings which contain apartments or condominiums, which contain three or more dwelling units, which are accessed from interior elevators or hallways, or from individual exterior entrances, and are separated by interior walls and/or floors. Multifamily does not include boarding houses, dormitories, fraternities, sororities, bed and breakfast establishments, single-family attached or detached dwellings, or hotels and motels, adult day care, memory care, or other similar institutional uses which provide support staff.

Patio Dwelling Unit means a dwelling that shares at least one wall with another home. Frequently built on small lots with patios in place of a traditional back yard.

Single Family, Attached or Detached, means a building designed exclusively for occupancy by one family and includes (but is not limited to) townhomes, green courts, motor courts and other similar residential configurations. Apartments and condominiums are considered Multifamily.

Townhome means a type of Single Family Attached Dwelling in which each single Dwelling goes from ground to roof and is separated from other Townhome Dwelling Units by a common wall while having individual outside access. Townhome Dwelling Units may have no side yards, or front and rear yards and may include two, three, four, or more dwellings.

Zero Lot Line means an alternative type of Single Family Detached Dwelling Unit which is situated on a lot so that one or more sides rest directly on the boundary line of the lot.

Short Term Rentals means any dwelling or portion thereof that is available for use or is used for accommodations or lodging of guests, paying a fee or compensation for a period of less than thirty (30) consecutive days.

Storage, Indoor (Allowed in Planning Areas F-1, F-2, F-3, G-1, G-2 only) means the keeping in an enclosed area of any components, products, material, merchandise, equipment, vehicles, RVs, boats, and trailers.

Storage, Outdoor (Allowed in Planning Areas F-1, F-2, F-3, G-1, G-2 only) means the keeping in an unenclosed area of any components, products, material, merchandise, equipment, vehicles, RVs, boats, and trailers. Fleet/company vehicles, equipment attached to fleet/company vehicles, short-term customer and staff parking, and approved trash enclosures shall not be considered outdoor storage.

Transition Zone is the 150' wide area identified on the PD Plan in Planning Areas A, B-1, and B-2 that is generally located towards the PDP property boundary and indicated with the cross-hatched pattern in those Planning Areas. The Transition Zone is established with this PDP to provide standards to control a range of land use development standards within this specific portion of the Planning Area, including minimum lot size, lighting, building colors, landscaping improvements, and fencing.

DATE:
PDP-01 07/08/2021
PDP-02 12/03/2021
PDP-03 04/13/2022
PDP-04 05/27/2022
PDP-05 06/09/2022

SHEET TITLE:
PD ZONING REGULATIONS

SHEET
14 OF 20

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

APPLICANT:



WESTSIDE INVESTMENT PARTNERS
4100 E. MISSISSIPPI AVE
SUITE 500
DENVER, CO 80246
303-984-9800

ENGINEER & SURVEYOR:

CORE
CORE CONSULTANTS, INC.
INVESTYOURCORE.COM
CORE CONSULTANTS
3473 S. BROADWAY
ENGLEWOOD, CO 80113
303-730-5960



DAWSON TRAILS
PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

PD ZONING REGULATIONS

SECTION 5 | OVERALL PROJECT STANDARDS

5.1 Planning Area Boundaries

The conceptual boundaries of all Planning Areas are shown on the Dawson Trails PD Plan. Where a Planning Area abuts an internal local street or drive or a collector street, the boundary shall be the centerline of the street, where applicable. Where a Planning Area abuts an arterial street, the boundary shall be the right-of-way of that street as indicated on the PD Plan. A Planning Area may be partially subdivided and/or subdivided into multiple filings and phases at the Site Development Plan / Plat stage of the development review process.

5.2 Amendments to the PD Plan and PD Zoning Regulations

- The maximum number of dwelling units approved for development in Dawson Trails is 5,850, including a maximum number of 2,400 Multifamily dwelling units. The maximum amount of non-residential use square footage is 3,200,000 square feet, subject to subsection 3 below.
- Residential
 - Dwelling units are subject to maximum transfers in each Planning Area as noted below in Table 5.2.1. In any case, the maximum number of dwelling units approved in this PD shall not exceed 5,850.

Table 5.2.1 - Maximum Allowed Transfer of Dwelling Units			
Character Area	Planning Area	Percentage Transfer Out	Percentage Transfer In
West	A	20%	0
	B-1	20%	0
	B-2	20%	0
Central	C-1	20%	15%
	C-2	20%	20%
	D	20%	20%
East	E-1	No Residential Allowed	No Residential Allowed
	E-2	20%	20%
	F-1	20%	20%
	F-2	20%	20%
	F-3	20%	20%
	G-1	No Residential Allowed	No Residential Allowed
	G-2	No Residential Allowed	No Residential Allowed

- The actual number of dwelling units approved will be determined and calculated at the Site Development Plan / Plat stage of the development review process. A Project Tracking Sheet will be used to document the series of plats at Dawson Trails over the life cycle of the project.
- The maximum number of allowed multifamily dwelling units is capped at 2,400, however, this may be increased by up to 15% as an Administrative Amendment to this PD. In any case, the maximum number of dwelling units approved in this PD shall not exceed 5,850.

- Non-residential
 - The maximum 3,200,000 square feet of non-residential use may be increased by up to 15% as an Administrative Amendment to this PD.
 - All non-residential uses in the West, Central, and East Character Areas that are residential use-supporting in nature, including but not limited to various types of amenities, clubhouses, and similar uses, shall not be counted towards the maximum allocation of non-residential use 3,200,000 square feet.
 - Assisted living facilities, adult day care, memory care, nursing homes, and continuum of care uses and other institutional use types that provide staffed support services do not count towards the 5,850 maximum allowed dwelling units in this PD.

5.3 Non-Residential Use Acreage Minimums

- Minimum acreages of non-residential uses are required and shall be located in F-1, F-2, F-3, G-1, and G-2 as follows:
 - Planning Areas F-1 and F-2: 20-acres
 - Planning Area F-3: 25-acres
 - Planning Area G-1: 62.6 acres
 - Planning Area G-2: 4.3 acres

5.4 Storage Use Acreage Maximums

- A total cumulative maximum of 30 acres of storage uses are permitted within Planning Areas F-1, F-2, F-3, G-1, and G-2.
 - Outdoor storage shall not exceed 15 acres.
 - Indoor and outdoor storage may both be included on the same site.

5.5 Automobile / Vehicle / RV / Motorcycle / All-Terrain Vehicle / Equipment Sales and Leasing Use Acreage Maximums

- A total cumulative maximum of 20 acres of Automobile / Vehicle / RV / Boat / Motorcycle / All-Terrain Vehicle / Equipment Sales and Leasing uses are permitted within Planning Areas F-1, F-2, F-3, G-1, and G-2.

5.6 Road Alignments

The PDP depicts conceptual locations of roadways. Recognizing that the final road alignments are subject to detailed engineering studies, realignments of roads/streets are expected and can be accomplished by the applicant/developer through the Site Development Plan / Plat stage of the development process without any amendment to these regulations or to the PDP itself. More significant road realignments, as determined by the Town of Castle Rock Development Services Director, shall follow the PDP Amendment procedure as provided in the Town of Castle Rock Municipal Code.

5.7 Trails and Trail Alignments

The PDP depicts general locations of trails. Recognizing that the final trail alignments are subject to detailed engineering studies and overall pedestrian connectivity adjustments, realignments and changes are expected, and can be accomplished by the applicant/developer through Site Development Plan / Plat stage of the development process without any amendment to these regulations or to the Plan Development Plan itself. In some cases, sidewalks planned along roadways and streets may be used to connect trail networks. Refer to the Dawson Trails PD Plan.

5.8 Open Space

Open space may be public or private. Public open space, PL-1, or PL-2 will be dedicated to the Town. Private open space, OSP, will be owned by a private entity, a metropolitan district or homeowners' association. An additional approximate 215 acres to be designated as either public or private open space at time of SPD / Plat.

5.9 Residential Parking

- Shared parking is allowed per Section 17.54 of the Municipal Code.
- Reduced parking standards may be requested per Section 17.54 of the Municipal Code.
- Table 5.8.1, below, identifies parking standards within the Dawson Trails PD. Parking shall follow the table below unless the applicant designates that the Town Code requirements are to be used in lieu thereof at the time of SDP.

Table 5.8.1	
Single-Family Detached Dwelling	2 Spaces per Dwelling Unit
Single-Family Attached Dwelling	1 space per 1 bedroom; 1.5 spaces per 2 bedroom; 2 spaces per 3+ bedroom; +15% of total required spaces for visitor parking
Multiple SFA & SFD on One Lot	1 space per 1 bedroom; 1.5 spaces per 2 bedroom; 2 spaces per 3+ bedroom; +15% of total required spaces for visitor parking
Clustered Single-Family Residential Dwelling	2 Spaces per Unit
Multi-Family Residential Dwelling (Multifamily and dwellings in multiple buildings on a single lot)	1 space per 1 bedroom; 1.5 spaces per 2 bedroom; 2 spaces per 3+ bedroom; +20% of total required spaces for visitor parking

Notes:
1. Off-street parking includes garage spaces (including tandem configurations), surface parking, other covered spaces, uncovered spaces, spaces accessed from private drives, and driveways.
2. On-street parking that is directly adjacent to the lot frontage of a public or private street may be counted as part of the parking requirements in Planning Area E-2, in conjunction with review of a SDP in Section 3, 4.B. of this PD.

5.10 Residential / Non-residential Use Adjacency Standards

- Planning Area E-1 shall have a minimum 100-foot open space buffer, measured from the western Dawson Trails property boundary. No structures which require a building permit are permitted within this open space buffer.
- The northern portion of Planning Area E-2, adjacent to the proposed Major Collector, shall have a minimum 50-foot open space buffer, measured from the east boundary of the Right-of-Way for the Major Collector. No structures which require a building permit are permitted within this open space buffer.
- The buffers noted 1. and 2. above are inclusive of the buffer described in the existing buffer agreement, which is filed with the Douglas County Clerk and Recorder, Reception Number 8625692.
- The Interface requirements of Chapters 17.50 and 17.51 of the Town of Castle Rock Municipal Code shall apply in the Dawson Trails PD only to development adjacent to the buffers described in 1 and 2 above, except that no additional prescriptive buffer is required.

5.11 Landscaping

All landscaping shall be in conformance with Town of Castle Rock Landscape and Irrigation Criteria Manual and the Dawson Trails Water Efficiency Plan, as amended.

5.12 Grading / Drainage

The grading/drainage of an individual lot or open space tract shall not vary from the approved Plat and Construction Documents - Grading, as applicable, without written approval of the Owner, certification of the Owner's Engineer(s), and Town review and approval. Any unauthorized work performed will be required to be returned to the specified grade by the individual(s) or organization(s) that authorized the change without proper approval.

5.13 Town-Owned Property

No easements, grading, or other disturbance associated with development is permitted on PL-1, PL-2, or other Town owned property without written approval from the Town of Castle Rock.

5.14 Compliance with Skyline/Ridgeline Protection District

All areas within the Skyline/Ridgeline protection area as shown on the Dawson Trails PD Plan shall be subject to Chapter 17.48 of the Castle Rock Municipal Code, as amended.

5.15 Wildland Fire Mitigation

The natural topography and existing vegetation of the development site and adjacent open space suggests that the design of the homes and the neighborhood incorporate methods to limit the potential for the spread of wildland fires. National Fire Protection Association measures approved by the Town of Castle Rock Fire Department shall be incorporated into each Site Development Plan. An overall Wildfire Vegetation Mitigation Plan is included in the PDP and will be further defined at each stage of development as associated with future Site Development Plans when the appropriate amount of planning and engineering information and detail are known.

5.16 Planning and Design

- Design and construction of lots, structures, roadways, and other improvements shall be sensitive to the existing topography and mature vegetation. The proposed improvements shall achieve a blended landscape (existing conditions combined with engineered conditions) that is congruent with the intended character of the Character Area and/or Planning Area improvements being implemented, as determined feasible.
- Structures in sloping areas shall be designed to generally conform to the slope by means of stepped foundations, retaining walls or similar methods that will seek to minimize grading and site preparation, as determined feasible.
- Grading shall be shaped to compliment the natural landforms, as determined feasible.
- Roads in steeply sloping or heavily vegetated areas shall be designed to minimize the area of disturbance, while recognizing grading impacts will require changes to existing slopes and removal of existing vegetation in many areas where development improvements are to be located. Where practical, clearing of vegetation within the right-of-way shall be feathered to create more natural appearing edges.

SECTION 6 | PERMITTED USES AND DEVELOPMENT STANDARDS

As outlined above in the Character Area descriptions, each Character Area is further organized by Planning Areas. While the Character Areas provide a general guide for similar types of development, each Planning Area provides allowed land uses and dimensional standards.

Refer to Section 6.11 Supplemental Development Standards. Supplemental Development Standard #16 (A through E) includes standards applicable in all Planning Areas. Sections 6.1 through 6.10 establish permitted uses and development standards unique to specific Planning Areas.

6.1 Planning Area A

- Permitted Uses
 - Residential
 - Single Family Detached
 - Detached Private Garage
 - Non-Residential
 - Home Occupations
 - Open Space, Public or Private
 - Private recreational and park uses, clubhouse, country clubs, recreational facilities, including but not limited to: swimming pools, sport courts, and jogging, equestrian riding, hiking and biking trails
 - Public Parks, Playgrounds, and other recreational areas
 - Utilities including but not limited to gas, electric, telecom. This includes structures or facilities commonly associated or required with the installation and operation of utilities
 - Water infrastructure including but not limited to detention/retention areas/ponds, lift stations, and piping, as well as structures typically associated with water infrastructure such as pump houses
 - Uses By Special Review
 - Solar collectors which are not part of the primary structure
 - Public Facilities
 - Development Standards (unless otherwise approved by the Town at the time of SDP or Plat)
 - Transition Zone Minimum Lot Size: Residential lots located within the designated Transition Zone, as identified on the PD Plan, shall be a minimum 7,700 square feet. (See Section 6.10 for additional standards)
- Minimum Lot Size: None
- Primary Structure
- Note: The numbers within parentheses () following each standard indicate additional development standards which may apply. See Section 6.11.*
- Setbacks (3, 4, 9, 13, 14)
 - Minimum Front Setback (1, 5, 8): 15'
 - Minimum Front Setback to Garage Door Face (1, 5, 8): 20'
 - Minimum Rear Setback (6): 20'
 - Minimum Rear Setback, Alley (6, 7): 2'
 - Minimum Side Setback, Interior Lot (6, 7, 12): 5'
 - Minimum Side Street Setback (1, 5, 6, 7, 8): 15'
 - Minimum Building Separation (3): 10'
 - Maximum Building Height (2): 35'

D. Accessory Structure

Note: The numbers within parentheses following each standard indicate additional development standards which may apply. See Section 6.11.

- Setbacks (3, 4, 9, 13, 14)
 - Minimum Front Setback (1, 5, 8): 20'
 - Minimum Rear Setback (6): 5'
 - Minimum Rear Setback, Alley (6, 7): 2'
 - Minimum Side Setback (interior lot) (6, 7, 12): 5'
 - Minimum Side Street Setback (1, 5, 6, 7, 8): 15'
- Minimum Building Separation (3): 10'
- Maximum Building Height (2): 35'

6.2 Planning Areas B-1 and B-2

- Permitted Uses
 - Residential
 - Single Family Detached
 - Detached private garages
 - Non-Residential
 - Open space, public or private
 - Private Recreational and Park uses, clubhouse, country clubs, recreational facilities, including but not limited to: Swimming Pools, Sport Courts, and jogging, equestrian riding, hiking and biking trails
 - Public Parks, playgrounds, and other recreational areas
 - Utilities including but not limited to gas, electric, telecom. This includes structures or facilities commonly associated or required with the installation and operation of utilities.
 - Water infrastructure including but not limited to: detention/retention areas/ponds, lift stations, and piping, as well as structures typically associated with water infrastructure such as pump houses.
 - Uses By Special Review
 - Public Facilities
 - Development Standards (unless otherwise approved by the Town at the time of SDP or Plat)
 - Transition Zone Minimum Lot Size: Residential lots located within the designated Transition Zone, as identified on the PD Plan, shall be 6,600 square feet. (See Section 6.10 for additional standards).
- Primary Structure
- Note: The numbers within parentheses following each standard indicate additional development standards which may apply. See Section 6.11.*
- Minimum Lot Size: None
 - Setbacks (3, 4, 13, 14)
 - Minimum Front Setback (1, 5, 8): 15'
 - Minimum Front Setback to Garage Door Face (1, 5, 8): 20'
 - Minimum Rear Setback (6): 20'
 - Minimum Rear Alley Setback (6, 7): 2'
 - Minimum Side Setback, interior lot (6, 7, 12): 5'
 - Minimum Side Street Setback (1, 5, 6, 7, 8): 15'
 - Minimum Building Separation (3): 10'
 - Maximum Building Height (2): 35'

C. Accessory Structure

Note: The numbers within parentheses () following each standard indicate additional development standards which may apply. See Section 6.11.

- Setbacks (3, 4, 13, 14)
 - Minimum Front Setback (1, 5, 8): 20'
 - Minimum Rear Setback (6): 5'
 - Minimum Rear Alley Setback (6, 7): 2'
 - Minimum Side Setback (interior lot) (6, 7, 12): 5'
 - Minimum Side Street Setback (1, 5, 6, 7, 8): 15'
- Minimum Building Separation (3): 10'
- Maximum Building Height (2): 35'

DATE:

PDP-01 07/08/2021
PDP-02 12/03/2021
PDP-03 04/13/2022
PDP-04 05/27/2022
PDP-05 06/09/2022

SHEET TITLE:

PD ZONING REGULATIONS

SHEET
15 OF 20

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

APPLICANT:



WESTSIDE INVESTMENT PARTNERS
4100 E. MISSISSIPPI AVE
SUITE 500
DENVER, CO 80246
303-984-9800

ENGINEER & SURVEYOR:



CORE CONSULTANTS INC.
CORE CONSULTANTS
3473 S. BROADWAY
ENGLEWOOD, CO 80113
303-730-5960



DAWSON TRAILS
PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE:
PDP-01 07/08/2021
PDP-02 12/03/2021
PDP-03 04/13/2022
PDP-04 05/27/2022
PDP-05 06/09/2022

SHEET TITLE:
PD ZONING REGULATIONS

SHEET
16 OF 20

PD ZONING REGULATIONS

6.3 Planning Areas C-1 and C-2

1. Permitted Uses
 - A. Residential
 1. Single Family Attached or Detached
 2. Clustered Single Family Dwelling Units, including but not limited to Zero Lot Line Dwellings, Patio Dwelling units
 3. Detached private garages
 - B. Non-Residential
 1. Assisted Living, Memory Care, or other similar institutional uses
 2. Nursing Home
 3. Adult Day Care
 4. Day Care Center Facility
 5. Day Care, In Home
 6. Open Space, Public or Private
 7. Public Parks, Playgrounds, and other non-commercial recreational areas
 8. Private Recreational and park uses, clubhouse, country clubs, recreational facilities, including but not limited to clubhouses, swimming pools, sport courts and jogging, equestrian riding, hiking and biking trails
 9. Utilities including but not limited to gas, electric, telecom. This includes structures or facilities commonly associated or required with the installation and operation of utilities.
 10. Water infrastructure including but not limited to detention/retention areas/ponds, lift stations, and piping, as well as structures typically associated with water infrastructure such as pump houses.
2. Uses By Special Review
 - A. Non-Residential
 1. Offices
 2. Gyms / Health Clubs
 3. Clinics
 4. Restaurants, without Drive-Through
 5. Private Clubs
 6. Retail
 7. Personal Services
 8. Commercial Services
 9. Public Facilities
 10. Studio Classes
 11. Places of Worship
 12. Recreation, Outdoor
 13. Solar Collectors which are not part of the primary structure

3. Maximum Building Height for All Uses (2):
 - A. Planning Area C-1: 45'
 - B. Planning Area C-2: 50'

4. Residential Setbacks: (unless otherwise approved by the Town at the time of SDP or Plat)
 - A. Primary Structure

**Note: The numbers within parentheses following each standard indicate additional development standards which may apply. See Section 6.11.*

 1. Minimum Lot Size: None
 2. Setbacks (3, 4, 13, 14)
 - a. Minimum Front Setback (1, 5, 8): 15'
 - b. Minimum Front Setback to Garage Door Face (1, 5, 8): 20'
 - c. Minimum Rear Setback (6): 10'
 - d. Minimum Rear Alley Setback (6, 7): 2'
 - e. Minimum Side Setback, interior lot (6, 7, 12): 5'
 - f. Minimum Side Street Setback (1, 5, 6, 7, 8): 10'
 3. Minimum Building Separation (3): 10'
 - B. Accessory Structure

**Note: The numbers within parentheses following each standard indicate additional development standards which may apply. See Section 6.11.*

 1. Setbacks (3, 4, 13, 14)
 - a. Minimum Front Setback (1, 5, 8): 20'
 - b. Minimum Rear Setback (6): 5'
 - c. Minimum Rear Alley Setback (6, 7): 2'
 - d. Minimum Side Setback (interior lot) (6, 7, 12): 5'
 - e. Minimum Side Street Setback (1, 5, 6, 7, 8): 15'
 2. Minimum Building Separation (3): 10'

5. Non-Residential Setbacks: To be established at the time of Site Development Plan / Plat application, review, and approval.

6.4 Planning Area D

1. Permitted Uses
 - A. Residential
 1. Single Family Detached
 2. Single Family Attached (Townhome, Duplex, Triplex, Fourplex, Zero Lot Line Dwellings, Patio Dwellings, Motor Courts, Green Courts, Clustered Dwellings)
 3. Multifamily (Apartments, Condominiums, or other similar Multifamily Configurations)

4. Multifamily
5. Clustered Single Family Dwelling Units
6. Condominium
7. Green Court
8. Motor Court
9. Patio Dwelling
10. Townhome
11. Zero Lot Line Dwelling
12. Clustered Single Family Dwelling Units on a single lot as a product for lease
13. Detached private garages

B. Non-Residential

1. Adult Day Care Facility
2. Assisted Living / Memory Care
3. ATM / Kiosk
4. Bed and Breakfast
5. Clinic
6. College / University / Vo-tech
7. Day Care Center Facility
8. Drive-Through Facility
9. Educational Facility
10. Funeral Home
11. Gym / Health Club
12. Hospital
13. Hotel / Motel
14. Nursing Home
15. Office (including Flex Office)
16. Parking Facility (stand-alone lot / structure)
17. Place of Worship
18. Private Club
19. Public Facilities
20. Recreation, Indoor or Outdoor
21. Retail
22. Restaurant
23. Studio Classes
24. Utilities, Public
25. Veterinary Clinic
26. Open Space, Public or Private
27. Public Parks, Playgrounds, and other non-commercial recreational areas
28. Private Recreational and park uses, clubhouse, country clubs, recreational facilities, including but not limited to swimming pools, sport courts, and jogging, riding, equestrian riding and biking trails
29. Utilities including but not limited to gas, electric, telecom. This includes structures or facilities commonly associated or required with the installation and operation of utilities.
30. Water infrastructure including but not limited to detention/retention areas/ponds, lift stations, and piping, as well as structures typically associated with water infrastructure such as pump houses.

2. Uses By Special Review
 - A. Solar collectors which are not part of the primary structure
 - B. Kennel / Doggy Daycare

3. Maximum Building Height for All Uses (2): 60'

4. Residential Setbacks: (unless otherwise approved by the Town at the time of SDP or Plat)

**Note: The numbers within parentheses following each standard indicate additional development standards which may apply. See Section 6.11.*

A. Primary Structure

1. Minimum Lot Size: None
2. Setbacks (3, 4, 10, 13, 14)
 - a. Minimum Front Setback (1, 5, 8): 15'
 - b. Minimum Front Setback to Garage Door Face (1, 5, 8): 20'
 - c. Minimum Rear Setback (6): 20'
 - d. Minimum Rear Alley Setback (6, 7): 2'
 - e. Minimum Side Setback, interior lot (6, 7, 12): 5'
 - f. Minimum Side Street Setback (1, 5, 6, 7, 8): 15'
3. Minimum Building Separation (3): 10'

B. Accessory Structure

1. Setbacks (3, 4, 10, 13, 14)
 - a. Minimum Front Setback (1, 5, 8): 20'
 - b. Minimum Rear Setback (6): 5'
 - c. Minimum Rear Alley Setback (6, 7): 2'
 - d. Minimum Side Setback (interior lot) (6, 7, 12): 5'
 - e. Minimum Side Street Setback (1, 5, 6, 7, 8): 15'
2. Minimum Building Separation (3): 10'

**Note: The numbers within parentheses (above) following each standard indicate additional development standards which may apply. See Section 6.11.*

5. Non-Residential Setbacks: To be established at the time of Site Development Plan / Plat application, review, and approval.

6.5 Planning Areas E-1 and E-2

1. Permitted Uses
 - A. Residential
 1. Single Family Detached (E-2 only)
 2. Single Family Attached (Townhome, Duplex, Triplex, Fourplex, Zero Lot Line Dwellings, Patio Dwellings, Motor Courts, Green Courts, Clustered Dwellings) (E-2 only)
 3. Mixed-Use (horizontal or vertical) (E-2 only)
 4. Multifamily (E-2 only)
 5. Clustered Single Family Dwelling Units, including but not limited to Zero Lot Line Dwelling Units, Patio Dwelling Units, two, three, and four, and other Multi-Family Dwelling Units (E-2 only)
 6. Clustered Single Family Dwelling Units on a single lot as a product for lease (E-2 only)
 7. Detached private garages (E-2 only)

B. Non-Residential

1. Assisted Living, Memory Care, or other similar institutional uses
2. ATM / Kiosk
3. Bed and Breakfast
4. Clinic
5. Day Care Center Facility
6. Drive Through Facility
7. Hospital
8. Nursing Home
9. Office (including Flex Office)
10. Place of Worship
11. Private Club
12. Public Facilities
13. Retail
14. Restaurant
15. Services, Commercial
16. Services, Personal
17. Services, Repair
18. Veterinary Clinic (to include 24/7 emergency care)
19. Open Space, Public or Private
20. Private Recreational and park uses, clubhouse, country clubs, recreational facilities, including but not limited to clubhouses, swimming pools, sport courts and jogging, riding, hiking and biking trails
21. Public Parks, Playgrounds, and other non-commercial recreational areas
22. Utilities including but not limited to gas, electric, telecom. This includes structures or facilities commonly associated or required with the installation and operation of utilities.
23. Water infrastructure including but not limited to detention/retention areas/ponds, lift stations, and piping, as well as structures typically associated with water infrastructure such as pump houses

2. Uses By Special Review
 - A. Solar collectors which are not part of the primary structure
 - B. Public Facilities

3. Maximum Building Height for all uses (2):
 - A. Planning Area E-1: 50'
 - B. Planning Area E-2: 60'

4. Residential Setbacks (unless otherwise approved by the Town at the time of SDP or Plat)
 - A. Primary Structure

**Note: The numbers within parentheses following each standard indicate additional development standards which may apply. See Section 6.11.*

1. Minimum Lot Size: None

2. Setbacks (3, 4, 10, 13, 14)
 - a. Minimum Front Setback (1, 5, 8): 15'
 - b. Minimum Front Setback to Garage Door Face (1, 5, 8): 20'
 - c. Minimum Rear Setback (6): 10'
 - d. Minimum Rear Alley Setback (6, 7): 2'
 - e. Minimum Side Setback (interior lot) (6, 7, 12): 5'
 - f. Minimum Side Street Setback (1, 5, 6, 7, 8): 15'
3. Minimum Building Separation (3): 10'

B. Accessory Structure

**Note: The numbers within parentheses following each standard indicate additional development standards which may apply. See Section 6.11.*

1. Setbacks (3, 4, 10, 13, 14)
 - a. Minimum Front Setback (6): 20'
 - b. Minimum Rear Setback (6, 7): 5'
 - c. Minimum Rear Alley Setback (6, 7, 8): 2'
 - d. Minimum Side Setback (interior lot) (6, 7, 12): 5'
 - e. Minimum Side Street Setback (1, 5, 6, 7, 8): 15'
2. Minimum Building Separation (3): 10'

Unofficial Copy

CHECKED BY: MB, SW, DJ, JR
DRAWN BY:

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

PD ZONING REGULATIONS

6.6 Planning Areas F-1, F-2 and F-3

1. Permitted Uses
 - A. Residential
 1. Single Family Attached (Townhome, Duplex, Triplex, Fourplex, or other similar Multi-Unit Configurations)
 2. Multifamily (Apartments, Condominiums, or other similar Multifamily Configurations)
 3. Mixed-Use (horizontal or vertical)
 4. Detached Private Garages

- Non-Residential
 1. Adult Day Care Assisted Living, Memory Care, or other similar institutional uses
 2. Alcoholic Beverage Sales
 3. ATM / Kiosk
 4. Auto Body and Vehicle / RV / Boat Equipment and Repair
 5. Automobile / Vehicle / RV / Boat / Motorcycle / All-Terrain Vehicle / Equipment Sales and Leasing (Subject to Section 5.5 of this PD)
 6. Automobile Service / Fuel Station / Wash / Rental
 7. Bed and Breakfast
 8. Clinic
 9. College / University / Vo-Tech
 10. Commercial Amusement, Indoor and Outdoor
 11. Day Care Center Facility
 12. Drive-Through Facility
 13. Educational Facility
 14. Funeral Home
 15. Gym / Health Club
 16. Hospital
 17. Hotel / Motel
 18. Industrial, Flex (F-1 and F-3 Only)
 19. Kennel / Doggy Daycare
 20. Large Animal Clinic and Hospital
 21. Medical Lab
 22. Multi-Modal Transit Facility
 23. Nursery or Greenhouse (Wholesale or Retail)
 24. Nursing Home
 25. Office (including Flex Office)
 26. Parking Facility (stand-alone lot / structure)
 27. Place of Worship
 28. Private Club
 29. Public Facilities
 30. Recreation, Indoor or Outdoor
 31. Retail
 32. Restaurant
 33. Services, Commercial
 34. Services, Personal
 35. Services, Repair
 36. Storage, Indoor or Outdoor (Subject to Section 5.4 of this PD)
 37. Studio Classes
 38. Utilities, Public
 39. Veterinary Clinic
 40. Open Space, Public or Private
 41. Utilities including but not limited to gas, electric, telecom. This includes structures or facilities commonly associated or required with the installation and operation of utilities.
 42. Water infrastructure including but not limited to detention/retention areas/ponds, lift stations, and piping, as well as structures typically associated with water infrastructure such as pump houses.

2. Uses By Special Review
 - A. Solar collectors which are not part of the primary structure
3. Maximum Building Height for All Uses (2, 11): 7'5"
4. Maximum Building Height for hospitality, medical, office, multi-family residential, and vertical mixed-use buildings Uses (2, 11): 90'

5. Residential Setbacks: (unless otherwise approved by the Town at the time of SDP or Plat)
 - A. Primary Structure
 1. Minimum Lot Size: None
 2. Setbacks (3, 4, 10, 13, 14)
 - a. Minimum Front Setback (1, 5, 8): 0"
 - b. Minimum Front Setback to Garage Door Face (1, 5, 8): 20'
 - c. Minimum Rear Setback (6): 0"
 - d. Minimum Rear Alley Setback (6, 7): 2'
 - e. Minimum Side Setback (interior lot) (6, 7, 12): 5'
 - f. Minimum Side Street Setback (1, 5, 6, 7, 8): 15'
 3. Minimum Building Separation (3): 10'

*Note: The numbers within parentheses (above) following each standard indicate additional development standards which may apply. See Section 6.11.

- Accessory Structure
 1. Setbacks (3, 4, 10, 13, 14)
 - a. Minimum Front Setback (1, 5, 8): 20'
 - b. Minimum Rear Setback (6): 5'
 - c. Minimum Rear Alley Setback (6, 7): 2'
 - d. Minimum Side Setback (interior lot) (6, 7, 12): 5'
 - e. Minimum Side Street Setback (1, 5, 6, 7, 8): 15'
 2. Minimum Building Separation (3): 10'

*Note: The numbers within parentheses (above) following each standard indicate additional development standards which may apply. See Section 6.11.

 6. Non-Residential Setbacks: To be established at the time of Site Development Plan / Plat application, review, and approval.

6.7 Planning Areas G-1 and G-2

1. Permitted Uses
 - A. Residential: No residential uses allowed.
 - B. Non-Residential
 1. Adult Day Care Assisted Living, Memory Care, or other similar institutional uses
 2. Alcoholic Beverage Sales
 3. Auto Body and Vehicle / RV / Boat Equipment and Repair
 4. Automobile / Vehicle / RV / Boat / Motorcycle / All-Terrain Vehicle / Equipment Sales and Leasing (Subject to Section 5.5 of this PD)
 5. Automobile Service / Fuel Station / Wash / Rental
 6. Bed and Breakfast
 7. Clinic
 8. College / University / Vo-Tech
 9. Commercial Amusement, Indoor and Outdoor
 10. Day Care Center Facility
 11. Drive-Through Facility
 12. Educational Facility
 13. Funeral Home
 14. Gym / Health Club
 15. Hospital
 16. Hotel / Motel
 17. Industrial, Flex and Light Industrial
 18. Kennel / Doggy Daycare
 19. Large Animal Clinic and Hospital
 20. Multi-Modal Transit Facility
 21. Nursery or Greenhouse (Wholesale or Retail)
 22. Nursing Home
 23. Office (including Flex Office)
 24. Parking Facility (stand-alone or structure)
 25. Place of Worship
 26. Private Club
 27. Public Facilities
 28. Recreation, Indoor and Outdoor
 29. Retail
 30. Restaurant
 31. Services, Commercial
 32. Services, Personal
 33. Services, Repair
 34. Shooting Range, Indoor
 35. Storage, Indoor or Outdoor (Subject to Section 5.4 of this PD)
 36. Studio Classes
 37. Utilities, Public
 38. Veterinary Clinic
 39. Warehousing and Distribution
 40. Utilities including but not limited to gas, electric, telecom. This includes structures or facilities commonly associated or required with the installation and operation of utilities.
 41. Water infrastructure including but not limited to detention/retention areas/ponds, lift stations, and piping, as well as structures typically associated with water infrastructure such as pump houses.

2. Uses By Special Review
 - A. Solar collectors which are not part of the primary structure
3. Maximum Building Height for All Uses (2, 11): 7'5"
4. Maximum Building Height for hospitality, medical, office, multi-family residential, and vertical mixed-use buildings Uses (2, 11): 90'
5. Non-Residential Setbacks: To be established at the time of Site Development Plan / Plat application, review, and approval.

6.8 Accessory Uses

1. In all Planning Areas:
 - A. Permitted Uses
 1. Commonly associated Accessory Uses, incidental to the Primary Use or Building, including but not limited to decks, patios, porches, storage sheds, private greenhouses, radio or TV antenna, TV satellite dishes, solar panels mounted on a primary structure, sport courts, private swimming pools and associated structures and private non-commercial facilities or structures for the keeping of household pets.
- B. Accessory Uses are subject to Chapter 17.52.210 of the Castle Rock Municipal Code.

6.9 Temporary Uses

1. In all Planning Areas:
 - A. Permitted Uses
 1. A temporary sales and marketing center including but not limited to trailers, temporary buildings, model homes, or other similar structures which may typically be used as a sales and marketing center.
 2. A temporary construction office including but not limited to trailers, temporary buildings, or other similar structures which may typically be used as an office.
 - B. Temporary uses are subject to Chapter 17.16.020 of the Castle Rock Municipal Code.


6.10 Transition Zone Development Standards

1. Transition Zone Development Standards apply to areas within Planning Areas A, B-1, and B-2, as indicated on the PD Plan.
2. Minimum Residential Lot Sizes Apply within Transition Zones as follows:
 - A. Planning Area A: 7,700 square feet
 - B. Planning Area B-1: 6,600 square feet
 - C. Planning Area B-2: 6,600 square feet
3. Colors: All occupied structures and accessory structures shall be constructed and maintained so that predominant exterior wall colors (including the colors of basement walls on the downhill side of the structure) and roof surfacing materials (a) generally repeat the colors found most commonly in the land and vegetation around the building (earth tone), and (b) have a light reflective value of no more than forty percent (40%). Reflective materials and bright colors that contrast dramatically with the colors of the land and vegetation around them shall not be used as predominant colors on any wall or roof surface.
4. Floodlighting: Floodlights shall not be used to light all or any portion of any primary or accessory structure facade. All outdoor light sources mounted on poles, buildings or trees to illuminate streets, sidewalks, walkways, parking lots or other outdoor areas shall use full cutoff light fixtures. For purposes of this standard, a full cutoff light fixture is one in which no more than two and one-half percent (2.5%) of the total output is emitted at ninety degrees (90°) from the vertical pole or building wall on which it is mounted. All such fixtures shall be installed or shielded so that no part of the light bulb or light source is visible beyond the Dawson Trails property boundaries, to the greatest extent feasible.
5. Exterior Lighting: No exterior lights of any sort may be erected, placed, installed, or otherwise incorporated into the residential lot, adjacent road right-of-way, adjacent property, or open space wherein any glare or direct light is visible beyond the perimeter of the Dawson Trails property boundaries. This applies to all direct lighting including, but not limited to entry lights, garage lights, and driveway illumination. Low profile landscape lighting shall, to the greatest extent feasible, be installed to minimize visibility from off the Dawson Trails property.
6. Vegetation: Each property shall include at least one (1) tree of a species with a height, when mature, of at least thirty-five feet (35') for each two thousand five hundred (2,500) square feet of lot or parcel area; provided, however, that this requirement shall not require any single-family residential lot to contain more than four (4) trees. Trees required under this section shall be located in the portion of the lot which will provide enhanced screening from the open space areas or properties adjacent to the Dawson Trails PDP property boundary. However, these plantings are not intended to completely screen all portions of all structures. All trees installed to meet the requirements of this subsection shall be of coniferous species and included in the Town of Castle Rock Plant List, shall be a minimum of eight (8) feet tall when planted, and shall be planted before a Certificate of Occupancy is issued for the primary structure, or if that is not possible due to planting season or weather conditions, then within three (3) months of the beginning of the next planting season for the species. In addition, significant trees which are located on a property and not within a location of a proposed structure shall be preserved, when possible, as indicated during the Site Development Plan Process as "Existing Vegetation to Remain." Such trees are eligible to count toward the above planting requirement regardless of whether they are coniferous or deciduous, even if not located in an optimal location for screening as noted above. Concurrently with the Site Development Plan / Plat stage of the development process, the property owner submitting such plan may request approval of a vegetation plan in which the vegetation requirements for certain lots or tracts may be increased, decreased, or deleted, to reflect the degree of visibility of structures located in various portions of the subdivision. Landscaping required by this standard shall be credited against the landscaping requirement imposed by any other section of Town Code, or this specific PDP.
7. Fencing: Fences located on private lots abutting PL-1 and PL-2 in Planning Areas A, B-1, and B-2 shall be constructed as a split rail, post and rail, or other similar design because such designs have a natural appearance, blend well into the natural terrain, have an open character, and are generally more suitable for wildlife. Open style fencing shall not exceed 42" in height. Wire mesh may be incorporated into the fencing design to keep pets in. Fences of other materials or designs are prohibited, including solid privacy fences. Short lengths of privacy fencing, up to 40 feet in total length and up to 6 feet in height, may be used to screen portions of lots containing hot tubs or other similar private on-site amenities, or to contain pets. Privacy fencing shall be on the interior of the lot, meet setbacks, and not conflict with easements. Privacy fencing shall not be used in place of open rail fencing.

6.11 Supplemental Development Standards

- Below are Supplemental Development Standards that may apply within each Planning Area. Supplemental Development Standard #14 (A through E) includes standards applicable in all Planning Areas.
1. The garage door face for the lot shall be at least 20' from the back of public sidewalk. Non-garage door building face may have a minimum 10' setback.
 2. Building height measurements for both residential and non-residential excludes chimneys, parapets, architectural designs that screen rooftop mechanical equipment from view, and other similar architectural elements. Stairwells may also encroach maximum building height, if required by building design or code.

3. Encroachments may include bay windows, window wells, cantilevers, chimneys, exterior posts/columns, solar panels mounted on primary structure, mechanical equipment, light fixtures, roof overhangs and other architectural features and are allowed to extend outward from the primary structure in front, side, and rear yards. In no instance may an encroachment cross the property line, be located less than six feet (6') from the finished material of the encroachment to the adjacent property or extend into a wet or dry utility easement. Non-habitable structures, such as covered porches and courtyards may encroach into a setback up to 5' provided the setback is a minimum of 10' and the encroachment is not within the public right-of-way, sight triangles, or transportation and utility easements. Roof overhangs are permitted with a maximum encroachment of 2' into the building setback. Window wells are permitted to encroach into setbacks up to, except as limited by wet and dry utility easements.
4. Setbacks shall be measured from public right-of-way/property line to the building foundation of habitable space or garage. Non-habitable spaces such as covered porches and courtyards may encroach into a setback up to 5' provided the encroachment is not within public right-of-way, sight triangles, or transportation and utility easements.
5. The minimum setback of a side loaded garage is defined from the right-of-way/property line to the street-facing building plane.
6. Zero Lot Line Setbacks:
 - A. Private drive loaded home side or rear setbacks and associated utility easements shall be determined at the Site Development Plan / Plat stage of the development review process. Zero lot line setbacks are permitted.
 - B. If a lot is located in a row, cluster or arrangement of same/similar sized lots but would otherwise be subject to a different range of setback standards, side or rear setbacks shall be consistent with the building separation as required, including potential reduced side setbacks per Note #9 herein.
 - C. 0' lot line configurations are allowed. When 0' lot line configurations are permitted, detached garages may also utilize a 0' setback. All structures must meet building separation and code requirements as well as minimum standards for architecture. Setbacks shall not be less than required utility easements.
 - D. Rear setbacks to alleys or private streets may be reduced to zero when the minimum width of the right-of-way or easement exceeds the minimum standard as identified in the street sections.
 - E. Setbacks from public right-of-ways shall be 10' unless otherwise determined and approved at the time of Site Development Plan
7. Side setbacks may be reduced to no less than 3' as measured from the finished material of the exterior wall to the property line as long as minimum code requirements are met (unless using a 0' lot line configuration, See Note 6 above).
8. Side yard setback for corner lots shall be determined at the time of Site Development Plan / Plat and shall only apply to lots abutting a public right of way. Lots siding onto private streets, private drives, open space areas, or other similar uses shall use the minimum 5' side yard setback standards.
9. For residential lots with multiple street frontages, all sides of the primary structure facing a public street must follow the Primary Structure Setbacks for "Min. Front Setback" and "Min. Front Yard Setback to Garage Door Face" as applicable.
10. In Planning Areas D, E-2, F-1, and F-3, Multifamily, Commercial, and/or Mixed-use buildings may utilize a 0' setback to private rights-of-ways or easements. Setback from the public rights-of-ways shall be 10' unless otherwise determined and approved at the time of Site Development Plan.
11. Hospitality, medical, office, multi-family residential, and vertical mixed-use buildings are allowed to have a maximum height of 90 feet.
12. Residential layouts with Side Yard Use Easements are permitted and shall be determined at the Site Development
13. Setbacks for clustered single-family developments will be administered as minimum building separation using minimum front, side, and rear yard dimensions.
14. General Notes (apply to all Planning Areas and Development Standards, as necessary).
 - A. Any dwelling or home type within this PDP may be for-sale, for-rent, or age-restricted housing product.
 - B. A tandem garage configuration is calculated the same way as a garage with standard configuration for driving residential parking requirements.
 - C. Shared driveways / driveway easements / private driveways are permitted for all uses.
 - D. Maximum building coverage in Character Areas East and Central shall be 75% for all uses, except that attached homes and commercial/non-residential uses have a maximum building coverage of 85%. All site requirements such as landscaping, parking, water quality, detention, and all other applicable development standards shall also be met.
 - E. When necessary, tread of first entry step on a sidewalk entering a lot may be located immediately adjacent to the public sidewalk, if the step is not within the right-of-way (refer to exhibit below).



TREAD RISER AT R.O.W.

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

PLANNER/LANDSCAPE ARCHITECT
NORRIS DESIGN
Planning | Landscape Architecture | Branding
1101 Bannock Street
Denver, Colorado 80204
P 303.892.1166
www.norris-design.com

PD ZONING REGULATIONS

SECTION 7 | PUBLIC LAND AND OPEN SPACE

7.1 PL-1 District

- Permitted Uses. Uses permitted by right in the PL-1 District are:
 - Active and developed parks, recreation center and facilities and related uses including, but not limited to, rest rooms, parking and drives, information kiosks and maintenance and storage buildings;
 - Facilities for cultural/art uses, community events and other civic uses;
 - All municipal and/or quasi-municipal facilities or utilities; and
 - Educational Facilities.
 - Facilities for acquisition, collection, disposal, drainage, storage of water, sewage, or reused water
 - Facilities for distribution or storage of electricity (above or below ground as needed)
- Development Standards. Development standards for the PL-1 District are as follows:
 - Maximum Height: Fifty (50) feet;
 - Minimum Front Yard Setback: A minimum of fifteen (15) feet from the property line; twenty-five (25) feet if abutting an arterial street.
- Use by Special Review. Uses permitted by special review in the PL-1 District are as follows:
 - Buildings, structures or other permanent improvements privately owned and operated, which must be open for public use;
 - Special district buildings and structures (C.R.S. Title 32); and
 - Any building or structure more than fifty (50) feet in height, but not to exceed seventy-five (75) feet in height.

7.2 PL-2 District

- Permitted Uses
 - Open space, wildlife sanctuary, trails, and associated service facilities.
 - Off-street parking and drives.
 - Facilities for acquisition, collection, disposal, drainage, storage of water, sewage, or reused water.
 - Utility and communication distribution lines (under or above ground as needed)
 - Facilities for distribution or storage of electricity (above or below ground as needed)
 - Irrigation facilities
- Development Standards.
 - Maximum Height: Twenty-five (25) feet;
 - Minimum Front Yard Setback: Twenty-five (25) feet.
- Use by Special Review. Applications for use by special review shall be evaluated under Section 17.38.050 of the Code, provided Section 17.38.040 shall have no application. Uses permitted by special review in the PL-2 District are as follows:
 - Any use allowed in the PL-1 District or otherwise determined by the Director which could be appropriate with additional review.

7.3 Private Open Space (OSP)

- Permitted Uses
 - Active and developed parks, community/recreation centers and related uses, including but not limited to, buildings/structures, restrooms, parking and drives, information kiosks, picnic structures, gazebos and similar amenity structures, and maintenance and storage buildings.
 - Facilities for cultural/art uses, community events and other similar uses.
 - Public or Private Open space, wildlife sanctuary, trails, and associated service facilities.
 - Off-street parking and drives.
 - Facilities for acquisition, collection, disposal, drainage storage of water, sewage, or reused water.
 - Utility and communication distribution lines (under or above ground as needed) Irrigation facilities
 - Additions/extensions of open space or PL-1 and PL-2 areas on the PD Plan,
 - Open space corridors along edges and/or internal to the Planning Area
 - Parks, pocket parks and/or other similar amenity areas
 - Enhanced portions of street corridors
 - Greenways
 - Gathering places
 - Detention/retention areas/pond areas
 - Facilities for distribution or storage of electricity (above or below ground as needed)
- Development Standards. Development standards for the OSP District are as follows:
 - Maximum Height: Fifty (50) feet.
- Setbacks: (unless otherwise approved by the Town at the time of SDP or Plat)
 - Minimum Front Setback: 15'
 - Minimum Front Yard Setback to Arterial: 25' or setback of the adjacent Planning Area, whichever is greater.
 - Other Setbacks are to be established at the time of Site Development Plan/ Plat application, review, and approval.

7.4 Reclassified Open Space

Private Open Space Reclassification Permitted. A limited amount (maximum 20 acres) of land depicted as PL-1 and / or PL-2 in this PDP shall be permitted to be reclassified as Private Open Space (OSP). Reclassification of any future OSP tracts will be coordinated with the Town, as appropriate, during the Site Development Plan / Plat stage of the development review process as more detail is known to determine where these sites should be located. Any portion of the potential 20 acres that are not reclassified and platted as OSP shall remain as PL-1 or PL-2 and shall be platted/dedicated to the Town. Replacement of reclassified acreage is not required.

SECTION 8 | ARCHITECTURE

Prescriptive architectural standards have been approved and adopted with this Dawson Trails Planned Development Plan and Planned Development Zoning Regulations and are incorporated herein as Appendix 1

SECTION 9 | SIGNAGE

Prescriptive signage standards have been approved and adopted with this Dawson Trails Planned Development Plan and Planned Development Zoning Regulations and are incorporated herein as Appendix 2

SECTION 10 | SUBMISSION OF SITE DEVELOPMENT PLANS AND/OR PLATS

- Following approval of the Dawson Trails PDP Amendment, the Property Owners shall submit a Site Development Plan for all or any portion(s) of the PDP, as are then ready for development.
- No structural building permit will be issued until a Site Development Plan and Plat have been presented to and approved by the Town.

SECTION 11 | TRANSITIONAL LAND USE

- After approval of the Dawson Trails PDP incorporated herein by reference, any portion or portions of the property described as the Dawson Trails PDP, which has not been subjected to a Site Development Plan and development has not commenced, may be used for agricultural purposes until approval of a Site Development Plan for the area or areas in question. Agricultural land uses, for the purposes of this section, shall mean farming, ranching, pre-existing residential uses, gardening, and existing building and out- buildings pertaining thereto. It shall not be deemed to include commercial feed yards, commercial poultry or pig farms, fur farms or kennels.
- Any activity permitted by this Section shall be considered to be a valid pre-existing non-conforming use within the area described in 11.1 above, until a Site Development Plan for such area or areas has/have been approved and development has commenced.
- Areas or agricultural activities shall be closed to vehicular traffic and off-road recreation motor biking, excepting agricultural vehicles and implements, emergency vehicles, vehicles engaged in utility and other maintenance work, and designees of the Master Developer, or the Town.

Unofficial Copy

APPLICANT:



WESTSIDE INVESTMENT PARTNERS
4100 E. MISSISSIPPI AVE
SUITE 500
DENVER, CO 80246
303-984-9800

ENGINEER & SURVEYOR:

CORE
CORE CONSULTANTS, INC.
LIVEYOURCORE.COM
CORE CONSULTANTS
3473 S. BROADWAY
ENGLEWOOD, CO 80113
303-730-5960



DAWSON TRAILS
PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE:
PDP-01 07/08/2021
PDP-02 12/03/2021
PDP-03 04/13/2022
PDP-04 05/27/2022
PDP-05 06/09/2022

SHEET TITLE:
PD ZONING REGULATIONS

SHEET
18 OF 20

CHECKED BY: MB, SW
DRAWN BY: DJ, JR

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

ARCHITECTURAL DESIGN STANDARDS

General Information

The architectural design standards guide the composition of the architectural styles for the Dawson Trails PD embracing the regional architecture of the Front Range. The property presents a unique opportunity to assimilate the Dawson Trails neighborhood elements in a scenic Front Range setting. The vernacular "Colorado architecture" envisioned for Dawson Trails is indicative of modern interpretations of rustic, ranch, mountain, prairie agrarian and western influenced styles and regional materials. These standards allow for architectural variety, including franchise architecture, complete with neighborhood elements to establish a cohesive neighborhood. The Character Areas in the PD establish a planning framework aligned with the architectural texture of Dawson Trails.

A wide range of land uses are permitted in the Dawson Trails development plan. Refer to the Dawson Ridge PD for descriptions of the West, Central and East Character Areas.

Development types categorized in these standards provide the overall standards and specific criteria for various types of users that will be incorporated into the PD Planning Areas, while maintaining the overall intent of the Character Areas.

The architectural design standards highlight the following development types:

- Pedestrian Oriented
- Commercial / Retail / Office
- Industrial
- Multifamily Residential
- Single Family Residential (*supplemental to existing Town standards*)

Design Standards (Overall)

The following design standards aim to create visual interest and consistency by addressing a variety of building types and complimentary styles. These standards also address specific design elements including massing, proportions, detailing elements, materials, and site design.

Buildings across all development types listed above should consider the following:

- All sides of a building open to public view shall display a similar level of quality and architectural interest.
- Variation in the building facade by vertical or horizontal articulation, window and entry variations, patios, plazas or other landscaped pedestrian areas are encouraged. Strong vertical elements such as windows, pilasters, columns, stairs, and towers should be used to identify individual commercial spaces.
- Large volumes or planes of buildings should be broken up into smaller ones to reduce the visual scale of a building. The mass of a building should be varied in form or divided to emphasize the various interior building functions.
- Variations in roofline and building parapet walls shall be utilized to effectively break up massing and provide visual interest.
- Shade shall be integrated throughout Dawson Trails via the use of overhangs and architectural shading elements.
- Building design shall incorporate textured surfaces, projections, recesses, shadow lines, color, window patterns, overhangs, reveals, changes in parapet height, and other treatments to avoid monolithic shapes and surfaces.
- The primary entrance of a building or store shall have a clearly defined, visible entrance with distinguishing features such as:
 - Arcades
 - Architectural details integrated into the building structure to frame the entryway.
 - Canopies or porticos
 - Enhanced pedestrian surfaces
 - Framing by outdoor pedestrian features or enhanced landscaping
 - Overhangs
 - Peaked roof forms or arches
 - Raised corniced parapets over the door
 - Recesses/projections
- For most buildings, at least two (2) of the elements listed below should repeat horizontally. Buildings with facades greater than 100 feet in length shall employ techniques to provide additional interest and to subdivide the wall plane including three of the elements listed below, repeated at appropriate intervals horizontally and/or vertically:
 - Color change
 - Texture change
 - Material change
 - Architectural variety and interest through a change in plane such as offsets, reveals, archways or projecting ribs
 - Wall plane projections or recesses
 - A variety of roof lines and parapet heights incorporating changes or elements
- Horizontal alignment of architectural elements such as windows, sills, cornices, banding, and other provisions is encouraged.
- Storefronts are to be complementary to the building materials. Storefronts may consist of an architectural treatment required by a national brand as appropriate.
- Exterior building materials shall use high quality, durable materials including tenant selected materials provided that they maintain the overall quality and style of the project. Predominant exterior building materials may include, but are not limited to:
 - Architectural metal
 - Brick
 - Clear and tinted glass
 - Concrete roof
 - Masonry: integral color, sand or water blasted, or stained textured
 - Metal roofs
 - Split-face, scored and/or architectural concrete masonry units (CMU)
 - Stone, natural or faux
 - Stucco/EIFS
 - Tilt-up concrete panels, where determined appropriate by the DTACC
- Buildings that utilize CMU walls shall use integrally colored units. Painted CMU is not permitted.

- Buildings that utilize tilt wall concrete wall panels shall require incorporation of sufficient articulation and color patterning to add a variety of texture and visual interest.
- Murals and graphics applied to exterior walls are permitted, subject to the Town of Castle Rock Sign Code.
- Roofing materials should be of a color and material consistent with the architectural character of the building and should convey a sense of permanence and quality.
- Screening of all roof top or pad mounted mechanical units is required.
- The style and placement of exterior accent lighting shall enhance the building's architectural elements such as entry features, pilasters, columns, and landscaping.
- Light to medium intensity colors with low reflectivity are preferred as the background building color. Brighter colors may be used for accents, trim or highlighting architectural features. The warm, subdued hues of natural, earth colors are encouraged.
- Color can be used to impact the scale of a building by highlighting various architectural elements.
- Integration of fabric/canvas awnings, flat metal awnings, trellises, and other similar provisions is encouraged.
- Buildings shall be situated to provide a visual and physical connection to the public roads/streets.
- A sense of entry shall be created into the development site by using building placement, landscaping treatments, signage, and other appropriate elements.
- Commercial developments within the PD are encouraged to provide vehicular access to adjoining properties or development sites in order to provide connectivity between development sites.
- A commercial development site shall provide pedestrian access throughout the site by linking to adjacent sidewalks, pathways, and/or transit stops, when appropriate, unless grade changes or other site constraints are prohibitive.
- Buildings, which are placed immediately adjacent to the sidewalk, shall promote visibility and pedestrian orientation potentially with plazas, outside dining, or other pedestrian areas.
- Integration of raised planters or potted plants is encouraged to define outdoor spaces.
- Use of site furnishings such as benches, tables, chairs, and fabric umbrellas are encouraged.
- For mixed use and non-residential single lot, multi-building development, pedestrian amenities that allow for use and enjoyment of outdoor areas as a development focal point or centralized amenity for people from other buildings. These can include a mix of pedestrian-scaled lighting, tables, drinking fountains, benches, seating walls, shade trees, raised landscape planters, berms, clock towers, specimen trees, potted plants, information kiosks, botanical exhibits, or art features.
- A variety of wall-mounted light fixtures, which fit the period or architectural style proposed, are encouraged. Unshielded lighting fixtures, wall packs and floodlights are prohibited.
- Delivery, loading, trash, and other service areas must be screened or integrated into the building.
- Screening must be accomplished by a wall constructed of integrally colored CMU, architectural metal screening, stone, stucco, textured stained concrete, brick, or similar materials that are compatible, to match the primary structure.

Pedestrian Oriented Area Standards

Intent: Planning Area E-2 in the PDP is a mixed-use parcel that is more centrally positioned in the Dawson Trails neighborhood. This Planning Area is categorized as a **Pedestrian Oriented Area** and has the potential to include a pedestrian-oriented cluster of uses and will provide opportunities to shop, work, live, and recreate. Pedestrian Oriented areas beyond the one described in Planning Area E-2 may also be developed in other areas of at Dawson Trails.

The following are the pedestrian design standards for the areas and buildings within the PDP that are categorized as a **Pedestrian Oriented Area**, which includes a centrally located gathering place and/or "main street" and will include the following:

- Either a publicly accessible and activated square/green/plaza OR a publicly accessible and activated "main street" at least one (1) block in length with buildings fronting with urban design elements such as on-street parking (parallel or head-in), street trees for shade, decorative/enhanced paving, lighting/street furnishings, and other elements to help establish and define the public realm of the place/street.
- Enhanced elements to support pedestrian connectivity may include crosswalks and mid-block crosswalks, defined by change of material, outdoor dining, pedestrian-scaled lighting (poles and/or bollards), dedicated bicycle parking in key locations, or similar improvements
- Development patterns to prioritize pedestrians by placing entrances at sidewalks, providing landscaping along main routes, and allowing on-street parking to help encourage slower vehicular traffic. As this area's goal is to be pedestrian oriented, the transportation network in this area should also provide safe crossings for pedestrians and cyclists and include mid-block crossings where necessary.
- Convenient pedestrian and bicycle access to all adjacent streets.
- Create pedestrian focal points with enhanced pedestrian paving, shaded sitting areas with comfortable seating and tables, proximate to cafes or coffee shops, views of landscaped areas, parks, or distant natural vistas, pedestrian-scaled lighting, and safe, non-intrusive people watching. Where possible, provide power and wi-fi to encourage people to work outdoors.
- Accessible parking spaces located, signed, striped, and lighted with close and convenient access to building entries.
- For multi-building office areas/campuses, pedestrian amenities that allow for use and enjoyment of outdoor areas as a development focal point or centralized amenity for people from other buildings. These can include a mix of pedestrian-scaled lighting, tables, drinking fountains, benches, seating walls, shade trees, raised landscape planters, berms, clock towers, specimen trees, potted plants, information kiosks, botanical exhibits, or art features.
- Convenient pedestrian access to transit stops and outlying parking areas, if any.
- Where feasible, design sites to accommodate bus stops.
- Bicycle parking in convenient and visible areas that do not interfere with pedestrian circulation.
- Interconnection of pedestrian areas with adjacent existing or planned open space.
- The potential for outdoor dining and/or other amenities to enliven plazas and open space areas.

Commercial / Retail / Office / Vertically Mixed Use Standards

Intent: The overall goal for this development type categorized as **Commercial / Retail / Office / Vertically Mixed Use** is to create an organized campus (if multiple buildings are contemplated) that incorporates a variety of retail, office, restaurant, hospitality, and other similar types of users. This development type may incorporate a horizontal and/or vertical mix of uses. These areas tend to be vehicular-centric commerce areas that include pedestrian accommodations serving core areas of the PDP. Combining a complementary mix of uses that are organized to establish a cohesive environment meant to enhance both daytime and nighttime activities is desired. Including elements such as community gathering spaces, covered patios, generous walking areas, and germane architecture that creates a front door presence within the overall neighborhood context further strengthens this type of use area.

Neighborhood retail and services areas and buildings can vary in size (sometimes significantly) and the surrounding context should be evaluated to ensure that each building fits into the specific area. Pad site and inline retail use areas and buildings should utilize similar design elements as the other areas of the specific area of context. These locations shall incorporate a similar level of site-specific building and pedestrian elements that contribute to the overall character of the Dawson Trails neighborhood.

Large format/destination retail uses shall provide a place(s) that is/are the "heart" of the specific shopping area. Large-scale tenants bring a national presence to the various use areas in the PD and provide unique synergies amongst themselves. These areas within the Dawson Trails PD should be designed to provide similar design features that are intended to enhance the overall experience.

Buildings that are associated with national franchise companies shall be allowed to retain the elements required to convey their national identity and brand. These buildings are encouraged to integrate the materials and design standards to complement the overall architectural character, when possible.

Flex Space and Industrial Standards

Intent: Dawson Trails Architectural Standards and the functionality of these commerce areas and manage the functionality of the Flex Space and Industrial buildings while integrating the overall character of the neighborhoods. The following is a summary of the supplemental design standards for the development within the PD **Flex Space and Industrial** planning areas.

- Focus architectural treatments to public street and highway exposures. Shield loading and back-of-house functions from public streets. Focus shall be placed on creating feature elements on facades, transitions in wall texture, color, height, plane, and overall expressions of mass and void. Designs shall avoid unbroken, flat walls of 100 feet or greater.
- Surfaces shall be predominantly concrete or masonry materials including tilt-up concrete and other large format masonry materials, painted or integrally colored CMU, stone, and trims of complementary materials. Metal panels, fabrications, and trims may be a component of the dominant materials when combined with concrete or masonry materials. Cement fiber board, phenolic wood, stucco, EIFS and other troweled or painted products may be used as accents.
- Accents of primary and secondary colors may be imposed on a primary field of natural colors and textures. Color is encouraged as a form giving element for entry and feature components.
- Service and loading operations shall be conducted within an enclosed structure or screened area.
- Outdoor storage, terminals, motor vehicle storage, contractors' yards, and transfer stations shall be screened or located in the back of house location.
- Major exterior trash and recycling receptacles shall remain within service and storage areas and be painted to match the primary or secondary color used on the main building.
- Cross dock facilities shall be allowed for truck loading and storage areas. Truck loading and storage within cross dock areas may be oriented both internal to the parcel areas and to the public right of ways. These areas shall be screened from public streets and open space networks through landscape design and screening wall techniques determined at time of SDP.
- Outdoor storage:
 - Outdoor service and storage areas shall be screened with solid masonry walls or opaque decorative fencing that complement the architectural character of the building from public streets, public spaces and I-25 corridor.
 - Where applicable, green screens with evergreen vines are encouraged to screen utility and service areas. Their shape can be integrated into the architectural character of the building. Green screens are to be used in addition to the required screen wall (they are not a replacement for the required wall).

Multifamily Residential Standards

Intent: The planning and design approach for **Multifamily Residential** development types is to ensure a general level of consistency and quality of a single multi-story building or a collection of multiple buildings. The overall site design should prioritize the public realm and pedestrian connectivity through the site. Multifamily uses may be horizontally and/or vertically integrated into a mixed-use building or district where it is encouraged to activate the first floor of the building(s) with commercial or other appropriate uses. The following architecture features shall enhance the design character of multifamily buildings and to complement the overall character of Dawson Trails.

Building Design: The following is a summary of supplemental Design Standards for a multifamily residential building.

- Four-sided architecture shall be integral to the design of all sides of a building and display a similar level of quality and architectural interest.
- Entries shall be emphasized with additional detailing.
- Buildings should be designed with a variety of surfaces, textures, shapes, multi-planed roofs, materials, and wall articulation.
- The scale, details, and materials shall be compatible with surrounding residential neighborhoods.
- A variety of heights, colors, setbacks, and step-backs are encouraged to avoid long, unarticulated building facades.
- Variations in exterior walls in depth and direction are encouraged. Use pop-outs, arches, and balconies to break up massing.
- Massive straight rooflines with flat appearances shall be avoided.
- Minimize the bulk and appearance of structures through the use of rooflines consisting of varying roof heights, directions, and shapes.
- Material will include architectural stone, composition siding, architectural plaster, high performance windows and glass, and other similar elements.
- Murals and graphics applied to exterior walls are permitted, subject to the Town of Castle Rock Sign Code.
- Garages shall be architecturally integrated into the established design character.
- Building placement and orientation shall vary for design interest and visual relief.
- Screening of mechanical units is required, to the extent possible.
- Integration of landscape and hardscape design elements and materials is to be provided in order to create public space and key arrival areas.
- Pedestrian access shall be provided throughout the site by linking buildings to adjacent sidewalks and pathways, when appropriate, unless grade changes or other site restrictions are prohibitive.
- Use of site furnishings such as benches, tables, chairs, and fabric umbrellas are encouraged.

Single-family Residential Standards (supplemental to Town standards)

Intent: These supplemental standards are to be used in addition to the Castle Rock Design Guidelines for Design and Development in the Town of Castle Rock, specifically for corner lot and lots adjacent to open space. The **Single-family Residential** development type can be comprised of detached or attached housing types.

- Architectural features for corner lots or lots adjacent to open space shall address the architectural treatment of residential elevations as listed below:
 - Side elevations on the street side of corner lots, or adjacent to open space or trailheads shall receive full architectural treatment, which includes substantially matching the character of the front of the house, using similar materials, window sizes and architectural details.
 - Townhomes, duplexes, single family for rent homes and single-family attached shall require four-side architectural treatment.

Landscape and Irrigation Design Standards

Intent: Landscape areas will be designed in conformance with the TOCR Landscape and Irrigation Criteria Manual, as amended, and the Dawson Trails Water Efficiency Plan. Landscape design shall consider the consistency of plant selection, design intent, its compatibility with the overall established landscape theme, and other site specific characteristics, as appropriate. Designs should utilize indigenous, historically adaptable, low maintenance, and hardy, turf, plants, and trees per the TOCR Landscape and Irrigation Criteria Manual.

Submittal Requirements (Dawson Trails Architectural Control Committee)

Dawson Trails Architectural Control Committee (DTACC) Review and Approval: All designs for proposed buildings, site improvements, and signage improvements must be reviewed and approved by the DTACC as a condition of acceptance of the Site Development Plan (SDP) by the Town of Castle Rock.

APPLICANT:



WESTSIDE INVESTMENT PARTNERS
4100 E. MISSISSIPPI AVE
SUITE 500
DENVER, CO 80246
303-984-9800

ENGINEER & SURVEYOR:

CORE
CORE CONSULTANTS, INC.
LIVELY@CORE.COM
CORE CONSULTANTS
3473 S. BROADWAY
ENGLEWOOD, CO 80113
303-730-5960



DAWSON TRAILS
PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE:
PDP-01 07/08/2021
PDP-02 12/03/2021
PDP-03 04/13/2022
PDP-04 05/27/2022
PDP-05 06/09/2022

SHEET TITLE:
ARCH DESIGN STANDARDS

SHEET
19 OF 20

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

APPLICANT:



WESTSIDE INVESTMENT PARTNERS
4100 E. MISSISSIPPI AVE
SUITE 500
DENVER, CO 80246
303-984-9800

ENGINEER & SURVEYOR:



CORE CONSULTANTS, INC.
CORECONSULTANTS.COM
CORE CONSULTANTS
3473 S. BROADWAY
ENGLEWOOD, CO 80113
303-730-5960



SIGN DESIGN STANDARDS


SECTION 9 | SIGNAGE

This section addresses signage for the Dawson Trails PDP to guide the overall integration of a signage master plan for the neighborhood.

Landmark signage and temporary signage will be guided by the Dawson Trails PDP. These signage locations will be shown at time of Site Development Plan (SDP) and / or with the sign permit application. Landmark signage along the I-25 corridor is permitted in Planning Areas F-1, F-2, F-3, G-1 and G-2 as defined on the PD Plan. Temporary signage in the Dawson Trails PDP as defined by the PD Plan and along the Interstate 25 corridor is permitted, subject to the provisions of the Municipal Code. The following summarizes the criteria for signage.

9.1 Landmark Signage

- A. A **Landmark Sign** is a non-electronic sign to be located with the F and G Planning Areas along the I-25 corridor directing attention to businesses, commodities, services, products, or properties within Dawson Trails.
- B. Landmark Signs are allowed in Planning Areas F-1, F-2, F-3, G-1 and G-2 and must be located within 300 feet of the Dawson Trails PD Plan property line along the Interstate 25 corridor and meet the spacing requirements noted below.
- C. Landmark Signs shall be located a minimum of 1,500 feet from other Landmark Signs and there may be a maximum of eight (8) Landmark Signs. Other on-site signage per the Dawson Trails Master Sign Plan (as defined by the Town of Castle Rock Municipal Code, Title 19 at the date of this application) shall not be included in this separation requirement. The distance shall be measured in a straight line from the closest points on each sign.
- D. Landmark Signs are permitted to be up 700 sq. ft. per sign face with a maximum of two (2) sign faces. Only one (1) sign face shall be visible from any one direction of travel on Interstate 25 for a total of two (2) sign faces.
- E. The Landmark Sign prototype exhibit represents a potential configuration for this sign type. The final design for the Landmark Sign will be determined at time of sign permit.



- F. Maximum sign height allowed for Landmark Signs is 70 feet from finished grade.
- G. Landmark Signs shall be set back a minimum of 25 feet from the nearest street or interstate right-of-way to the closest point of the sign. The Landmark Signs shall be placed within landscape areas.
- H. Pole signs and attached highway electronic signs are prohibited.
- I. Landmark Signs material finishes include concrete, stone, architectural precast concrete, manufactured stone and wood products, aluminum, wood, metal, plastic translucent panels and illuminated sign panels or other similar materials. Architectural lighting of the sign faces is allowed. This may include internal illumination such as translucent panels, backlighted features or similar techniques for tenant names and logos in the sign face areas. All light sources, either internal or external, provided to illuminate signs shall be placed or directed away from public streets, highways, sidewalks or adjacent premises. The final design for the Landmark Sign shall be approved by the Dawson Trails Architectural Control Committee, refer to the Architectural Standards.
- J. A sign permit is required for Landmark Signs.

9.2 Temporary Signage and Banners

- A. Temporary Signage and Banners directing attention to businesses, commodities, services, products, real estate or properties within Dawson Trails are allowed in Planning Areas A, B, C, D, E, F and G.

Unofficial Copy

DAWSON TRAILS
PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE:

- PDP-01 07/08/2021
- PDP-02 12/03/2021
- PDP-03 04/13/2022
- PDP-04 05/27/2022
- PDP-05 06/09/2022

SHEET TITLE:

SIGN DESIGN STANDARDS

SHEET
20 OF 20

ORDINANCE NO. 2022-017

**AN ORDINANCE AMENDING THE TOWN'S ZONE DISTRICT MAP BY
APPROVING THE DAWSON TRAILS PLANNED DEVELOPMENT PLAN AND
ZONING REGULATIONS**

WHEREAS, proper application has been made to the Town of Castle Rock (the "Town") by Dawson Trails I, LLC and Dawson Trails II, LLC, (collectively, the "Applicant") for an amendment to the zoning of the property described in the attached *Exhibit 1* (the "Property"); and

WHEREAS, development of the northern portion of the Property is presently governed by the Westfield Trade Center Preliminary Planned Unit Development Site Plan, while development of the southern portion of the Property (the "Dawson Ridge Portion") is presently governed by the Dawson Ridge Preliminary Planned Unit Development Site Plan; and

WHEREAS, the Applicant has requested approval for the Dawson Trails Planned Development Plan and Zoning Regulations (the "PD Plan"); and

WHEREAS, with respect to the Dawson Ridge Portion of the Property, the Applicant is the successor in title to Dawson Ridge Metropolitan District No. 1 (the "District"); and

WHEREAS, the District and the Town are parties to that certain Suspension Agreement, dated October 8, 1992 (the "Suspension Agreement"); and

WHEREAS, among other things, the Suspension Agreement provides that, as a successor in title to the Dawson Ridge Portion, the rights, privileges, duties, and obligations of the District under that certain Annexation and Development Contract between the Town and Bellamah Community Development, dated November 15, 1984, shall be suspended until such time as the District or its successor in title has submitted a development plan to the Town for review and approval; and

WHEREAS, public hearings on the PD Plan have been held before the Planning Commission and Town Council in accordance with the applicable provisions of the Castle Rock Municipal Code; and

WHEREAS, the Town Council finds and determines that the PD Plan complies with the applicable requirements set forth in Chapters 17.32, 17.34, and 17.36 of the Castle Rock Municipal Code, the Town's Vision 2030 and the Comprehensive Master Plan; and

WHEREAS, the Town Council further finds and determines that the Applicant has satisfied the conditions of the Suspension Agreement with respect to the submission of a development plan.

NOW, THEREFORE, IT IS ORDAINED BY THE TOWN COUNCIL OF THE TOWN OF CASTLE ROCK, COLORADO:

Section 1. Suspension Agreement. The rights, privileges, duties, and obligations of the Applicant, as successor in title to the District with respect to the Dawson Trails Portion of the Property

shall hereby resume as of the effective date of this Ordinance.

Section 2. Approval. The Dawson Trails Planned Development Plan and Zoning Regulations in the form attached as *Exhibit 2* is hereby approved. To the extent that the Property is within the boundaries of the Dawson Ridge Preliminary Planned Unit Development Site Plan or the Westfield Trade Center Preliminary Planned Unit Development Site Plan, both Plans and the ordinances approving said Plans are hereby superseded by this Ordinance.

Section 3. Effective Date. With the effective date of this Ordinance, the Property is subject to the Castle Rock Municipal Code and all ordinances, resolutions, rules and regulations of the Town.

Section 4. Severability. If any clause, sentence, paragraph, or part of this ordinance or the application thereof to any person or circumstances shall for any reason be adjudged by a court of competent jurisdiction invalid, such judgment shall not affect the remaining provisions of this ordinance.

Section 5. Safety Clause. The Town Council finds and declares that this ordinance is promulgated and adopted for the public health, safety and welfare and this ordinance bears a rational to the legislative object sought to be obtained.

APPROVED ON FIRST READING this 16th day of August, 2022 by a vote of 7 for and 0 against, after publication in compliance with Section 2.02.100.C of the Castle Rock Municipal Code; and


6th **PASSED, APPROVED AND ADOPTED ON SECOND AND FINAL READING** this day of September, 2022, by the Town Council of the Town of Castle Rock by a vote of 7 for and 0 against.

ATTEST:

TOWN OF CASTLE ROCK




Lisa Anderson, Town Clerk




Jason Gray, Mayor

Approved as to form:


Approved as to content:



Michael J. Hyman, Town Attorney



Tara Vargish, Director of Development Services



DAWSON TRAILS PROJECT PERIMETER DESCRIPTION:

TWO (2) PARCELS OF LAND PORTIONS OF SECTIONS 15, 21, 22, 27, 28, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

THE BEARINGS FOR THIS DESCRIPTION ARE BASED ON THE NORTH LINE OF THE SOUTH HALF OF THE SOUTH HALF OF SECTION 21, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH P.M., BEING ASSUMED TO BEAR S89°55'56"E, FROM THE SOUTH 1/16TH CORNER OF SAID SECTIONS 21 & 22, BEING MONUMENTED BY A PIPE WITH A 2" ALUMINUM CAP STAMPED "LS 6935" TO THE SOUTH 1/16TH CORNER OF SAID SECTIONS 20 & 21, BEING MONUMENTED BY A PIPE WITH A 2 INCH ALUMINUM CAP, STAMPED "LS 6935", WITH ALL BEARINGS CONTAINED HEREIN RELATIVE THERETO.

PARCEL 1:

BEGINNING AT THE SOUTH 1/16TH CORNER OF SAID SECTIONS 21 & 22, ALSO BEING A POINT ON THE SOUTH LINE OF TWIN OAKS, A SUBDIVISION PLAT RECORDED AT RECEPTION NO. 161972, IN THE RECORDS OF THE DOUGLAS COUNTY CLERK AND RECORDER'S OFFICE;
THENCE S 89°28'35" E, ALONG THE SOUTH LINE OF SAID TWIN OAKS SUBDIVISION AND ALONG THE NORTH LINE OF THE SOUTH HALF OF THE SOUTH HALF OF SAID SECTION 22, A DISTANCE OF 404.37 FEET TO A POINT ON THE WEST LINE OF THE TWIN OAKS ROAD RIGHT-OF-WAY, AS DEDICATED BY SAID TWIN OAKS SUBDIVISION;
THENCE ALONG THE WEST LINE OF SAID TWIN OAKS DRIVE RIGHT-OF-WAY AND ALONG THE SOUTH LINE OF THE TERRITORIAL ROAD RIGHT-OF-WAY, AS DEDICATED BY SAID TWIN OAKS SUBDIVISION, THE FOLLOWING FOUR (4) COURSES:

1. S 02°01'48" E, A DISTANCE OF 52.10 FEET TO THE SOUTH LINE OF SAID TERRITORIAL ROAD RIGHT-OF-WAY;
2. N 87°58'41" E, A DISTANCE OF 109.24 FEET TO A POINT OF CURVATURE;
3. ALONG THE ARC OF A CURVE TO THE LEFT HAVING A RADIUS OF 245.68 FEET, A CENTRAL ANGLE OF 28°36'44" AND AN ARC LENGTH OF 122.69 FEET;
4. N 59°21'57" E, A DISTANCE OF 23.19 FEET TO A POINT ON THE SOUTH LINE OF SAID TWIN OAKS SUBDIVISION;

THENCE S 89°28'35" E, ALONG SAID SOUTH LINE, A DISTANCE OF 174.31 FEET TO THE SOUTHEAST CORNER OF SAID TWIN OAKS SUBDIVISION;
THENCE N 17°17'13" E, ALONG THE EAST LINE OF SAID TWIN OAKS SUBDIVISION, A DISTANCE OF 139.27 FEET TO A POINT ON THE EAST LINE OF SAID TERRITORIAL ROAD RIGHT-OF-WAY AND A POINT OF NON-TANGENT CURVATURE;
THENCE ALONG THE EAST LINE OF SAID TERRITORIAL ROAD RIGHT-OF-WAY THE FOLLOWING TWO (2) COURSES:

1. ALONG THE ARC OF A NON-TANGENT CURVE TO THE LEFT HAVING A RADIUS OF 198.98 FEET, A CENTRAL ANGLE OF 31°52'19" AND AN ARC LENGTH OF 110.69 FEET, SUBTENDED BY A CHORD OF WHICH BEARS N 33°13'23" E, A DISTANCE OF 109.26 FEET;
2. N 17°17'13" E, A DISTANCE OF 534.55 FEET TO A POINT ON THE SOUTH LINE OF THE TERRITORIAL ROAD RIGHT-OF-WAY AS DEDICATED BY THAT DEED RECORDED AT RECEPTION NO. 8816440, SAID DOUGLAS COUNTY RECORDS;

THENCE N 89°40'41" E, ALONG SAID SOUTH LINE, A DISTANCE OF 1599.61 FEET TO A POINT ON THE WEST LINE OF THE BURLINGTON NORTHERN SANTA FE RAILROAD RIGHT-OF-WAY;
THENCE S 15°17'57" W, ALONG SAID WEST LINE, A DISTANCE OF 8675.32 FEET TO THE NORTHEAST CORNER OF THAT PARCEL OF LAND DESCRIBED IN THAT DEED RECORDED AT RECEPTION NO. 2004131453, SAID DOUGLAS COUNTY RECORDS;
THENCE ALONG THE NORTH, WEST AND SOUTH LINES OF SAID PARCEL, THE FOLLOWING THREE (3) COURSES:

1. S 89°46'16" W, A DISTANCE OF 678.73 FEET;
2. S 00°19'26" W, A DISTANCE OF 600.54 FEET;
3. S 89°29'06" E, A DISTANCE OF 515.85 FEET TO A POINT ON THE WEST LINE OF SAID BURLINGTON NORTHERN SANTA FE RAILROAD RIGHT OF WAY;

THENCE S 15°17'57" W, ALONG SAID WEST LINE, A DISTANCE OF 547.53 FEET TO A POINT ON THE EAST LINE OF THE NORTHEAST QUARTER OF SAID SECTION 33; THENCE N 00°02'14" W, ALONG SAID EAST LINE, A DISTANCE OF 226.55 FEET TO A POINT ON THE WEST LINE OF SAID BURLINGTON NORTHERN SANTA FE RAILROAD RIGHT-OF-WAY;
THENCE S 15°19'54" W, ALONG SAID WEST LINE, A DISTANCE OF 789.53 FEET TO A POINT ON THE SOUTH LINE OF THE NORTH HALF OF SAID SECTION 33;
THENCE N 89°35'18" W, ALONG SAID SOUTH LINE, A DISTANCE OF 5123.28 FEET TO THE EAST QUARTER CORNER OF SAID SECTION 32, ALSO BEING THE NORTHEAST CORNER OF KEENE RANCH FILING NO. 1, A SUBDIVISION PLAT RECORDED AT RECEPTION NO. 9523375, SAID DOUGLAS COUNTY RECORDS;
THENCE S 89°21'58" W, ALONG THE NORTH LINE OF SAID KEENE RANCH FILING NO. 1 AND ALONG THE SOUTH LINE OF THE NORTHEAST QUARTER OF SAID SECTION 32, A DISTANCE OF 2414.68 FEET TO THE SOUTHEAST CORNER OF THAT PARCEL OF LAND DESCRIBED IN THAT DEED RECORDED AT RECEPTION NO. 2004051359, SAID DOUGLAS COUNTY RECORDS; THENCE ALONG THE EAST AND NORTH LINES OF SAID PARCEL OF LAND, THE FOLLOWING TWO (2) COURSES:

1. N 00°19'46" W, A DISTANCE OF 208.73 FEET TO THE NORTHEAST CORNER OF SAID DEED;
2. S 89°21'58" W, A DISTANCE OF 208.73 FEET TO A POINT ON THE WEST LINE OF THE NORTHEAST QUARTER OF SAID SECTION 32, ALSO BEING A POINT ON THE EAST LINE OF SAID KEENE RANCH FILING NO. 1;

THENCE N 00°19'46" W, ALONG THE EAST LINE OF SAID KEENE RANCH FILING NO. 1, ALONG THE EAST LINE OF KEENE RANCH FILING NO. 2, A SUBDIVISION PLAT RECORDED AT RECEPTION NO. 9639479, SAID DOUGLAS COUNTY RECORDS, AND ALONG THE WEST LINE OF THE NORTHEAST QUARTER OF SAID SECTION 32, A DISTANCE OF 2505.72 FEET TO THE NORTH QUARTER CORNER OF SAID SECTION 32;
THENCE N 00°39'34" W, ALONG THE EAST LINE OF SAID KEENE RANCH FILING NO. 2 AND ALONG THE WEST LINE OF THE EAST HALF OF SAID SECTION 29, A DISTANCE OF 5308.62 FEET TO THE NORTH QUARTER CORNER OF SAID SECTION 29, BEING THE NORTHEAST CORNER OF SAID KEENE RANCH FILING NO. 2 PLAT, AND THE SOUTHWEST CORNER OF CASTLE MESA SOUTH, A SUBDIVISION PLAT RECORDED AT RECEPTION NO. 145078, SAID DOUGLAS COUNTY RECORDS;
THENCE S 89°02'42" E, ALONG THE NORTH LINE OF THE EAST HALF OF SAID SECTION 29 AND ALONG THE SOUTH LINE OF SAID CASTLE MESA SOUTH SUBDIVISION, A DISTANCE OF 2661.01 FEET TO THE SOUTHEAST CORNER OF SAID CASTLE MESA SOUTH SUBDIVISION, BEING THE SOUTHWEST CORNER OF SAID SECTION 21;
THENCE N 00°02'04" W, ALONG THE EAST LINE OF SAID CASTLE MESA SOUTH SUBDIVISION AND ALONG THE WEST LINE OF THE SOUTH HALF OF THE SOUTH HALF OF SAID SECTION 21, A DISTANCE OF 1322.70 FEET TO THE SOUTH 1/16TH CORNER OF SAID SECTIONS 20 & 21, BEING THE SOUTHWEST CORNER OF SAID TWIN OAKS SUBDIVISION;

THENCE S 89°55'56" E, ALONG THE SOUTH LINE OF SAID TWIN OAKS SUBDIVISION AND ALONG THE NORTH LINE OF THE SOUTH HALF OF THE SOUTH HALF OF SAID SECTION 21, A DISTANCE OF 5286.17 FEET TO THE POINT OF BEGINNING.

LESS AND EXCEPT THE FOLLOWING TWO (2) PARCELS OF LAND;

TWO (2) PARCELS OF LAND, AS DESCRIBED IN SAID DEED RECORDED AT RECEPTION NO. 2004051359, SAID DOUGLAS COUNTY RECORDS, BEING A PORTION OF THE SOUTH HALF OF SECTION 28, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

THE BEARINGS FOR THESE EXCEPTION PARCELS ARE BASED ON THE SOUTH LINE OF SECTION 28, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH P.M., BEING ASSUMED TO BEAR S89°47'47"E, FROM THE SOUTHWEST CORNER OF SAID SECTION 28, BEING MONUMENTED BY A 1" PIPE WITH A 2-1/2" ALUMINUM CAP STAMPED "LS 6935" TO THE SOUTHEAST CORNER OF SAID SECTIONS 28, BEING MONUMENTED BY #6 REBAR WITH A 2-1/2" ALUMINUM CAP, STAMPED "LS 6935", WITH ALL BEARINGS CONTAINED HEREIN RELATIVE THERETO.

COMMENCING AT THE SOUTHWEST CORNER OF SAID SECTION 28, THENCE N 65°29'17" E, A DISTANCE OF 1262.53 FEET TO THE POINT OF BEGINNING;

THENCE N 00°45'02" W, A DISTANCE OF 208.73 FEET;

THENCE S 89°47'38" E, A DISTANCE OF 208.73 FEET;

THENCE S 00°45'02" E, A DISTANCE OF 208.73 FEET;

THENCE N 89°47'38" W, A DISTANCE OF 208.73 FEET TO THE POINT OF BEGINNING;

ALSO EXCEPTING THE FOLLOWING PARCEL

COMMENCING AT THE SOUTHEAST CORNER OF SAID SECTION 28, THENCE N 40°06'49" E, A DISTANCE OF 1765.27 FEET TO THE POINT OF BEGINNING;

THENCE N 89°47'47" W, A DISTANCE OF 208.73 FEET;

THENCE N 00°45'11" W, A DISTANCE OF 208.73 FEET;

THENCE S 89°47'47" E, A DISTANCE OF 208.73 FEET;

THENCE S 00°45'11" E, A DISTANCE OF 208.73 FEET TO THE POINT OF BEGINNING;

CONTAINING A NET AREA OF 81,902,811 SQUARE FEET OR 1,880.230 ACRES, MORE OR LESS.

PARCEL 2:

COMMENCING AT THE SOUTH 1/16TH CORNER OF SAID SECTIONS 21 & 22, ALSO BEING A POINT ON THE SOUTH LINE OF TWIN OAKS, A SUBDIVISION PLAT RECORDED AT RECEPTION NO. 161972, IN THE RECORDS OF THE DOUGLAS COUNTY CLERK AND RECORDER'S OFFICE;

THENCE N 53°44'53" E, A DISTANCE OF 1331.13 FEET TO A POINT ON THE EAST LINE OF SAID TWIN OAKS PLAT AND A POINT ON THE NORTH LINE OF THE TERRITORIAL ROAD RIGHT-OF-WAY, AS DEDICATED BY THAT DEED RECORDED AT RECEPTION NO. 8816440, SAID DOUGLAS COUNTY RECORDS AND THE POINT OF BEGINNING;

THENCE ALONG THE EAST LINE OF SAID TWIN OAKS PLAT, THE FOLLOWING THREE (3) COURSES:

1. N 17°17'13" E, A DISTANCE OF 557.93 FEET;

2. S 89°27'27" E, A DISTANCE OF 65.00 FEET;
3. N 00°22'15" W, A DISTANCE OF 1329.37 FEET TO THE SOUTHWEST CORNER OF LOT 3, SAID TWIN OAKS PLAT;

THENCE N 03°03'12" W, ALONG THE WEST LINE OF SAID LOT 3, A DISTANCE OF 567.45 FEET TO THE NORTHWEST CORNER OF SAID LOT 3, BEING A POINT OF CURVATURE ON THE SOUTH LINE OF THE BRISCOE LANE RIGHT-OF-WAY, AS DEDICATED BE SAID TWIN OAKS PLAT;

THENCE ALONG THE PORTIONS OF BRISCOE LANE VACATED BY ORDINANCE NO. 86-24, RECORDED IN BOOK 680 AT PAGE 920, SAID DOUGLAS COUNTY RECORDS THE FOLLOWING TWO (2) COURSES:

1. N 39°55'38" W, A DISTANCE OF 30.00 FEET TO A POINT OF NON-TANGENT CURVATURE;
2. ALONG THE ARC OF A NON-TANGENT CURVE TO THE RIGHT HAVING A RADIUS OF 329.30 FEET, A CENTRAL ANGLE OF 27°16'16" AND AN ARC LENGTH OF 156.74 FEET, SUBTENDED BY A CHORD OF WHICH BEARS N 63°42'30" E, A DISTANCE OF 155.26 FEET;

THENCE N 12°39'22" W, ALONG THE WEST LINE OF LOT 4, SAID TWIN OAKS PLAT, A DISTANCE OF 687.67 FEET TO THE NORTHWEST CORNER OF SAID LOT 4 ALSO BEING THE WEST 1/16TH CORNER OF SAID SECTIONS 15 & 22;

THENCE S 89°31'22" E, ALONG THE SOUTH LINE OF THE SOUTHWEST QUARTER OF SAID SECTION 15, A DISTANCE OF 890.07 FEET TO THE SOUTHWEST CORNER OF THAT PARCEL OF LAND DESCRIBED AS PARCEL E IN THAT DEED RECORDED AT RECEPTION NO. 2019088324, SAID DOUGLAS COUNTY RECORDS;

THENCE ALONG THE WEST AND NORTH LINES OF PARCELS E, F & G THE FOLLOWING FOUR (4) COURSES:

1. N 00°11'34" E, A DISTANCE OF 900.14 FEET;
2. S 89°48'26" E, ALONG THE NORTH LINES OF PARCELS E AND F, A DISTANCE OF 1014.77 FEET TO THE SOUTHWEST CORNER OF THAT PARCEL OF LAND DESCRIBED AS PARCEL G;
3. N 00°11'34" E, A DISTANCE OF 842.72 FEET;
4. S 89°48'26" E, A DISTANCE OF 928.55 FEET TO A POINT ON THE WEST LINE OF THE BURLINGTON NORTHERN SANTA FE RAILROAD RIGHT OF WAY AND A POINT OF NON-TANGENT CURVATURE;

THENCE ALONG THE WEST LINE OF SAID BURLINGTON NORTHERN SANTA FE RAILROAD RIGHT-OF-WAY THE FOLLOWING TWO (2) COURSES:

1. ALONG THE ARC OF A NON-TANGENT CURVE TO THE LEFT HAVING A RADIUS OF 5779.58 FEET, A CENTRAL ANGLE OF 05°35'04" AND AN ARC LENGTH OF 563.33 FEET, SUBTENDED BY A CHORD OF WHICH BEARS S 18°04'54" W, A DISTANCE OF 563.11 FEET;
2. S 15°17'57" W, A DISTANCE OF 4536.04 FEET TO A POINT ON THE NORTH LINE OF SAID TERRITORIAL ROAD RIGHT-OF-WAY;

THENCE S 89°40'41" W, ALONG SAID NORTH LINE, A DISTANCE OF 1628.83 FEET TO THE POINT OF BEGINNING.

CONTAINING AN AREA OF 7,993,235 SQUARE FEET OR 183.499 ACRES, MORE OR LESS.

OVERALL DAWSON RIDGE PROJECT PERIMETER DESCRIPTION CONTAINS AN AREA OF 89,896,046 SQUARE FEET OR 2,063.729 ACRES, MORE OR LESS.


DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN

TWO PARCELS OF LAND BEING ALL OF SECTION 26 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 28, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

VICINITY MAP



SHEET INDEX

- SHEET 1 COVER
- SHEET 2 OWNER'S SIGN CERTIFICATION
- SHEET 3 PLANNED DEVELOPMENT PLAN
- SHEET 4 OPEN SPACE, PUBLIC LAND, AND TRAILS PLAN
- SHEET 5 NATURAL FEATURES MAP
- SHEET 6 PHASING PLAN
- SHEET 7 DRAINAGE & DRAINAGE PLAN
- SHEET 8 WILDLAND MANAGEMENT PLAN
- SHEET 9 ZONING REGULATIONS
- SHEET 10 ARCHITECTURAL DESIGN STANDARDS
- SHEET 11 SIGN DESIGN STANDARDS

PURPOSE STATEMENT

The Dawson Trails PDP is an amendment to the Dawson Ridge Preliminary P.U.D. Site Plan and a portion of the Westfield Trade Center Preliminary P.U.D. Site Plan to zone the property for residential, mixed use, commercial, industrial, open space, and PLO.

VESTING

This Dawson Trails Planned Development Plan inclusive of the embedded PDP zoning regulations constitutes a site specific development plan pursuant to Chapter 7.08 of the Castle Rock Municipal Code and §24-64-101, et seq., C.R.S., and establishes vested property rights through December 31, 2092, to undertake and complete the development and use of the property in accordance with this plan. Town Council may approve a one time ten-year extension of the vesting period, not to exceed December 31, 2087.

TECHNICAL CRITERIA VARIANCE APPROVAL

Approved 5/11/2022
Approval allows for reduced intersection spacing between full movement intersections along Dawson Trail Blvd/Prairie Hawk Dr.

SUMMARY TABLE

CHARACTER AREA	PLANNING AREA	LAND USE TYPE	PERCENTAGE	MAX. DENSITY UNITS	MIN. LOT SIZE	MIN. FRONT YARD SETBACK	MIN. SIDE YARD SETBACK	MIN. REAR YARD SETBACK	% OF PROPERTY	MAX. BUILDING HEIGHT (FT)
WEST	A	SPD	20%	40	7,200 sq ft	75'	5'	5'	1.5%	30'
	B	SPD	10%	20	4,000 sq ft	75'	5'	5'	0.75%	30'
	C	SPD	10%	20	4,000 sq ft	75'	5'	5'	0.75%	30'
CENTRAL										
CENTRAL	D	SPD	20%	40	7,200 sq ft	75'	5'	5'	1.5%	30'
	E	SPD	10%	20	4,000 sq ft	75'	5'	5'	0.75%	30'
	F	SPD	10%	20	4,000 sq ft	75'	5'	5'	0.75%	30'
EAST										
EAST	G	SPD	20%	40	7,200 sq ft	75'	5'	5'	1.5%	30'
	H	SPD	10%	20	4,000 sq ft	75'	5'	5'	0.75%	30'
	I	SPD	10%	20	4,000 sq ft	75'	5'	5'	0.75%	30'

MAX. OVERALL UNIT AREA COEFFICIENT (MOR) TO EXCEED: 0.850
 MAX. MAXI-FAMILY OVERALL UNIT COEFFICIENT (MOR) TO EXCEED: 2.450
 MAX. COV./MIN. NET PL. EAST & CENTRAL SUBDIVISIONS: 1.500/0.000

PLANNING AREA	1574	80.0%
OPEN SPACE (PL. 3.0 ON)	1513	28.0%
PUBLIC LAND (RECREATION) (PL. 3)	201	11.0%
ROW (APPARATUS)	607	2.5%
TOTAL PROPERTY (APPROXIMATELY)	1963	100.0%

LAND USE SUMMARY NOTE
 1) ROW LAND AREA IS A VERTICAL MEASURE. HOSPITALITY, MEDICAL, OFFICE, AND MULTIFAMILY RESIDENTIAL USES ARE ALLOWED TO HAVE A MAXIMUM HEIGHT OF 6 FEET FOR SECTION 611 ON SHEET 17.

PDP STANDARD NOTES

- A SMALL PORTION OF THE MINERAL RIGHTS ASSOCIATED WITH THIS PROPERTY HAS BEEN RESERVED FOR THE SMALL PORTION OF SEVERED MINERAL RIGHTS, A WAIVER OF NOTICE BY SUCH HOLDER HAS BEEN RECEIVED AS A PART OF THE AMENDMENT.
- THIS PROPERTY LIES WITHIN FEMA ZONE X, THE UNSHADDED AREA OF FIRM MAPS NO. 08303C026Z, 08303C030Z, 08303C035Z, 08303C040Z, AND 08303C045Z, REVISED MARCH 19, 2016. NO STRUCTURES SHALL BE PERMITTED IN THE APPROVED 100-YEAR FLOOD PLAIN. THE SITE ALSO HAS MAJOR DRAINAGE AREAS WITH BASIN AREAS GREATER THAN 10 ACRES ON-SITE.
- THIS PROPERTY IS WITHIN THE TOWN OF CASTLE ROCK BLUE, RED AND GREEN WATER PRESSURE ZONES. ALL WATERSHEDS (CONCRETE OR ASPHALT) SUBGRADE ACCESS ROADS CAPABLE OF WITHSTANDING THE IMPOSED LOADS OF FIRE APPARATUS (75,000 LB.) AND ALL REQUIRED FIRE HYDRANTS SHALL BE INSTALLED AND MADE SERVICEABLE PRIOR TO AND DURING ALL VERTICAL CONSTRUCTION.
- RIGHT-OF-WAY FOR INGRESS AND EGRESS FOR EMERGENCY VEHICLES IS GRANTED OVER, ACROSS, ON AND THROUGH ANY AND ALL PRIVATE ROADS AND DRIVES.

GENERAL NOTES

- ALL DEVELOPMENT ASSOCIATED WITH THE DAWSON TRAILS PDP SHALL COMPLY WITH ALL FEDERAL, STATE AND TOWN REGULATIONS REGARDING WILDFIRE INCLUDING THE MIGRATORY BIRD ACT AND BURROWING OWL SURVEY IF REQUIRED.
- UPDATED SOILS REPORTS SHALL BE SUBMITTED WITH EACH SITE DEVELOPMENT PLAN AND/OR PLAT.
- ALL IWA ACCESS GATES SHALL INCLUDE AN OPTICON SYSTEM OR OTHER SYSTEM APPROVED BY THE TOWN OF CASTLE ROCK FIRE DEPARTMENT.
- A WILDLAND/URBAN INTERFACE WILDFIRE VEGETATION MANAGEMENT PLAN (VMP), OR COMPLIANCE LETTER IS REQUIRED TO BE SUBMITTED FOR EACH PORTION OF THE PLANNED DEVELOPMENT WITH THE FIRST SDP OR CONSTRUCTION DRAWINGS FOR EVALUATION AND APPROVAL BY THE TOWN OF CASTLE ROCK FIRE DEPARTMENT. THIS PLAN SHALL BE DEVELOPED BY A DESIGN PROFESSIONAL FAMILIAR WITH WILDFIRE MITIGATION TECHNIQUES AND STANDARDS. REFER TO SHEET 13 AND THE TOWN OF CASTLE ROCK COMMUNITY WILDFIRE PROTECTION PLAN.

LEGAL DESCRIPTION

TWO (2) PARCELS OF LAND PORTIONS OF SECTIONS 15, 21, 22, 27, 28, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

THE BEARINGS FOR THIS DESCRIPTION ARE BASED ON THE NORTH LINE OF THE SOUTH HALF OF THE SOUTH HALF OF SECTION 21, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH P.M., BEING ASSUMED TO BEAR S89°55'56" E. FROM THE SOUTH 1/2 CORNER OF SAID SECTIONS 21 & 22, BEING MONUMENTED BY A PIPE WITH A 2" ALUMINUM CAP, STAMPED "S 6935" TO THE SOUTH 1/2 CORNER OF SAID SECTIONS 20 & 21, BEING MONUMENTED BY A PIPE WITH A 1" INCH ALUMINUM CAP, STAMPED "S 6935", WITH ALL BEARINGS CONTAINED HEREIN RELATIVE THERETO.

PARCEL 1:
 BEGINNING AT THE SOUTH 1/2 CORNER OF SAID SECTIONS 21 & 22, ALSO BEING A POINT ON THE SOUTH LINE OF TWIN OAKS, A SUBDIVISION PLAT RECORDED AT RECEPTION NO. 1619172, IN THE RECORDS OF THE DOUGLAS COUNTY CLERK AND RECORDS OFFICE; THENCE S 89°28'35" E. ALONG THE SOUTH LINE OF SAID TWIN OAKS SUBDIVISION AND ALONG THE NORTH LINE OF THE SOUTH HALF OF SAID SECTION 21, A DISTANCE OF 404.37 FEET TO A POINT ON THE WEST LINE OF THE TWIN OAKS ROAD RIGHT-OF-WAY AS DECATED BY SAID TWIN OAKS SUBDIVISION; THENCE ALONG THE SOUTH LINE OF SAID TWIN OAKS DRIVE RIGHT-OF-WAY AND ALONG THE SOUTH LINE OF THE TERRITORIAL ROAD RIGHT-OF-WAY, AS DECATED BY SAID TWIN OAKS SUBDIVISION, THE FOLLOWING FOUR (4) COURSES:

- S 02°01'48" E. A DISTANCE OF 52.10 FEET TO THE SOUTH LINE OF SAID TERRITORIAL ROAD RIGHT-OF-WAY;
- N 87°58'41" E. A DISTANCE OF 109.24 FEET TO A POINT OF CURVATURE;
- ALONG THE ARC OF A CURVE TO THE LEFT HAVING A RADIUS OF 245.68 FEET, A CENTRAL ANGLE OF 28°25'40" AND AN ARC LENGTH OF 122.89 FEET;
- N 53°21'57" E. A DISTANCE OF 29.34 FEET TO A POINT ON THE SOUTH LINE OF SAID TWIN OAKS SUBDIVISION;

THENCE S 89°28'35" E. ALONG SAID SOUTH LINE, A DISTANCE OF 174.33 FEET TO THE SOUTHWEST CORNER OF SAID TWIN OAKS SUBDIVISION; THENCE N 17°12'13" E. ALONG THE EAST LINE OF SAID TWIN OAKS SUBDIVISION, A DISTANCE OF 139.27 FEET TO A POINT ON THE EAST LINE OF SAID TERRITORIAL ROAD RIGHT-OF-WAY AND A POINT OF BEGINNING.

THENCE ALONG THE EAST LINE OF SAID TERRITORIAL ROAD RIGHT-OF-WAY THE FOLLOWING TWO (2) COURSES:

- ALONG THE ARC OF A NON-TANGENT CURVE TO THE LEFT HAVING A RADIUS OF 188.16 FEET, A CENTRAL ANGLE OF 31°27'18" AND AN ARC LENGTH OF 110.69 FEET, SUBTENDED BY A CHORD OF WHICH BEARS N 35°12'23" E. A DISTANCE OF 109.18 FEET;
- N 17°12'13" E. A DISTANCE OF 234.55 FEET TO A POINT ON THE SOUTH LINE OF THE TERRITORIAL ROAD RIGHT-OF-WAY AS DECATED BY THAT DEED RECORDED AT RECEPTION NO. 8816440, SAID DOUGLAS COUNTY RECORDS;

THENCE N 89°40'41" E. ALONG SAID SOUTH LINE, A DISTANCE OF 158.61 FEET TO A POINT ON THE WEST LINE OF THE BURLINGTON NORTHERN SANTA FE RAILROAD RIGHT-OF-WAY; THENCE S 15°17'57" W. ALONG SAID WEST LINE, A DISTANCE OF 85.33 FEET TO THE NORTHEAST CORNER OF THAT PARCEL OF LAND DESCRIBED IN THAT DEED RECORDED AT RECEPTION NO. 2004051363, SAID DOUGLAS COUNTY RECORDS;

THENCE ALONG THE NORTH, WEST AND SOUTH LINES OF SAID PARCEL THE FOLLOWING THREE (3) COURSES:

- S 89°40'41" E. A DISTANCE OF 678.73 FEET;
- S 02°01'48" E. A DISTANCE OF 506.54 FEET;
- S 89°28'35" E. A DISTANCE OF 515.85 FEET TO A POINT ON THE WEST LINE OF SAID BURLINGTON NORTHERN SANTA FE RAILROAD RIGHT-OF-WAY;

THENCE S 15°17'57" W. ALONG SAID WEST LINE, A DISTANCE OF 147.53 FEET TO A POINT ON THE EAST LINE OF THE NORTHEAST QUARTER OF SAID SECTION 18; THENCE N 02°01'48" W. ALONG SAID EAST LINE, A DISTANCE OF 226.55 FEET TO A POINT ON THE WEST LINE OF SAID BURLINGTON NORTHERN SANTA FE RAILROAD RIGHT-OF-WAY; THENCE S 15°17'57" W. ALONG SAID WEST LINE, A DISTANCE OF 749.53 FEET TO A POINT ON THE SOUTH LINE OF THE NORTH HALF OF SAID SECTION 33;

THENCE N 89°28'35" W. ALONG SAID SOUTH LINE, A DISTANCE OF 1213.28 FEET TO THE EAST QUARTER CORNER OF SAID SECTION 32, ALSO BEING THE NORTHEAST CORNER OF KEENE RANCH PLING NO. 2, SUBDIVISION PLAT RECORDED AT RECEPTION NO. 1925375, SAID DOUGLAS COUNTY RECORDS;

THENCE S 89°28'35" W. ALONG THE NORTH LINE OF SAID KEENE RANCH PLING NO. 2 AND ALONG THE SOUTH LINE OF THE NORTHEAST QUARTER OF SAID SECTION 32, A DISTANCE OF 243.68 FEET TO THE SOUTHWEST CORNER OF THAT PARCEL OF LAND DESCRIBED IN THAT DEED RECORDED AT RECEPTION NO. 2004051363, SAID DOUGLAS COUNTY RECORDS; THENCE ALONG THE EAST AND NORTH LINES OF SAID PARCEL OF LAND, THE FOLLOWING TWO (2) COURSES:

- N 02°01'48" W. A DISTANCE OF 306.73 FEET TO THE NORTHEAST CORNER OF SAID DEED;
- S 89°15'58" W. A DISTANCE OF 208.73 FEET TO A POINT ON THE WEST LINE OF THE NORTH LINE OF SAID KEENE RANCH PLING NO. 2; ALSO BEING A POINT ON THE EAST LINE OF SAID KEENE RANCH PLING NO. 2;

THENCE N 02°01'48" W. ALONG THE EAST LINE OF SAID KEENE RANCH PLING NO. 1, ALONG THE EAST LINE OF KEENE RANCH PLING NO. 2, A SUBDIVISION PLAT RECORDED AT RECEPTION NO. 9638479, SAID DOUGLAS COUNTY RECORDS, AND ALONG THE WEST LINE OF THE NORTHEAST QUARTER OF SAID SECTION 32, A DISTANCE OF 295.74 FEET TO THE NORTH QUARTER CORNER OF SAID SECTION 32;

THENCE N 02°01'48" W. ALONG THE EAST LINE OF SAID KEENE RANCH PLING NO. 2 AND ALONG THE WEST LINE OF THE EAST HALF OF SAID SECTION 29, A DISTANCE OF 308.92 FEET TO THE NORTH QUARTER CORNER OF SAID SECTION 29, BEING THE NORTHEAST CORNER OF SAID KEENE RANCH PLING NO. 2 PLAT, AND THE SOUTHWEST CORNER OF CASTLE MESA SOUTH, A SUBDIVISION PLAT RECORDED AT RECEPTION NO. 145078, SAID DOUGLAS COUNTY RECORDS;

THENCE S 89°21'42" E. ALONG THE NORTH LINE OF THE EAST HALF OF SAID SECTION 29 AND ALONG THE SOUTH LINE OF SAID CASTLE MESA SOUTH SUBDIVISION, A DISTANCE OF 246.03 FEET TO THE SOUTHWEST CORNER OF SAID CASTLE MESA SOUTH SUBDIVISION, BEING THE SOUTHWEST CORNER OF SAID SECTION 21;

THENCE N 02°01'48" W. ALONG THE EAST LINE OF SAID CASTLE MESA SOUTH SUBDIVISION AND ALONG THE WEST LINE OF THE SOUTH HALF OF THE SOUTH HALF OF SAID SECTION 21, A DISTANCE OF 1132.70 FEET TO THE SOUTH 1/2 CORNER OF SAID SECTIONS 20 & 21, BEING THE SOUTHWEST CORNER OF SAID TWIN OAKS SUBDIVISION;

THENCE S 89°55'56" E. ALONG THE SOUTH LINE OF SAID TWIN OAKS SUBDIVISION AND ALONG THE NORTH LINE OF THE SOUTH HALF OF THE SOUTH HALF OF SAID SECTION 21, A

DISTANCE OF 578.17 FEET TO THE POINT OF BEGINNING; LESS AND EXCEPT THE FOLLOWING TWO (2) PARCELS OF LAND.

TWO (2) PARCELS OF LAND, AS DESCRIBED IN SAID DEED RECORDED AT RECEPTION NO. 30005155, SAID DOUGLAS COUNTY RECORDS, BEING A PORTION OF THE SOUTH HALF OF SECTION 28, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

THE BEARINGS FOR THESE EXCEPTION PARCELS ARE BASED ON THE SOUTH LINE OF SECTION 28, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH P.M., BEING ASSUMED TO BEAR S89°47'47" E. FROM THE SOUTHWEST CORNER OF SAID SECTION 28, BEING MONUMENTED BY A 1" PIPE WITH A 2" ALUMINUM CAP STAMPED "S 6935" TO THE SOUTHEAST CORNER OF SAID SECTIONS 28, BEING MONUMENTED BY #6 REBAR WITH A 2-1/2" ALUMINUM CAP, STAMPED "S 6935", WITH ALL BEARINGS CONTAINED HEREIN RELATIVE THERETO.

COMMENCING AT THE SOUTHWEST CORNER OF SAID SECTION 28, THENCE N 65°29'17" E. A DISTANCE OF 1242.53 FEET TO THE POINT OF BEGINNING;

THENCE N 02°01'48" W. A DISTANCE OF 300.73 FEET;

THENCE S 89°47'47" E. A DISTANCE OF 208.73 FEET;

THENCE S 00°45'02" E. A DISTANCE OF 208.73 FEET;

THENCE N 89°47'47" E. A DISTANCE OF 208.73 FEET TO THE POINT OF BEGINNING; ALSO EXCEPTING THE FOLLOWING PARCELS:

COMMENCING AT THE SOUTHEAST CORNER OF SAID SECTION 28, THENCE N 40°06'49" E. A DISTANCE OF 1745.27 FEET TO THE POINT OF BEGINNING;

THENCE N 87°57'41" W. A DISTANCE OF 208.73 FEET;

THENCE N 02°45'11" W. A DISTANCE OF 208.73 FEET;

THENCE S 89°47'47" E. A DISTANCE OF 208.73 FEET;

THENCE S 00°21'21" E. A DISTANCE OF 208.73 FEET TO THE POINT OF BEGINNING; CONTAINING A NET AREA OF 81,902.81 SQUARE FEET OR 1,880.230 ACRES, MORE OR LESS.

PARCEL 2:
 COMMENCING AT THE SOUTH 1/2 CORNER OF SAID SECTIONS 21 & 22, ALSO BEING A POINT ON THE SOUTH LINE OF TWIN OAKS, A SUBDIVISION PLAT RECORDED AT RECEPTION NO. 1619172, IN THE RECORDS OF THE DOUGLAS COUNTY CLERK AND RECORDS OFFICE;

THENCE N 89°40'41" E. A DISTANCE OF 1311.13 FEET TO A POINT ON THE EAST LINE OF SAID TWIN OAKS PLAT AND A POINT ON THE NORTH LINE OF THE TERRITORIAL ROAD RIGHT-OF-WAY, AS DECATED BY THAT DEED RECORDED AT RECEPTION NO. 8816440, SAID DOUGLAS COUNTY RECORDS AND THE POINT OF BEGINNING;

THENCE ALONG THE EAST LINE OF SAID TWIN OAKS PLAT, THE FOLLOWING THREE (3) COURSES:

- N 17°12'13" E. A DISTANCE OF 557.93 FEET;
- N 89°27'27" W. A DISTANCE OF 65.00 FEET;
- N 00°27'25" E. A DISTANCE OF 1329.37 FEET TO THE SOUTHWEST CORNER OF LOT 3, SAID TWIN OAKS PLAT;

THENCE N 03°03'32" W. ALONG THE WEST LINE OF SAID LOT 3, A DISTANCE OF 587.55 FEET TO THE NORTHWEST CORNER OF SAID LOT 3, BEING A POINT OF CURVATURE ON THE SOUTH LINE OF THE BRIDGES LANE RIGHT-OF-WAY, AS DECATED BY SAID TWIN OAKS PLAT;

THENCE ALONG THE PORTIONS OF BRIDGES LANE W/CAVED BY ORDINANCE NO. 46, 24, RECORDED IN BOOK 860 AT PAGE 970, SAID DOUGLAS COUNTY RECORDS THE FOLLOWING TWO (2) COURSES:

- N 89°55'56" W. A DISTANCE OF 300.00 FEET TO A POINT OF NON-TANGENT CURVATURE;
- ALONG THE ARC OF A NON-TANGENT CURVE TO THE RIGHT HAVING A RADIUS OF 329.30 FEET, A CENTRAL ANGLE OF 27°10'35" AND AN ARC LENGTH OF 156.74 FEET, SUBTENDED BY A CHORD OF WHICH BEARS N 63°42'30" E. A DISTANCE OF 155.24 FEET;

THENCE N 10°27'27" W. ALONG THE WEST LINE OF LOT 4, SAID TWIN OAKS PLAT, A DISTANCE OF 587.67 FEET TO THE NORTHWEST CORNER OF SAID LOT 4, ALSO BEING THE WEST 1/2 CORNER OF SAID SECTIONS 15 & 22;

THENCE S 89°27'27" E. ALONG THE SOUTH LINE OF THE SOUTHWEST QUARTER OF SAID SECTION 15, A DISTANCE OF 800.07 FEET TO THE SOUTHWEST CORNER OF THAT PARCEL OF LAND DESCRIBED AS PARCEL C IN THAT DEED RECORDED AT RECEPTION NO. 201068282, SAID DOUGLAS COUNTY RECORDS;

THENCE ALONG THE WEST AND NORTH LINES OF PARCELS E, F & G THE FOLLOWING FOUR (4) COURSES:

- N 02°01'48" E. A DISTANCE OF 900.81 FEET;
- S 89°47'47" E. ALONG THE NORTH LINES OF PARCELS E AND F, A DISTANCE OF 1014.77 FEET TO THE SOUTHWEST CORNER OF THAT PARCEL OF LAND DESCRIBED AS PARCEL G;
- N 02°31'34" E. A DISTANCE OF 845.72 FEET;
- S 89°47'47" E. A DISTANCE OF 408.15 FEET TO A POINT ON THE WEST LINE OF THE BURLINGTON NORTHERN SANTA FE RAILROAD RIGHT-OF-WAY AND A POINT OF NON-TANGENT CURVATURE;

THENCE ALONG THE WEST LINE OF SAID BURLINGTON NORTHERN SANTA FE RAILROAD RIGHT-OF-WAY THE FOLLOWING TWO (2) COURSES:

- ALONG THE ARC OF A NON-TANGENT CURVE TO THE LEFT HAVING A RADIUS OF 5779.58 FEET, A CENTRAL ANGLE OF 05°35'04" AND AN ARC LENGTH OF 563.93 FEET, SUBTENDED BY A CHORD OF WHICH BEARS S 18°04'54" W. A DISTANCE OF 563.11 FEET;
- S 15°17'57" W. A DISTANCE OF 4536.06 FEET TO A POINT ON THE NORTH LINE OF SAID TERRITORIAL ROAD RIGHT-OF-WAY;

THENCE S 89°47'47" W. ALONG SAID NORTH LINE, A DISTANCE OF 1520.83 FEET TO THE POINT OF BEGINNING;

CONTAINING AN AREA OF 7,993.235 SQUARE FEET OR 183.499 ACRES, MORE OR LESS. OVERALL DAWSON RIDGE PROJECT PERIMETER DESCRIPTION CONTAINS AN AREA OF 49,866.5 SQUARE FEET OR 2,032.529 ACRES, MORE OR LESS.

DAWSON TRAILS PLANNED DEVELOPMENT PLAN / PROJECT NO. PDP21-0001



1818 Broadway Blvd
 Denver, CO 80202
 303.733.1414
 www.norrisdesign.com

APPLICANT
 WESTSIDE INVESTMENT PARTNERS
 4100 E. MISSISSIPPI AVE
 DENVER, CO 80248
 303.944.8900

ENGINEER & SURVEYOR
 CORE CONSULTANTS
 3475 S. BROADWAY
 ENGLEWOOD, CO 80151
 303.726.8600



DAWSON TRAILS
 PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
 AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN

DATE
PDP-01-07/08/2021
PDP-02-12/03/2021
PDP-03-04/13/2022
PDP-04-05/27/2022
PDP-05-06/09/2022

SHEET TITLE

COVER

SHEET 1 OF 2

Exhibit 2

DAWSON TRAILS PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
THREE PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 27, 29, 32, 33 & 34 TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

OWNERSHIP CERTIFICATION:

THE UNDERSIGNED ARE ALL THE OWNERS OF CERTAIN LANDS IN THE TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS AND STATE OF COLORADO DESCRIBED HEREIN

DAWSON TRAILS II LLC
SIGNED THIS _____ DAY OF _____, 20____

NOTARY BLOCK
SUBSCRIBED AND SWORN TO BEFORE ME THIS _____ DAY OF _____, 20____

BY _____ AS _____ OF THE DAWSON TRAILS II LLC, A COLORADO LIMITED LIABILITY COMPANY

WITNESS MY HAND AND OFFICIAL SEAL.

NOTARY PUBLIC _____

MY COMMISSION EXPIRES: _____

OWNERSHIP CERTIFICATION:

THE UNDERSIGNED ARE ALL THE OWNERS OF CERTAIN LANDS IN THE TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS AND STATE OF COLORADO DESCRIBED HEREIN

DAWSON TRAILS II LLC
SIGNED THIS _____ DAY OF _____, 20____

NOTARY BLOCK
SUBSCRIBED AND SWORN TO BEFORE ME THIS _____ DAY OF _____, 20____

BY _____ AS _____ OF THE DAWSON TRAILS II LLC, A COLORADO LIMITED LIABILITY COMPANY

WITNESS MY HAND AND OFFICIAL SEAL.

NOTARY PUBLIC _____

MY COMMISSION EXPIRES: _____

OWNERSHIP CERTIFICATION:

THE UNDERSIGNED ARE ALL THE OWNERS OF CERTAIN LANDS IN THE TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS AND STATE OF COLORADO DESCRIBED HEREIN

TOWN OF CASTLE ROCK, A MUNICIPAL CORPORATION

BY _____ MAYOR

ATTEST:

TOWN CLERK _____

SIGNED THIS _____ DAY OF _____, 20____

NOTARY BLOCK
SUBSCRIBED AND SWORN TO BEFORE ME THIS _____ DAY OF _____, 20____

BY _____ AS MAYOR AND BY _____ AS TOWN CLERK

WITNESS MY HAND AND OFFICIAL SEAL.

NOTARY PUBLIC _____

MY COMMISSION EXPIRES: _____

PLANNING COMMISSION RECOMMENDATION:

THIS PLANNED DEVELOPMENT PLAN WAS RECOMMENDED FOR APPROVAL BY THE PLANNING COMMISSION OF THE TOWN

OF CASTLE ROCK, COLORADO ON THE _____ DAY OF _____, 20____

CHAIR _____ DATE _____

ATTEST:

DIRECTOR OF DEVELOPMENT SERVICES _____ DATE _____

TOWN COUNCIL APPROVAL:
THIS PLANNED DEVELOPMENT PLAN WAS APPROVED BY THE TOWN COUNCIL OF THE TOWN OF CASTLE ROCK, COLORADO, ON THE

_____ DAY OF _____, 20____

MAYOR _____ DATE _____

ATTEST:

TOWN CLERK _____ DATE _____

LIENHOLDER SUBORDINATION CERTIFICATE:

THE UNDERSIGNED ARE ALL THE MORTGAGEES AND LIENHOLDERS OF CERTAIN LANDS IN THE TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS AND STATE OF COLORADO DESCRIBED HEREON. THE UNDERSIGNED BENEFICIARY OF THE LIEN

CREATED BY THE INSTRUMENT RECORDED _____ AT

RECEPTION NO. _____ DOUGLAS COUNTY, COLORADO, SUBORDINATES THE SUBJECT LIEN TO THE TERMS, CONDITIONS AND RESTRICTIONS OF THIS DOCUMENT.

BWG LLC, A COLORADO LIMITED LIABILITY COMPANY

SIGNED THIS _____ DAY OF _____, 20____

NOTARY BLOCK SUBSCRIBED AND SWORN TO BEFORE ME THIS _____ DAY OF _____, 20____

BY _____ AS _____ OF _____

WITNESS MY HAND AND OFFICIAL SEAL.

NOTARY PUBLIC _____

MY COMMISSION EXPIRES: _____

DOUGLAS COUNTY CLERK AND RECORDER'S CERTIFICATE:

THIS PLANNED DEVELOPMENT PLAN WAS FILED FOR RECORD IN THE OFFICE OF THE COUNTY CLERK AND RECORDER OF DOUGLAS

COUNTY AT _____ ON THE _____ DAY OF _____, 20____ AT RECEPTION NO. _____

DOUGLAS COUNTY CLERK AND RECORDER

BY: _____

SURVEYOR'S CERTIFICATE:

I, _____ A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF COLORADO, DO HEREBY CERTIFY THAT THE SURVEY AND LEGAL DESCRIPTION REPRESENTED BY THIS PLANNED DEVELOPMENT PLAN WAS MADE UNDER MY SUPERVISION AND THE MONUMENTS SHOWN THEREON ACTUALLY EXIST AND THIS PLANNED DEVELOPMENT PLAN ACCURATELY REPRESENTS THAT SURVEY.

REGISTERED LAND SURVEYOR _____ DATE _____

TITLE CERTIFICATION:

I, _____ AN AUTHORIZED REPRESENTATIVE OF LAND TITLE GUARANTEE COMPANY A TITLE INSURANCE COMPANY LICENSED TO DO BUSINESS IN THE STATE OF COLORADO, HAVE MADE AN EXAMINATION OF THE PUBLIC RECORDS AND STATE THAT ALL OWNERS, MORTGAGES AND LIENHOLDERS OF THE PROPERTY ARE LISTED IN THE CERTIFICATE OF OWNERSHIP AND LIENHOLDER SUBORDINATION CERTIFICATE.

AUTHORIZED REPRESENTATIVE _____

TITLE COMPANY _____

SIGNED THIS _____ DAY OF _____, 20____

NOTARY BLOCK

SUBSCRIBED AND SWORN TO BEFORE ME THIS _____ DAY OF _____, 20____

BY _____ AS AUTHORIZED REPRESENTATIVE OF _____

WITNESS MY HAND AND OFFICIAL SEAL.


NOTARY PUBLIC _____

MY COMMISSION EXPIRES: _____



WESTSIDE INVESTMENT PARTNERS
4100 E MISSISSIPPI AVE
SUITE 500
CASTLE ROCK, CO 80045
303-681-8600

ENGINEER & SURVEYOR
CORE
CORE CONSULTANTS
3475 S BROADWAY
ENGLEWOOD, CO 80113
303-730-5960



DAWSON TRAILS
PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE:
PDE-01-07-08/2021
PDE-02-12-03/2021
PDE-03-04-13/2022
PDE-04-05-27/2022
PDE-05-06-09/2022

SHEET TITLE:
OWNERSHIP
CERTIFICATION

SHEET
2 OF 20

DESIGNED BY
DRAWN BY

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
 TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 27, 27, 28, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 61 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

PLANNER/LANDSCAPE ARCHITECT
 NORRIS DESIGN
 1001 1/2 UNIVERSITY AVENUE, SUITE 100
 DENVER, CO 80202

APPLICANT
 WESTFIELD INVESTMENT PARTNERS
 4100 E. MISSISSIPPI AVE
 SUITE 501
 DENVER, CO 80214
 303.951.8270

ENGINEER & SURVEYOR
 CORE CONSULTANTS
 3412 S. BROADWAY
 ENGLEWOOD, CO 80110
 303.735.5460

DAWSON TRAILS

DAWSON TRAILS
 PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
 (AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE:
 PDP-01.07.28/2021
 PDP-02.12.03/2021
 PDP-03.04.13/2022
 PDP-04.05.27/2022
 PDP-05.06.09/2022

SHEET TITLE:
 OVERALL PD PLAN

SHEET
 3 OF 20


OPEN SPACE AND PUBLIC LAND SUMMARY

	ACREAGE	% OF TOTAL
PUBLIC LAND		
STATE	0.00	0.00%
FEDERAL	0.00	0.00%
OPEN SPACE		
100 YEAR FLOODPLAIN (TOWN OF CASTLE ROCK)	30.9	1.2%
100 YEAR FLOODPLAIN (PEMA)	1.2	0.0%
TRANSITION ZONE	20.7	0.8%
MODERATE SKYLINE	1.1	0.0%
MINOR SKYLINE	0.0	0.0%
OPEN SPACE AND PUBLIC LAND TOTAL	52.9	2.0%

NOTE: THE TOTAL SKYLINE DEPENDENT ON THE SKYLINE DETERMINED BY THE DEVELOPER.

LEGEND

- PROPERTY BOUNDARY
- PLANNING AREA BOUNDARY
- CHARACTER AREA BOUNDARY
- MAJOR DRAINAGEWAY
- TRANSITION ZONE
- MODERATE SKYLINE
- MINOR SKYLINE
- 100 YEAR FLOODPLAIN (TOWN OF CASTLE ROCK)
- 100 YEAR FLOODPLAIN (PEMA)
- PROPOSED ARTERIAL RIGHT OF WAY
- FUTURE COLLECTOR RIGHT OF WAY
- 5' NATURAL SURFACE TRAIL
- 10' HARD SURFACE TRAIL



DAWSON TRAILS PLANNED DEVELOPMENT PLAN | PROJECT NO. PDP21-0001


CHECKED BY: M.B. SWY
 DRAWN BY: D.J. JR.

DAWSON TRAILS


PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
 TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

KEY MAP




Unofficial Copy



LEGEND

	PROPERTY BOUNDARY		TRANSITION ZONE		PROPOSED ARTERIAL RIGHT OF WAY
	PLANNING AREA BOUNDARY		MODERATE SKYLINE		FUTURE COLLECTOR RIGHT OF WAY
	CHARACTER AREA BOUNDARY		MINOR SKYLINE		5' NATURAL SURFACE TRAIL
	MAJOR DRAINAGEWAY		100 YEAR FLOODPLAIN (TOWN OF CASTLE ROCK)		10' HARD SURFACE TRAIL
			100 YEAR FLOODPLAIN (FEMA)		



DAWSON TRAILS PLANNED DEVELOPMENT PLAN PROJECT NO. PDP21-0501

PLANNED DEVELOPMENT
 ARCHITECTURE
NORRIS DESIGN
 Public & Commercial Architecture & Planning

APPLICANT

 WESTSIDE INVESTMENT PARTNERS
 4102 E. 118TH AVENUE
 SUITE 500
 DENVER, CO 80231
 303.981.9300

ENGINEER & SURVEYOR
CORE
 CONSULTANTS
 3475 S. BROADWAY
 ENGLEWOOD, CO 80113
 303.739.5400

DAWSON TRAILS

DAWSON TRAILS
 PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
 (AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE

PDP-01-07/08/2021
PDP-02-12/03/2021
PDP-03-04/13/2022
PDP-04-05/27/2022
PDP-05-08/09/2022

SHEET TITLE
 PD PLAN

SHEET
 4 OF 20


CHECKED BY: MB, SW
 DRAWN BY: DJ, JR

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
 TWO PARCELS OF LAND BEING ALL OF SECTION 26 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 4 SOUTH, RANGE 67 WEST OF THE 6TH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

KEY MAP




Unofficial Copy

PD - PLANNED DEVELOPMENT
(KEENE RANCH)
DOUGLAS COUNTY


ER - ESTATE RESIDENTIAL
(CASTLE ROCK)
DOUGLAS COUNTY

LRR - LARGE RURAL RESIDENTIAL
(TWIN OAKS)
DOUGLAS COUNTY



LEGEND

- | | | | | | |
|--|-------------------------|--|---|--|--------------------------------|
| | PROPERTY BOUNDARY | | TRANSITION ZONE | | PROPOSED ARTERIAL RIGHT OF WAY |
| | PLANNING AREA BOUNDARY | | MODERATE SKYLINE | | FUTURE COLLECTOR RIGHT OF WAY |
| | CHARACTER AREA BOUNDARY | | MINOR SKYLINE | | 5' NATURAL SURFACE TRAIL |
| | MAJOR DRAINAGE WAY | | 10' HARD SURFACE TRAIL | | 100 YEAR FLOODPLAIN (FEMA) |
| | | | 100 YEAR FLOODPLAIN (TOWN OF CASTLE ROCK) | | |



DAWSON TRAILS PLANNED DEVELOPMENT PLAN | PROJECT NO. PDP21-0001

PLANNED LANDSCAPE ARCHITECT
NORRIS DESIGN
 THE LANDSCAPE ARCHITECTS

APPLICANT

 WEST'S DE INVESTMENT PARTNERS
 1108 E MISSISSIPPI AVE
 SUITE 303
 DENVER, CO 80246
 303.984.9400

ENGINEER & SURVEYOR

CORE
 CORE CONSULTANTS
 3473 S BROWNWAY
 ENGLEWOOD, CO 80113
 303.730.5900

DAWSON TRAILS

DAWSON TRAILS
 PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
 (AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE
 PDP-01 02/08/2021
 PDP-02 12/03/2021
 PDP-03 04/14/2022
 PDP-04 08/27/2022
 PDP-05 06/09/2022

SHEET TITLE:
 PD PLAN

SHEET
 5 OF 20



CHECKED BY: MS, SW
 DRAWN BY: CJ, JR

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS


(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
 TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

KEY MAP



LEGEND

- PROPERTY BOUNDARY
- PLANNING AREA BOUNDARY
- CHARACTER AREA BOUNDARY
- MAJOR DRAINAGEWAY
- TRANSITION ZONE
- MODERATE SKYLINE
- MINOR SKYLINE
- 100 YEAR FLOODPLAIN (TOWN OF CASTLE ROCK)
- PROPOSED ARTERIAL RIGHT OF WAY
- FUTURE COLLECTOR RIGHT OF WAY
- 5' NATURAL SURFACE TRAIL
- 10' HARD SURFACE TRAIL
- 100 YEAR FLOODPLAIN (FEMA)



CHECKED BY: MB, SW, DJ, JR
DRAWN BY:

PLANNED LANDSCAPE ARCHITECT
NORRIS DESIGN
 1115 S. 10TH ST.
 SUITE 200
 CASTLE ROCK, CO 80108
 303.984.5900

APPLICANT

 WESTSIDE INVESTMENT PARTNERS
 4102 E. MISSOURI AVE
 SUITE 800
 DENVER, CO 80216
 303.984.5900

ENGINEER & SURVEYOR

CORE
 CONSULTANTS
 3472 S. BROADWAY
 ENGLEWOOD CO 80113
 303.723.5260

DAWSON TRAILS

DAWSON TRAILS
 PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
 (AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE:
 PDP-01.07.08/2021
 PDP-02.12.01/2021
 PDP-03.04.13/2022
 PDP-04.05.27/2022
 PDP-05.05.08/2022

SHEET TITLE
 PD PLAN



SHEET
 6 OF 20

DAWSON TRAILS


PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 6 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

KEY MAP



LEGEND		
	PROPERTY BOUNDARY	
	PLANNING AREA BOUNDARY	
	CHARACTER AREA BOUNDARY	
	MAJOR DRAINAGEWAY	
	TRANSITION ZONE	
	MODERATE SKYLINE	
	MINOR SKYLINE	
	100 YEAR FLOODPLAIN (TOWN OF CASTLE ROCK)	
	PROPOSED ARTERIAL RIGHT OF WAY	
	FUTURE COLLECTOR RIGHT OF WAY	
	5' NATURAL SURFACE TRAIL	
	10' HARD SURFACE TRAIL	
	100 YEAR FLOODPLAIN (FEMA)	



DAWSON TRAILS PLANNED DEVELOPMENT PLAN PROJECT NO. PDP21-0001

PLANNER/LANDSCAPE ARCHITECT
NORRIS DESIGN
1000 S. W. 10th Ave.
Suite 100
Denver, CO 80202
303.955.1000

APPLICANT
WESTSIDE INVESTMENT PARTNERS
4100 E. MISSISSIPPI AVE
SUITE 500
DENVER, CO 80246
303.955.1000

ENGINEER & SURVEYOR
CORE CONSULTANTS
3473 S. BROADWAY
ENGLEWOOD, CO 80113
303.730.9400

DAWSON TRAILS

DAWSON TRAILS
PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE
PDP-01 07/08/2021
PDP-02 12/03/2021
PDP-03 04/14/2022
PDP-04 08/27/2022
PDP-05 08/02/2022

SHEET TITLE
PD PLAN

SHEET
7 OF 20



CHECKED BY: MB, SW
DRAWN BY: DJ, JR

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
 TWO PARCELS OF LAND BEING ALL OF SECTION 29 AND PORTIONS OF SECTIONS 15, 21, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 81 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

KEY MAP



PLANNERS-GATE ARCHITECT
 NORRIS DESIGN

APPLICANT
 WESTSIDE INVESTMENT PARTNERS
 410 E. MISSISSIPPI AVE
 SUITE 500
 DENVER, CO 80202
 303.564.9600

ENGINEER & SURVEYOR
 CORE CONSULTANTS
 3475 S. BROADWAY
 ENGLEWOOD, CO 80113
 303.730.5949

DAWSON TRAILS

DAWSON TRAILS
 PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
 (AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE:
 PDP-01-07-2021
 PDP-02-12-2021
 PDP-03-04-2022
 PDP-04-05-2022
 PDP-05-08-2022

SHEET TITLE:
 PD PLAN

SHEET
 8 OF 20



DAWSON TRAILS PLANNED DEVELOPMENT PLAN - PROJECT NO. PDP21-0011

DESIGNED BY: DRAUGHTING

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
 TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 32, 33 & 34, TOWNSHIP 9 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

PLANNED LANDSCAPE ARCHITECTURE
MORRIS DESIGN
 1000 E. 10TH AVENUE
 DENVER, CO 80202

APPLICANT
WESTSIDE INVESTMENTS PARTNERS
 4100 E. 10555TH AVE
 SUITE 600
 DENVER, CO 80231
 303.984.9600

ENGINEER & SURVEYOR
CORE
 3417 S. BROADWAY
 ENGLEWOOD, CO 80113
 303.739.9500

DAWSON TRAILS


DAWSON TRAILS
 PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
 (AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE:
 PDP-01 07/09/2021
 PDP-02 12/09/2021
 PDP-03 04/13/2022
 PDP-04 05/27/2022
 PDP-05 06/02/2022

SHEET TITLE
 OPEN SPACE, P.L.D. & TRAILS PLAN

SHEET
 9 OF 20

Unofficial



NOTES

- TRAILS SHOWN ON THIS PLAN EXHIBIT REPRESENT CONCEPTUAL ALIGNMENTS THAT WILL BE FINALIZED DURING THE SITE DEVELOPMENT PLAN/PLAT/CDS PROCESS FOR EACH PHASE OF THE PROJECT. THESE ALIGNMENTS REPRESENT A CONNECTED PEDESTRIAN SYSTEM THAT INCLUDES BOTH TRAILS THROUGH OPEN SPACE AREAS AND TRAILS/SIDEWALKS ADJACENT TO ROADS AND STREETS. CONNECTIONS TO EACH PLANNING AREA WILL BE MADE TO FACILITATE ACCESS. AS APPROPRIATE, SOME TRAIL ALIGNMENTS MAY CHANGE SIGNIFICANTLY BASED ON TOPOGRAPHY/SLOPE/GRADING/DRAINAGE, EXISTING VEGETATION, CONSTRUCTABILITY, AND OTHER FACTORS CONSIDERED AT THE TIME THEY ARE DESIGNED/ENGINEERED.
- TRAIL AND OPEN SPACE IMPROVEMENTS WILL BE CONSTRUCTED IN A PHASED MANNER IN ACCORDANCE WITH THE DEVELOPMENT AGREEMENT AND IN COORDINATION WITH PLATTING/CDS AND ASSOCIATED CONSTRUCTION TIMING OF IMPROVEMENTS WITH THOSE SUBDIVISION PLINGS. GENERALLY, AS PRIVATE DEVELOPMENT AREAS ARE PLANNED/ENGINEERED, REQUIRED IMPROVEMENTS ASSOCIATED WITH ADJACENT PL-1, PL-2 AND OSP (OPEN SPACE) AREAS THAT ARE BEING PLATTED WILL BE COORDINATED AND PLANNED/DESIGNED/ENGINEERED TO THE LEVEL REQUIRED BASED ON TOWN APPROVAL PERMITTING OR CONSTRUCTION TIMING NEEDS.
- ATTACHED AND DETACHED SIDEWALKS ARE NOT INCLUDED IN THE TRAIL SYSTEM.
- PRIVATE OPEN SPACE RECLASSIFICATION PERMITTED WITH TOWN APPROVAL. A LIMITED AMOUNT (MAXIMUM 20 ACRES) OF LAND DEPICTED AS PL-1 AND/OR PL-2 IN THIS PDP SHALL BE PERMITTED TO BE RECLASSIFIED AS PRIVATE OPEN SPACE (OSP). RECLASSIFICATION OF ANY FUTURE OSP TRACTS WILL BE COORDINATED WITH THE TOWN, AS APPROPRIATE, DURING THE SITE DEVELOPMENT PLAN/PLAT STAGE OF THE DEVELOPMENT REVIEW PROCESS AS MORE DETAIL IS KNOWN TO DETERMINE WHERE THESE SITES SHOULD BE LOCATED. ANY PORTION OF THE POTENTIAL 20 ACRES THAT ARE NOT RECLASSIFIED AND PLATTED AS OSP SHALL REMAIN AS PL-1 OR PL-2 AND SHALL BE PLATTED/DEDICATED TO THE TOWN. REPLACEMENT OF RECLASSIFIED ACRES IS NOT REQUIRED.
- EXISTING VEGETATION TO BE RETAINED WILL BE DESIGNATED ON SITE DEVELOPMENT PLANS.

OPEN SPACE AND PUBLIC LAND SUMMARY

PUBLIC LAND		
	ACREAGE	% OF TOTAL
PL-1 (DEDICATED TO TOWN)	227.8	11.9%
OPEN SPACE		
PL-2 (DEDICATED TO TOWN)	462.2	22.4%
OSP (PRIVATE)	70.8	3.4%
SUBTOTAL	533.0	25.8%
FUTURE OPEN SPACE (1)	215.0	10.4%
OPEN SPACE TOTAL	748.0	36.2%
OPEN SPACE AND PUBLIC LAND TOTAL	975.8	47.3%

NOTE: (1) FUTURE OPEN SPACE DESIGNATION (PL-1, PL-2, OSP) TO BE DETERMINED AT TIME OF PLAT

PARCEL SUMMARY

PUBLIC LAND		
	ACREAGE	% OF PROPERTY
PL-1-01	15	0.2%
PL-1-02	5.0	0.4%
PL-1-03	17.0	0.8%
PL-1-04	122	5.9%
PL-1-05	130	2.9%
PL-1-06	7.5	0.4%
PL-1-07	44.1	2.1%
PL-1-08	5.5	0.2%
PL-1-09	170	0.6%
PL-1-10	187	5.2%
PL-1 TOTAL	227.8	11.9%

OPEN SPACE		
	ACREAGE	% OF PROPERTY
PL-2-01	362.9	18.0%
PL-2-02	27.2	1.3%
PL-2-03	0.9	0.0%
PL-2-04	5.3	0.3%
PL-2-05	4.1	0.2%
PL-2-06	44	0.2%
PL-2-07	27.6	1.3%
PL-2-08	3.9	0.0%
PL-2 TOTAL	462.2	22.4%


OSP (PRIVATE)		
	ACREAGE	% OF PROPERTY
OSP-1	2.1	0.1%
OSP-2	4.1	0.2%
OSP-3	17.3	0.8%
OSP-4	3.6	0.2%
OSP-5	4.5	0.2%
OSP-6	11.7	0.6%
OSP-7	19.8	0.9%
OSP-8	4.1	0.2%
OSP TOTAL	70.8	3.4%

FUTURE OPEN SPACE (1)	215.0	10.4%
OPEN SPACE TOTAL	748.0	36.2%
OPEN SPACE & PUBLIC LAND TOTAL	975.8	47.3%

NOTE: (1) FUTURE OPEN SPACE DESIGNATION (PL-1, PL-2, OSP) TO BE DETERMINED AT TIME OF PLAT

LEGEND

- PROPERTY BOUNDARY
- PLANNING AREA BOUNDARY
- CHARACTER AREA BOUNDARY
- PROPOSED ARTERIAL RIGHT OF WAY
- FUTURE COLLECTOR RIGHT OF WAY
- PROPOSED PLD
- PROPOSED OPEN SPACE (PL-2 AND OSP)
- HIGHPOINTS
- 100 YEAR FLOODPLAIN (TOWN OF CASTLE ROCK)
- 100 YEAR FLOODPLAIN (FEMA)
- 5' NATURAL SURFACE TRAIL
- 10' HARD SURFACE TRAIL
- MAJOR DRAINAGEWAY
- REGIONAL DETENTION POND (APPROXIMATE LOCATION)




CHECKED BY: MRS. BRYAN J. JR.
 DRAWN BY:

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS


(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
 TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH RANGE 61 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO



LEGEND

- | | | |
|---------------------|-----------------------|---|
| PROPERTY BOUNDARY | HIGH HABITAT | MAJOR DRAINAGEWAY |
| HISTORIC RAILROAD | LOW HABITAT | 100 YEAR FLOODPLAIN (TOWN OF CASTLE ROCK) |
| EXISTING VEGETATION | ELEV 6750 HIGHPPOINTS | 100 YEAR FLOODPLAIN (FEMA) |

* NOTE: SOURCE DOCUMENT IS DOUGLAS COUNTY 2040 COMPREHENSIVE MASTER WILDLIFE RESOURCES MAP PLAN



DAWSON TRAILS PLANNED DEVELOPMENT PLAN | PROJECT NO. PDP21-0201



WESTSIDE INVESTMENT PARTNERS
 4100 E. MISSISSIPPI AVE
 SUITE 500
 DENVER, CO 80246
 303.684.8800

ENGINEER & SURVEYOR
CORE
 CONSULTANTS
 3473 S BROADWAY
 ENGLEWOOD, CO 80113
 303.733.9500



DAWSON TRAILS
 PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
 (AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE:
<u>PDP-01 02/08/2021</u>
<u>PDP-02 12/09/2021</u>
<u>PDP-03 04/13/2022</u>
<u>PDP-04 05/27/2022</u>
<u>PDP-05 06/03/2022</u>

SHEET TITLE
 NATURAL FEATURES MAP

SHEET
 10 OF 20


CREATED BY: [unreadable] DWG NO: [unreadable]

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34 TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO



- LEGEND**
- EXISTING MAJOR CONTROL POINTS
 - EXISTING MAJOR CONTROL POINTS
 - PROP. MAJOR CONTROL POINTS
 - PLANNING AREA BOUNDARY
 - MAJOR DRAINAGEWAY
 - OFF-SITE DRAINAGE BASIN
 - ON-SITE DRAINAGE BASIN
 - MAJOR DRAINAGE BASIN
 - OFF-SITE FLOW ARROW
 - ON-SITE FLOW ARROW
 - PROPOSED SIGNIFICANT FLOODPLAIN
 - 10-YEAR FLOODPLAIN
 - 100-YEAR FLOODPLAIN

- NOTES**
1. DRAINAGE BASINS AND FLOW DIRECTIONS ARE APPROXIMATE.
 2. FLOODPLAIN BOUNDARIES AND FLOODPLAIN ELEVATIONS AND MAY CHANGE DUE TO FUTURE DEVELOPMENT AND/OR CONSTRUCTION.
 3. THE SITE LIES WITHIN THE UNPAVED PORTION OF THE FEDERAL HIGHWAY FLOODPLAIN.
 4. 100-YEAR FLOODPLAIN ASSOCIATED WITH THE SOUTH DAWSON NORTH BRANCH, DAWSON RIDGE, DAWSON RIDGE NORTH AND DAWSON RIDGE SOUTH ARE SHOWN AND DRAINAGE FACILITIES WILL BE RE-EVALUATED BY A FLOODPLAIN SPECIALIST ON 10/30/2022.
 5. EFFORTS WILL BE MADE TO STABILIZE, PROTECT, AND PRESERVE THE MAJOR DRAINAGEWAYS ON SITE. WORKS WILL BE LIMITED TO IMPROVEMENTS IN THE AREAS OF ENCROACHMENT FOR THE PROPOSED DETENTION FACILITIES AND AS NOTED IN THE MASTER DRAINAGE PLAN FOR THE DRAINAGEWAYS. THE IMPROVEMENTS WILL CONFORM TO THE TOWN OF CASTLE ROCK DRAINAGE DESIGN AND TECHNICAL DESIGN MANUAL. THESE IMPROVEMENTS WILL BE DESIGNED TO MITIGATE EROSION AND PRESERVE THE NATURAL CHARACTER AND HISTORICAL DRAINAGE PATTERNS TO THE GREATEST EXTENT FEASIBLE.
 6. THE INTERSECTION OF FURNERAL ROAD, CENTRAL VALLEY DRIVE AND 151515 E 4 FURNAL COUNTY AND STATE PROJECT CHANNEL ARE SHOWN FOR THE SAME. THESE ARE NOT NECESSARILY THROUGH THE SITE WILL BE PART OF THE CIVIL PROJECT.

JJJJ
NORRIS DESIGN
 Planning | Landscape Architecture | Surveying
 1101 South 30th Street
 Denver, Colorado 80204
 P: 303.752.1146
 www.norrisdesign.com

APPLICANT

WESTSIDE INVESTMENT PARTNERS
 4100 E. MISSISSIPPI AVE
 SUITE 500
 DENVER, CO 80226
 303-864-9803

ENGINEER & SURVEYOR

CORE CONSULTANTS
 3473 S. BROADWAY
 ENGLEWOOD, CO 80113
 303-733-5960

DAWSON TRAILS

DAWSON TRAILS
 PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
 (AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

NOT FOR CONSTRUCTION

DATE
 PDP-01 07/04/2021
 PDP-02 12/03/2021
 PDP-03 04/13/2022
 PDP-04 04/27/2022
 PDP-05 05/05/2022

SHEET TITLE
 GRADING & DRAINAGE PLAN

SHEET
 12 OF 20

CHECKED BY: M.B. SW
 DRAWN BY: D. JR.

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 27, 29, 33, 37 & 34, TOWNSHIP 8 SOUTH RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO



APPLICANT

WESTSIDE INVESTMENT PARTNERS
4100 E. 155th STREET
SUITE 500
DENVER, CO 80231
303.984.0800

ENGINEER & SURVEYOR
CORE
3471 S BROADWAY
ENGLEWOOD, CO 80113
303.733.9197



DAWSON TRAILS
 PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
 (AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

WILDLAND/URBAN INTERFACE WILDFIRE VEGETATION MANAGEMENT PLAN:

THIS PROPERTY HAS VARYING DEGREES OF COVERAGE BY MULTIPLE VEGETATIVE TYPES. THUSLY FIRE MITIGATION SHALL BE APPROPRIATELY CONSIDERED AS DEVELOPMENT MOVES FORWARD. WILDFIRE MITIGATION IS THE IMPLEMENTATION OF VARIOUS MEASURES DESIGNED TO MINIMIZE THE DESTRUCTIVE EFFECTS FROM A WILDFIRE. AT THE TIME OF SITE DEVELOPMENT PLAN, THE APPLICANT SHALL WORK WITH THE TOWN OF CASTLE ROCK FIRE DEPARTMENT TO CREATE A FINAL AND IMPLEMENTABLE URBAN/WILDLAND INTERFACE AREA VEGETATION MANAGEMENT PLAN. BELOW ARE SUGGESTED PRACTICES THAT DEVELOPERS, BUILDERS AND HOMEOWNERS CAN IMPLEMENT TO HELP MITIGATE FIRE RISK FOR RESIDENCES.

A. WITHIN 30 FEET OF A STRUCTURE (BUILDING ENVELOPE AND IMMEDIATE AREA):

1. CREATE A "DEFENSIBLE SPACE" TO REDUCE THE LIKELIHOOD OF A DAMAGING WILDFIRE IN THE IMMEDIATE VICINITY OF THE HOME. DEFENSIBLE SPACE IS THE AREA WHERE VEGETATION HAS BEEN DESIGNED, INSTALLED AND MAINTAINED TO REDUCE THE POSSIBILITY OF FIRE SPREADING BETWEEN THE LANDSCAPE AND THE BUILDING.
2. IF NATIVE VEGETATION HAS BEEN SUCCESSFULLY RETAINED IN THIS AREA, PRUNE TREE CANOPIES FROM THE GROUND UP TO A MINIMUM HEIGHT OF 10 FEET. REMOVE ANY SMALL OR SUPPRESSED STEMS IN THE UNDER STORY OF DOMINANT TREES. DO NOT REMOVE MORE THAN 1/3 OF LIVE BRANCHES FROM CONIFERS.
3. WHEN PRESENT, TRIM ANY SHRUBS, PARTICULARLY GAMBEL OAK GROWING BELOW THE CANOPY OF LARGER RETAINED TREES.
4. PRUNE RETAINED CONIFEROUS TREES TO MINIMIZE CROWN OVERLAP. ISOLATE INDIVIDUAL TREES BY PRUNING BACK CANOPIES TO CREATE A SEPARATION BETWEEN TREES.
5. TRIM DENSE, CONTINUOUS GAMBEL OAK STANDS AND PRUNE TALLER SPECIMENS UP FROM THE GROUND TO CREATE A MORE OPEN TREE LIKE FORM. REMOVE SECTIONS OF LARGE BUT LOW GROWING STANDS TO CREATE DISCONTINUOUS ISLANDS OF VEGETATION.
6. INSTALL A CONTINUOUS NON-IRRIGATED ROCK MULCH BED OR OTHER NON-COMBUSTIBLE MATERIAL FOR A MINIMUM OF 5 FEET AROUND THE PERIMETER OF THE BUILDING.
7. MINIMIZE FOUNDATION TYPE PLANTINGS, ESPECIALLY ADJACENT TO COMBUSTIBLE SIDING. KEEP ALL SHRUB PLANTINGS A MINIMUM OF 5 FEET FROM THE FOUNDATION. EXCLUDE MORE COMBUSTIBLE SHRUB SPECIES (CONIFEROUS EVERGREENS LIKE JUNIPER, ARBORVITAE, SPRUCE, PINE AND FIR) AND SPACE SHRUBS TO CREATE LOW, NON-CONTINUOUS PLANTINGS NEAR THE BUILDING.
8. PLANT ONLY DECIDUOUS TREE AND SHRUB SPECIES WITHIN 15 FEET OF STRUCTURES. PROVIDE IRRIGATION AS REQUIRED FOR THE SUCCESSFUL ESTABLISHMENT AND LONG-TERM HEALTH OF NEW TREES.
9. PLANT TREES FAR ENOUGH AWAY FROM THE BUILDING THAT AT MATURITY, TREE CANOPIES WILL NOT OVERHANG THE ROOF.
10. PLANT SOO OR SEED WITH LOW-GROWING GRASS SEED MIXES.
11. PROVIDE IRRIGATION TO TURF AND NATIVE GRASSES WITHIN THIS AREA TO PREVENT SUMMER DORMANCY.
12. MAINTAIN NATIVE GRASS HEIGHT TO A MAXIMUM OF 6 INCHES.
13. PLANT WILDFLOWERS ONLY IF THEY WILL BE IRRIGATED AND WILL BE CUT BACK TO A MAXIMUM HEIGHT OF 8 INCHES AT THE END OF GROWING SEASON (FOLLOWING SEED PRODUCTION).
14. DISPOSE OF ALL SLASH OR PLANT TRIMMINGS OUTSIDE OF THIS ZONE (OFF SITE).

B. BETWEEN 30 FEET AND 150 FEET FROM STRUCTURES AND ROADWAYS (TREE AND SHRUB PRESERVATION AREA): NOTE THE EXTENT OF THIS ZONE IS AFFECTED BY SLOPE AND IS GREATER WHEN STRUCTURES OR ROADWAYS ARE AT THE TOP OF THE SLOPE AND WHEN SLOPES ARE RELATIVELY STEEP. SLOPE IS LESS CRITICAL WHEN STRUCTURES ARE AT THE BASE OF A SLOPE OR ON LEVEL GROUND.

1. CLEAR SMALL DIAMETER, SNOWBENT, DISEASED, DAMAGED OR SUPPRESSED STEMS IN THE UNDER STORY OF LARGER PINE TREES.
2. PRUNE TO RAISE THE CANOPY OF LARGE, EXISTING TREES TO 12 FEET ABOVE GROUND LEVEL.

3. TRIM SHRUBS GROWING DIRECTLY BENEATH LARGER TREES PER SECTION A, NOTE 2 ABOVE.
4. REMOVE ANNUALLY, DEAD STEMS AND BRANCHES FROM SHRUBS AND TREES.
5. SPACE NEWLY PLANTED CONIFEROUS TREES (≥70 TALL AT MATURITY) AT LEAST 20-30 FEET APART TO PROVIDE A MINIMUM OF 10 FEET BETWEEN CROWNS AT MATURITY. IF PINON PINE GROUPINGS (CLUMPS OF TWO OR MORE OF THE SAME SPECIES), AND CONIFEROUS SHRUB GROUPINGS ARE PLANTED, PROVIDE 20-30 FEET BETWEEN GROUPINGS. DECIDUOUS TREES AND SHRUBS ARE NOT SUBJECT TO THIS GUIDANCE WHEN PLANTED AS PART OF AN IRRIGATED AND MAINTAINED LANDSCAPE.
6. PRUNE THE BRANCHES OF SMALLER OR NEWLY PLANTED TREES AS THEY GROW. UP TO A HEIGHT OF 8-12 FEET ABOVE THE GROUND. DO NOT OVER PRUNE THE CROWNS OF SMALLER TREES.
7. TRIM OR MOW NATIVE GRASSES AND WILDFLOWERS MID-SUMMER AND IN THE FALL OR SPRING TO MAXIMUM HEIGHT OF 8 INCHES.
8. DISPOSE OF ALL SLASH OR PLANT TRIMMINGS OFF SITE, BY CHIPPING, OR OTHER MECHANICAL TREATMENTS.

C. BEYOND 150 FEET OF THE STRUCTURE AND OPEN SPACES (PRESERVATION / ENVIRONMENTALLY SENSITIVE AREA):

1. CLEAR SMALLER UNDERSTORY TREES AND SHRUBS PER SECTION B, NOTE 1 ABOVE.
2. UNDERTAKE SELECTIVE THINNING TO IMPROVE HEALTH AND APPEARANCE OF WOODS AND NATIVE GRASS AREAS.
3. REMOVE SMALLER TREES IN CROWDED STANDS TO INCREASE TREE SPACING.
4. PROVIDE SEPARATION BETWEEN GAMBEL OAK CLUMPS TO BREAK UP HORIZONTAL CONTINUITY OF FUELS AND REDUCE CROWN FIRE POTENTIAL.
5. TRIM OR MOW NATIVE GRASSES ALONG TRAILS TO ALLOW POTENTIAL USE AS PRE-CONSTRUCTED FIRE LINES. THESE MOWN AREAS SHOULD BE 8 FEET WIDE ON BOTH SIDES OF TRAILS. ANY SHRUB CLUMPS RETAINED WITHIN 20 FEET OF TRAILS SHOULD BE PRUNED TO REDUCE LADDER FUELS AND MAINTAINED IN A MITIGATED CONDITION.
6. RETAIN AN INCREASED NUMBER OF STANDING DEAD TREES PER ACRE FOR WILDLIFE HABITAT UNLESS THEY POSE A THREAT TO UTILITIES OR HUMAN USE.
7. SLASH OR PLANT TRIMMINGS MAY BE DISPOSED OF WITHIN THIS AREA IF TREATED AND REDUCED TO A MAXIMUM DEPTH OF 6 INCHES. IF CHIPPED, MULCH DEPTH SHOULD NOT EXCEED 4 INCHES IN DEPTH.

D. STRUCTURAL WILDFIRE GUIDELINES:

1. ALL ROOFS SHALL HAVE CLASS A FIRE RATING.
2. DECKING MATERIAL SHALL HAVE A CLASS B OR HIGHER FIRE RATING.
3. ANY FENCING CONNECTED TO STRUCTURES SHALL USE NON-COMBUSTIBLE MATERIALS WITHIN 5 FEET OF STRUCTURES OR DECKS.
4. ALL VENTS (FOUNDATION, SOFFIT, EAVE, ETC.) SHALL HAVE 1/8" INCH OR SMALLER OPENING SIZES.
5. GUTTERS SHALL BE NON-COMBUSTIBLE OR HAVE CLASS A FIRE RATING.


E. MAINTENANCE OF FIRE MITIGATION:

1. FIRE MITIGATION ON PRIVATE LOTS IS THE RESPONSIBILITY OF THE PROPERTY OWNER.
2. FIRE MITIGATION UNDERTAKEN BY THE DEVELOPER ON OPEN SPACES OR COMMON AREAS SHALL BE MAINTAINED BY THE HOMEOWNERS ASSOCIATION (HOA) OR ALTERNATIVELY BY A SPECIAL DISTRICT (SD), AS MAY BE DETERMINED AT THE TIME OF CONVEYANCE.
3. PLANTED VEGETATION ALONG ALL THOROUGHFARES SHALL BE MAINTAINED TO MANAGE RISK OF CROWN FIRE OR FLAME INTRUSION (IMPINGEMENT) INTO THE PUBLIC RIGHT-OF-WAY.
4. THE HOA OR SD (IF APPLICABLE) SHALL ESTABLISH PROCEDURES FOR RESIDENTS TO IMPLEMENT OR MAINTAIN WILDFIRE MITIGATION MEASURES PER C.R.S. 30-23-3-100.5 (A.K.A. 30-100; HOMEOWNER BILL OF RIGHTS).

GENERAL NOTES:

1. A WILDLAND/URBAN INTERFACE WILDFIRE VEGETATION MANAGEMENT PLAN SHALL BE COMPLETED AND SUBMITTED TO THE TOWN OF CASTLE ROCK WITH EACH SITE DEVELOPMENT PLAN, OR SITE DEVELOPMENT PLAN AMENDMENT.
2. MITIGATION REQUIREMENTS SHALL BE COMPLETED AS ESTABLISHED IN THE DEVELOPMENT AGREEMENT.

CHECKED BY: [Signature]
 DATE: [Date]



DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 31, 33 & 34, TOWNSHIP 5 SOUTH, RANGE 6 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

PD ZONING REGULATIONS

SECTION 1 | PURPOSE

The purpose of the Dawson Trails Planned Development Plan (PDP) and Zoning Regulations contained herein is to establish standards for the development and improvement of the property. The standards contained in these Zoning Regulations are intended to carry out the goals of this planned community.

SECTION 2 | GENERAL PROVISIONS

- Adoption**
The Zoning Regulation and the Dawson Trails Planned Development Plan have been adopted by the Town Council by Ordinance No. 2022-017 on the 6th day of September 2022 and have been incorporated therein pursuant to Section 11.32 of Title 17, Zoning of the Town of Castle Rock Municipal Code, after appropriate public notice and hearings.
- Applicability**
The Dawson Trails Planned Development Plan and Zoning Regulations shall run with the land and bind owners of record and successors in interest to the property.
- Maximum Level of Development**
The total number of dwelling units or total commercial, industrial, or other non-residential square footage within the established planning area is the maximum allowed for planning and development. The maximum number of dwelling units approved for development within the Dawson Trails Planned Development (PD) is 5,850. The maximum non-residential square footage approved for development in the Dawson Trails PD is 3,200,000.
- Relationship to Town of Castle Rock Regulations**
All Town ordinances and regulations, as the same are amended from time to time, shall apply to and be enforceable in the Dawson Trails PD. All references herein to the Town of Castle Rock Municipal Code (CMC), specifically cited Code Chapters and Sections, and Town technical criteria (Clarity) shall mean as in effect at the time of the approval of the Dawson Trails Planned Development Plan and Zoning Regulations, and as the Code and Criteria are amended. Accordingly, such Town ordinances and regulations shall govern and control over any conflicting provisions in the PD Zoning Regulations, unless such conflicting provision is vested as its express development right under the applicable Development Agreement.

The standard zoning requirements of the Town zoning ordinance, including off-street parking, landscaping, site development, accessory and temporary uses, use by special review and variance processes, unless expressly varied in these zoning regulations, shall apply to the Dawson Trails PD. The PD Zoning Regulations shall not preclude the application of Town ordinances, including variances thereon, which are of general application throughout the Town unless such application would conflict with an express development right (see Chapter 17.06, CMAC).

- Development Agreement**
In addition to these regulations, certain portions of the development of the Dawson Trails PD are controlled by an agreement between the Town of Castle Rock and the Property Owners. This agreement provides for a vesting of the property rights set forth in the Dawson Trails Planned Development Plan and establishes a Water Bank to Dawson Trails. This agreement, entitled the Dawson Trails Development Agreement, between Dawson Trails LLC and Dawson Trails III LLC and the Town of Castle Rock (the "Development Agreement"), was adopted by the Town of Castle Rock on the 6th day of September 2022, by Resolution No. 2022-018. In the event of a conflict between the terms of this PD Zoning Regulations and the Development Agreement, the Development Agreement shall control.

SECTION 3 | GENERAL PROJECT DESCRIPTION

- Overall Development Plan**
The Dawson Trails PD consists of approximately 2,063.77 acres with zoning that allows a maximum of 5,850 residential dwelling units as well as provisions for a wide range of commercial, office, industrial uses. A maximum of 3.2 million square feet of non-residential uses is permitted in Dawson Trails PD. This development plan originates from low density residential planning areas located in the western portions of the PD (higher density mixed-use areas located in the eastern portions of the PD).

The location of the PD property is within a designated "gateway" to Castle Rock, being situated at the southern most boundary of the Town, west of Interstate 25 (I-25). The general character of the Dawson Trails neighborhood is shaped by a comprehensive network of open spaces, trails, and parks. Public land dedication will be used by local and regional public bodies which may include neighborhood and regional parks, schools, and other public facilities. Roads and planning areas are planned and located to enhance aspects to existing topography and mature vegetation with preservation of many topographic high points and other natural features, being incorporated into the overall design.

This development plan provides approximately 433 acres of interconnected open space which accommodates wildlife movement and habitat and includes a diversity of topography and existing views. All development within Dawson Trails PD is to be sited so as to most closely comply with the Mayflower Bird Treaty Act. No federal or state protected species were found inhabiting the property.

3.2 Character Areas and Planning Areas

- Intent**
The Dawson Trails PD is organized into three (3) Character Areas, according to similarities in land use and development characteristics of the Planning Areas. The West Character Area generally consists of low density single-family detached residential uses on the west and north sides of the "Yoke", as well as significant interconnected open space corridors and trails. The Central Character Area contains a wide range of residential housing types and includes opportunities for supporting neighborhood commercial uses, and key open space corridors and parks on the east side of the ridge while transitioning to the higher terrain. The East Character Area has a general character of being a commercial, employment, and mixed-use area with a broad range of land uses, including higher density residential uses.

- West Character Area**
The West Character Area (West) is composed of single-family detached residences and neighborhood support amenities such as a clubhouse, community center, or other similar uses. This Character Area generally serves as the transition from the Central Character Area to the existing single-family detached residential lots located in Douglas County. The West consists of the lowest residential densities in Dawson Trails. The area also preserves large areas of key open spaces and natural corridors with mature vegetation and establishes a significant natural transition buffer where adjacent County residential properties. Only single-family detached residential homes are permitted in the West. Commercial land uses are not permitted. The West Character Area is composed of three (3) Planning Areas totaling a maximum of 1,183 dwelling units.

- Planning Area A** is the westernmost development area in the Dawson Trails PD, separated from the adjacent County residential properties by a single open space buffer area. The western edge of this Planning Area conforms to the existing topography and preserves much of the physical characteristics and mature vegetation. Development in this Planning Area will consist of lower density single-family detached residential uses. A Transition Zone, with additional development standards area required, exists where Planning Area boundaries are adjacent to existing Douglas County residential development. A Transition Zone exists where additional development standards are required (See Section 5.10).

- Planning Areas B-1 and B-2** establish the northernmost and southeastern portions of the West Character Area. These Planning Areas are closest to the existing "Yoke" (a single-family detached residential subdivision) and the existing "Yoke" (a single-family detached residential subdivision). As with Planning Area A, development will be characterized by single-family detached residential. The edges of these Planning Areas are established in this PD Plan to be sensitive to existing topography and other physical characteristics of the property. Transition Zone development standards, as defined within the PD, apply to some edges of these Planning Areas (See Section 5.10).

- Central Character Area**
The Central Character Area (Central) acts as a transition area between the lower density West Character Area and the higher density/medium East Character Area. This Character Area allows higher density residential uses as well as non-residential uses, primarily in the eastern portion and away from the West Character Area and closer to the East Character Area and Dawson Trails Boulevard. All residential development in the Central Area include a wide range of housing types including single-family attached and detached as well as multi-family. This Character Area will include a well-connected series of neighborhood parks, potential neighborhood commercial, and both locally and regionally oriented linear uses, parks, and other open space and amenities. The Central Character Area is comprised of three (3) Planning Areas totaling a maximum of 3,327 dwelling units and limited density corridors allowed.

- Planning Area C-1** is primarily a residential land use area, with some supporting neighborhood commercial and other low density non-residential uses permitted as well as by special review, anticipated to occur along collector roads and around residential uses. Based on land use types permitted and associated development standards, the intensity of uses and density of residential development will generally decrease from east to west within the Planning Area.
- Planning Area C-2** is similar to Planning Area C-1 but permits slightly higher residential densities. The southern portion of this Planning Area generally permits lower levels of density, due to the proximity of the Town/County boundary.
- Planning Area D** is an area that permits a wide range of residential uses, mixed uses, and a wide range of commercial and other non-residential uses. Both horizontal and vertically mixed uses and uses are appropriate and permitted. The residential land uses and residential densities will generally occur along the major north-south axis (Dawson Trails Boulevard) located along the eastern boundary of the Planning Area.

- East Character Area**
The East Character Area (East) is influenced by its proximity to and visibility from Interstate 25, the Crystal Valley Interchange, and Dawson Trails Boulevard. Accordingly, the type of development occurring here will tend to be higher density, more use (both vertical and horizontal mixtures) as well as a wide range of non-residential uses. Residential neighborhood and commercial site design in the East will strive to create pedestrian friendly connections and provide access to a variety of modes of transportation.

Residential development in the East is anticipated to include denser and more compact housing types such as condominiums, townhouses, apartments and high density attached single-family detached and attached units. A maximum of 1,340 dwelling units and limited transfer of units between planning areas is allowed.

Office buildings, retail stores, restaurants, service commercial, light industry and other similar uses will provide employment, shopping, and local and regional destinations in the Character Area. Large format retailers, also known as "big-box" stores are appropriate in Planning Areas E-2, F-1, F-1 and F-3, along with other uses.

The East Character Area is comprised of seven (7) Planning Areas, and development standards included in this PD create a logical transition to the adjacent Central Character Area. Land uses allowed among the Planning Areas are similar, with the exception of Planning Areas G-1 and G-2 which allow light and flex industrial uses and public residential uses.

- Planning Area E-1** is a mixed-use parcel, located within the Crystal Valley Interchange area and is adjacent to the Twin Falls single-family detached residential subdivision located in Douglas County, to the west. The proximity to adjacent commercial or mixed-use Planning Areas allows for similar development opportunities, but at a lower intensity. Development standards, which establish appropriate buffer areas and lower profile buildings, serve to guide development and site planning within this Planning Area. The western boundary of this Planning Area is existing light rail alignment and will follow the Douglas County Clerk and Recorder, Reception Number 0028282-2 labeled on the PDP. This agreement requires a 100-foot-wide buffer in this area.

- Planning Area E-2** in the PDP is a mixed-use parcel that is more centrally positioned in the Dawson Trails neighborhood. This Planning Area is categorized as a Pedestrian Oriented Area and has the potential to include a pedestrian-oriented cluster of uses and will provide opportunities to shop, work, live, and recreate. Pedestrian Oriented Areas beyond the one described in Planning Area E-2 may also be developed within the areas of Dawson Trails, The Pedestrian Oriented Area will include the following:
 - Include either a publicly accessible and activated squaregreen-space OR a publicly accessible and activated "town street" or at least one (1) block in length with buildings fronting will attract pedestrian access oriented onto the space or street and incorporating typical urban design elements such as curbed parking (parallel or head-in) street trees for shade, decorative/enhanced paving, lighting/street furnishings, and other elements to help establish and define the public realm of the place/hood.
 - Include all non-residential and residential uses permitted in Planning Area E-2.
 - Enhanced elements to support pedestrian connectivity may include crosswalks, outdoor dining, pedestrian-rated lighting (poles and/or bollards), dedicated bicycle parking in key locations, or similar improvements.

- Development patterns as a Pedestrian Oriented Area** in this portion of Planning Area E-2 should prioritize pedestrians by placing awnings at sidewalk, providing landscaping along main routes, and allowing on-street parking to help encourage slower vehicular traffic. As a primary design principle for the gathering place/main street is to be pedestrian-oriented, the transportation network in these areas should also provide safe crossings for pedestrians and cyclists and may include mid-block crossings where necessary. Additional guidelines and standards can be found in the Dawson Trails Architectural Guidelines.

- Planning Areas F-1, F-2 and F-3** are proximate to the proposed I-25 interchange and provide the widest range of land uses within Dawson Trails. These Planning Areas are likely to contain more auto-oriented and destination type land uses while providing safe connections for cyclists and pedestrians.
- Planning Areas G-1 and G-2** provide for a similar range of land uses as in the other portions of the East Character Area but does not permit residential land uses.

SECTION 4 | DEFINITIONS

In addition to the standard definitions found in the Town of Castle Rock Zoning Ordinance (Title 17), as amended, the following definitions of terms shall apply to this PD.

- Accessory Structure** means a detached subordinate building, the use of which is customarily incidental to that of the main building or to the main use of the land and which is located on the same lot with the main building or use.
- Adult Day Care Facility** means a facility that provides services under an adult day care program on a daily or regular basis but not overnight to four or more elderly or handicapped persons who are not related by blood, marriage, or adoption to the owner of the facility.
- Attached or Detached Private Garage** means an accessory building or portion of a dwelling which is fully enclosed and used for the sheltering of permitted vehicles and storage of household equipment incidental to the residential occupancy. This definition shall not include a carport or other open shelter.
- Driveway Easement** means an easement placed upon a common or shared driveway, benefiting the lot or more property owners which allows such drive for access.
- Final Home** means (a) an establishment that holds, cares for, or prepares human remains prior to final disposition, including a crematory or embalming room; (b) an establishment that holds prior to the general public, as providing funeral goods and services; (c) an establishment that provides funeral or memorial services to the public for compensation.

Industrial, Flex means industrial buildings which allow for a wide range of office and warehouse uses. Flex buildings usually contain a larger percentage of office space than a typical distribution warehouse building and can be easily adapted to the spatial needs of the tenant.

Labor Animal Clinic and Hospital means a clinic and/or hospital that provides medical care for large animals, including but not limited to equine, ruminant, and other livestock. This may include services such as feed checks, administering medicines, checkups, and surgeries.

Master Developer means the Master Developer for Dawson Trails PD and/or as assignee of all or certain phases of the project that will be the entity responsible for providing the spine infrastructure, including roads, sewer, and water for the project. The Master Developer shall form or amend the Service Plan for any required quasi-governmental metropolitan district, the property owner's association, and design review committee.

Non-Residential means development containing commercial, retail, industrial, and institutional uses. Residential and residential ancillary uses such as schools, churches, public spaces (G-1) and public facilities are not considered to be non-residential uses.

Office, Flex means buildings that are designed and marketed as suitable for offices but with space available that is able to accommodate mail storage, job shops, mail/drop-off centers, retail or similar operations. Generally, flex spaces has storefront type windows in the office area of the space.

Residential:

Clustered Dwelling means single family or multi-family, attached, or detached, dwelling units which are grouped closely together or one lot as a means to preserve nearby open space that would otherwise be distributed somewhat evenly across the site.

Condominium means a type of multi-family Dwelling. The unit is individually owned, each owner receives a recordable deed to the individual unit purchased, including the right to sell, mortgage, etc., the unit and sharing joint ownership of any common grounds, passageways, etc.

Dwelling or Dwelling Unit means any building or portion thereof which is used as the primary residence or sleeping place of one or more human beings, but not including hotels, motels, tourist courts, clubs, hospitals, or similar uses.

Green Court means a group of single family, attached or detached, dwelling units which are accessed on the rear either a private drive or an alley. Green Court dwellings may either be on individual lots or a commonly owned lot. Typically included is a common shared open space area which dwells from front and which is maintained by either a private homeowner's association or other similar entity.

Multi-Court means a group of single family, attached or detached, dwelling units which are accessed by a common shared driveway.

Multifamily means buildings which contain apartments or condominiums, which contain three or more dwelling units, which are accessed from minor elevations or corridors, or have individual exterior entrances, and are separated by interior walls or fire doors. Multifamily does not include boarding houses, dormitories, hostels, motels, bed and breakfast establishments, single-family attached or detached dwellings, or hotels and motels, adult day care, senior care, or other similar institutional uses which provide support staff.

Patio Dwelling Unit means a dwelling that shares at least one wall with another home. Frequently built on small lots with patios in place of a traditional back yard.

Single Family, Attached or Detached means a building developed exclusively for occupancy by one family and includes (but is not limited to) dwellings, group courts, motor courts and other similar residential configurations. Apartments and condominiums are considered Multifamily.

Townhome means a type of Single Family Attached Dwelling in which each single dwelling opens from ground to roof and is separated from other Townhome Dwelling Units by a common wall having individual outside access. Townhome Dwelling Units may have no side yards, or front and rear yards and may include two, three, four, or more dwellings.

Zero Lot Line means an alternative type of Single Family Detached Dwelling Unit which is situated on a lot so that one or more sides rest directly on the boundary line of the lot.

Short Term Rentals means any dwelling or portion thereof that is available for use as a used for accommodations or lodgings of guests, paying a fee or compensation for a period of less than thirty (30) consecutive days.

Storage, Indoor (Allowed in Planning Areas F-1, F-2, F-3, G-1, G-2 only) means the keeping in an enclosed area of any components, products, material, merchandise, equipment, vehicles, RVs, boats, and trailers.

Storage, Outdoor (Allowed in Planning Areas F-1, F-2, F-3, G-1, G-2 only) means the keeping in an unenclosed area of any components, products, material, merchandise, equipment, vehicles, RVs, boats, and trailers. Recreational vehicles, equipment attached to recreational vehicles, short-term customer and staff parking, and approved bath enclosures shall not be considered outdoor storage.

Transition Zone is the 150' wide area identified on the PD Plan in Planning Areas A, B-1, and B-2 that is generally located towards the PDP property boundary and enclosed with the area-attached pattern in those Planning Areas. The Transition Zone is established with this PD to provide standards to convert a group of land use development standards within this specific portion of the Planning Area, including minimum lot size, setbacks, building colors, landscaping improvements, and fencing.

PLANNER/LANDSCAPE ARCHITECT
NORRIS DESIGN
1000 S. W. 10TH AVE.
SUITE 100
DENVER, CO 80202

APPLICANT
WESTSIDE INVESTMENT PARTNERS
4100 E. MISSISSIPPI AVE
SUITE 500
DENVER, CO 80246
303.954.8889

ENGINEER & SURVEYOR
CORE CONSULTANTS
3475 S. BROADWAY
ENGLEWOOD, CO 80113
303.733.5960

DAWSON TRAILS

DAWSON TRAILS
PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE
POP-01/07/2020/2021
POP-02/19/2020/2021
POP-03/04/13/2022
POP-04/08/27/2022
POP-05/06/29/2022

SHEET TITLE
PD ZONING REGULATIONS

SHEET
14 OF 20

MBR: SVW
D.J. JIR
CHECKED BY:
DRAWN BY:

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 27, 29, 32, 33 & 34, TOWNSHIP A SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO



Project Name: DAWSON TRAILS
Project Address: 3475 S. BRADSHAW
ENGLEWOOD, CO 80113
303.700.9590

APPLICANT:



WESTSIDE INVESTMENT PARTNERS
4102 E. MISSISSIPPI AVE
SUITE 500
DENVER, CO 80216
303.944.6400

ENGINEER & SURVEYOR:

CORE CONSULTANTS
3475 S. BRADSHAW
ENGLEWOOD, CO 80113
303.700.9590



DAWSON TRAILS
PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

PD ZONING REGULATIONS

SECTION 5 | OVERALL PROJECT STANDARDS

5.1 Planning Area Boundaries

The conceptual boundaries of all Planning Areas are shown on the Dawson Trails PD Plan. Where a Planning Area abuts an internal local street or drives or a collector street, the boundary shall be the centerline of the street, where applicable. Where a Planning Area abuts an arterial street, the boundary shall be the right-of-way of that street as indicated on the PD Plan. A Planning Area may be partially subdivided and/or subdivided into multiple lots and parcels as the Site Development Plan (Final stage of the development review process).

5.2 Amendments to the PD Plan and PD Zoning Regulations

The maximum number of dwelling units approved for development in Dawson Trails is 5,852 including a maximum number of 1,020 Multi-Family dwelling units. The maximum amount of non-residential use square footage is 3,000,000 square feet, subject to subsections 5.3 through 5.4.

2. Dwellings

All dwelling units are subject to minimum standards in each Planning Area as noted below in Table 5.2.1. In any case, the maximum number of dwelling units approved in this PD shall not exceed 5,852.

Character Area - Planning Area	Percentage Transfer Out	Percentage Transfer In
West		
B-1	25%	0
B-2	25%	0
B-3	25%	0
Central		
C-1	20%	15%
C-2	20%	20%
D	20%	20%
East		
E-1	No Residential Allowed	No Residential Allowed
E-2	20%	20%
F-1	20%	20%
F-2	20%	20%
F-3	20%	20%
G-1	No Residential Allowed	No Residential Allowed
G-2	No Residential Allowed	No Residential Allowed

The actual number of dwelling units approved will be determined and calculated at the Site Development Plan (Final stage of the development review process). A Project Tracking Sheet will be used to document the series of plans at Dawson Trails over the life cycle of the project.

The maximum number of allowed multifamily dwelling units is capped at 1,020. However, this may be increased by up to 15% as an Administrative Amendment to this PD. In any case, the maximum number of dwelling units approved in this PD shall not exceed 3,850.

3. Non-residential
A. The maximum 3,000,000 square feet of non-residential use may be increased by up to 15% as an Administrative Amendment to this PD.

B. All non-residential uses in the West, Central and East Character Areas that are residential use supporting in nature, including but not limited to various types of amenity, clubhouse, and similar uses, shall not be sited towards the maximum allocation of non-residential use of 3,000,000 square feet.

C. Assisted living facilities, adult day care, memory care, nursing homes, and continues of care units and other multi-unit use types that provide assisted services do not count towards the 3,850 maximum allowed dwelling units in the PD.

- 3.3 Non-Residential Use Acreage Minimums**
- A. Minimum acreage of non-residential uses are required and shall be applied in F-1, F-2, F-3, G-1, and G-2 as follows:
 - 1. Planning Area F-1 and F-2: 20-acres
 - 2. Planning Area F-3: 25-acres
 - 3. Planning Area G-1: 67.5-acres
 - 4. Planning Area G-2: 7-acres

- 3.4 Storage Use Acreage Minimums**
- 1. A total cumulative maximum of 50 acres of storage uses are permitted within Planning Areas F-1, F-2, F-3, G-1, and G-2.
 - A. Outdoor storage shall not exceed 15 acres.
 - B. Indoor and outdoor storage may both be included on the same site.

- 3.5 Automobile / Vehicle / RV / Boat / Motorcycle / All-Terrain Vehicle / Equipment Sales and Leasing Use Acreage Minimums**
- 1. A total cumulative maximum of 20 acres of Automobile / Vehicle / RV / Boat / Motorcycle / All-Terrain Vehicle / Equipment Sales and Leasing uses are permitted within Planning Areas F-1, F-2, F-3, G-1, and G-2.

5.8 Road Alignments
The PD depicts conceptual locations of roadways. Recognizing that the final road alignments are subject to detailed engineering studies, adjustments of road alignments are expected and can be accomplished by the applicant/developer through the Site Development Plan (Final stage of the development review process) without any amendment to these regulations or to the PD itself. Any applicant road requirements, as determined by the Town of Castle Rock Development Services Director, shall follow the PD Amendment procedure as provided in the Town of Castle Rock Municipal Code.

5.7 Trails and Trail Alignments
The PD depicts general locations of trails. Recognizing that the final trail alignments are subject to detailed engineering studies and several pedestrian connectivity adjustments, adjustments and changes are expected, and can be accomplished by the applicant/developer through the Site Development Plan (Final stage of the development review process) without any amendment to these regulations or to the Plan Development Plan itself. In some cases, sidewalks or paved shoulders along roadways and streets may be used to correct trail alignment. Refer to the Dawson Trails PD Plan.

5.8 Open Space
Open space may be public or private. Public open space, PL-1 or PL-2 will be dedicated to the Town. Private open space, OSP, will be owned by a private entity, a non-profit, or other public or private open space as a use of SPD or PUD.

- 5.9 Residential Parking**
1. Shared parking is allowed per Section 17.54 of the Municipal Code.
 2. Reduced parking standards may be requested per Section 17.54 of the Municipal Code not exceed 1.85:1.
- Table 5.1.1 below identifies parking standards within the Dawson Trails PD. Parking shall follow the table below unless the applicant demonstrates that the Town Code requirements are too burdensome in a particular area of the SPD.
- | Use Type | Single-Family Detached Dwelling | Single-Family Attached Dwelling | Multi-Family Residential (Township) |
|--|---------------------------------|---------------------------------|-------------------------------------|
| 1. Single-Family Detached Dwelling | 1 space per 1.85 bedroom | 1.5 spaces per 1.85 bedroom | 1.5 spaces per 1.85 bedroom |
| 2. Single-Family Attached Dwelling | 1.5 spaces per 1.85 bedroom | 1.5 spaces per 1.85 bedroom | 1.5 spaces per 1.85 bedroom |
| 3. Multi-Family Residential (Township) | 1.5 spaces per 1.85 bedroom | 1.5 spaces per 1.85 bedroom | 1.5 spaces per 1.85 bedroom |

5.10 Residential / Non-Residential Use Adjacency Standards
1. Planning Area E-1 shall have a minimum 100-foot open space buffer, measured from the east boundary of the western Dawson Trails property boundary. No structure which requires a building permit are permitted within this open space buffer.
2. The eastern portion of Planning Area E-2, adjacent to the proposed Major Collector, shall have a minimum 50-foot open space buffer, measured from the east boundary of the Right-of-Way for the Major Collector. No structure which requires a building permit are permitted within this open space buffer.
3. The buffers north and 2, above are inclusive of the buffer described in the existing buffer agreement, which is filed with the Douglas County Clerk and Recorder, Reception Number 662692.
4. The setback requirements of Chapters 17.50 and 17.51 of the Town of Castle Rock Municipal Code shall apply in the Dawson Trails PD only, to development adjacent to the buffers described in 1 and 2 above, except that no additional prescriptive buffer is required.

5.11 Landscaping
All landscaping shall be in conformance with Town of Castle Rock Landscape and Irrigation Criteria Manual and the Dawson Trails Water Efficiency Plan, as amended.

5.12 Grading / Drainage
The grading/drainage of an individual lot or open space tract shall vary from the approved Plat and Consistency Documents - Grading Plans, as appropriate, without written approval of the Owner, certificate of the Owner's Engineer(s), and Town review and approval. Any uncontracted work performed will be required to be returned to the satisfied grade by the individual(s) or organization(s) that authorized the change without proper approval.

5.13 Town-Owned Property
No encroachment, grading, or other disturbance associated with development is permitted on PL-1, PL-2 or other Town owned property without written approval from the Town of Castle Rock.

5.14 Compliance with Statewide Erosion Protection District
All areas within the Statewide Erosion Protection Area as shown on the Dawson Trails PD Plan shall be subject to Chapter 17.43 of the Castle Rock Municipal Code, as amended.

5.15 Wildland Fire Mitigation
The natural topography and existing vegetation of the development site and adjacent open space suggests that the design of the homes and the neighborhood incorporate methods to limit the potential for the spread of wildland fires. National Fire Protection Association measures approved by the Town of Castle Rock Fire Department shall be incorporated into each Site Development Plan. An overall Wildfire Vegetation Mitigation Plan is included in the PD and will be further defined at each stage of planning and engineering information and cost are known.

- 5.15 Planning and Design**
1. Design and construction of all structures, roadways, and other improvements shall be sensitive to the existing topography and natural vegetation. The proposed improvements shall achieve a landscaped landscape (existing conditions, proposed such as improved conditions) that is consistent with the intended character of the Character Area and/or Planning Area. Improvements being implemented, as determined by the Town.
 2. Structures in sloping areas shall be designed to generally conform to the slope by means of stepped foundations, retaining walls or similar methods that will serve to minimize grading and site preparation as determined locally.
 3. Grading shall be shaped to complement the natural topography, as determined locally.
 4. Roads in steeply sloping or heavily vegetated areas shall be designed to minimize the area of cut/drainage, while recognizing grading impacts will occur changes to existing slopes and removal of existing vegetation in many areas where development improvements are to be located. Where practical, clearing of vegetation within the right-of-way shall be feathered to create more natural appearing edges.

SECTION 6 | PERMITTED USES AND DEVELOPMENT STANDARDS

As noted above in the Character Area descriptions, each Character Area is further organized by Planning Area. While the Character Areas provide a general guide for similar types of development, each Planning Area provides allowed land uses and dimensional standards.

Refer to Section 6.11 Supplemental Development Standards - Supplemental Development Standard #16 (A through E) includes standards applicable to all Planning Areas. Sections 6.1 through 6.10 establish permitted uses and development standards unique to specific Planning Areas.

- 6.1 Planning Area A**
- 1. Permitted Uses**
- A. Residential
 - 1. Single-Family Detached
 - 2. Detached Private Garage
 - B. Non-Residential
 - 1. Home Occupations
 - 2. Open Space, Public or Private
 - 3. Private recreational and park uses, clubhouses, country clubs, recreational facilities, including but not limited to swimming pools, sports courts and jogging, equestrian riding, hiking and biking trails
 - 4. Public Parks, Playgrounds, and other recreational areas
 - 5. Utilities including but not limited to gas, electric, telecom. This includes structures or facilities commonly associated or required with the installation and operation of utilities.
 - 6. Water infrastructure including but not limited to detention/infiltration basins, pumps, and ponds, as well as structures typically associated with water infrastructure such as pump houses.
 - C. Uses By Special Review
 - 1. Solar collectors which are not part of the primary structure
 - 2. Public Facilities
- 2. Development Standards (unless otherwise approved by the Town at the time of SPD or Plat)**
- A. Transition Zone Minimum Lot Size: Residential lots located within the designated Transition Zone shall be a minimum 7,730 square feet (See Section 6.10 for additional standards).
 - B. Minimum Lot Size: None
 - C. Primary Structure
 - 1. Single-Family Detached
 - a. Minimum Front Setback (ft.): 5.0'
 - b. Minimum Front Setback to Garage Door Face (ft.): 5.0'
 - c. Minimum Rear Setback (ft.): 5.0'
 - d. Minimum Side Setback (Interior Side) (ft.): 5.0'
 - e. Minimum Side Street Setback (ft.): 5.0' to 15'
 - 2. Minimum Building Separation (ft.): 10'
 - 3. Maximum Building Height (ft.): 35'

- D. Accessory Structure
 - 1. Maximum lot coverage: 10% of the lot area, with a maximum of 100 square feet (See Section 6.11)
 - 1. Setback (ft.): 5.0' to 15'
 - a. Minimum Front Setback (ft.): 5.0' to 20'
 - b. Minimum Rear Setback (ft.): 5'
 - c. Minimum Side Setback (Interior Side) (ft.): 5.0'
 - d. Minimum Side Street Setback (Interior Side) (ft.): 5.0' to 15'
 - e. Minimum Side Street Setback (ft.): 5.0' to 15'
- 2. Minimum Building Separation (ft.): 10'
- 3. Maximum Building Height (ft.): 35'

6.2 Planning Areas B1 and B2

- 1. Permitted Uses**
- A. Residential
 - 1. Single-Family Detached
 - 2. Detached private garages
 - B. Non-Residential
 - 1. Open space, public or private
 - 2. Private Recreational and Park Uses, clubhouses, country clubs, recreational facilities, including but not limited to swimming pools, sports courts, and jogging, equestrian riding, hiking and biking trails
 - 3. Public Parks, Playgrounds, and other recreational areas
 - 4. Utilities including but not limited to gas, electric, telecom. This includes structures or facilities commonly associated or required with the installation and operation of utilities.
 - 5. Water infrastructure including but not limited to detention/infiltration basins, pumps, and ponds, as well as structures typically associated with water infrastructure such as pump houses.

2. Uses By Special Review

- A. Solar collectors which are not part of the primary structure
- B. Public Facilities

B. Primary Structure

- 1. Minimum Lot Size: None
- 2. Setback (ft.): 5.0' to 15'
- a. Minimum Front Setback (ft.): 5.0' to 15'
- b. Minimum Front Setback to Garage Door Face (ft.): 5.0' to 20'
- c. Minimum Rear Setback (ft.): 20'
- d. Minimum Rear Alley Setback (ft.): 2'
- e. Minimum Side Setback (Interior Side) (ft.): 2.0'
- f. Minimum Side Street Setback (ft.): 5.0' to 15'
- 3. Minimum Building Separation (ft.): 10'
- 4. Maximum Building Height (ft.): 35'

C. Accessory Structure

- 1. Maximum lot coverage: 10% of the lot area, with a maximum of 100 square feet (See Section 6.11)
- 1. Setback (ft.): 5.0' to 15'
- a. Minimum Front Setback (ft.): 5.0' to 20'
- b. Minimum Rear Setback (ft.): 5'
- c. Minimum Rear Alley Setback (ft.): 2'
- d. Minimum Side Setback (Interior Side) (ft.): 2.0' to 5'
- e. Minimum Side Street Setback (ft.): 5.0' to 15'
- 2. Minimum Building Separation (ft.): 10'
- 3. Maximum Building Height (ft.): 35'

CHECKED BY: MB, SW, DJ, JR
DATE: 08/06/2022

SHEET TITLE:
PD ZONING REGULATIONS

SHEET
15 OF 20

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 30, 31 & 34, TOWNSHIP 6 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO



DAWSON TRAILS
PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

PD ZONING REGULATIONS

6.3 Planning Areas C-1 and C-2

1. Permitted Uses:

A. Residential:

- 1. Single Family Attached or Detached
- 2. Clustered Single Family Dwelling Units, including but not limited to Zero Lot Line Dwelling Units, Pico Dwelling Units
- 3. Detached private garages

B. Non-Residential:

- 1. Assisted Living, Memory Care, or other senior institutional uses
- 2. Nursing Home
- 3. Adult Day Care
- 4. Day Care Center Facility
- 5. Day Care in Home
- 6. Open Space, Public or Private
- 7. Public Parks, Playgrounds, and other non-commercial recreational areas
- 8. Private Recreational and park uses, clubhouse, country club, recreational facilities, including but not limited to clubhouse, swimming pools, sport courts and jogging/equestrian complex, and walking trails
- 9. Utilities, including but not limited to gas, electric, telecom. This includes structures or facilities commonly associated or required with the installation and operation of utilities.
- 10. Water infrastructure, including but not limited to detention/retention basins/ponds, lift stations, and piping, as well as structures typically associated with water infrastructure such as pump houses.

2. Uses By Special Review:

A. Non-Residential:

- 1. Offices
- 2. Gyms / Health Clubs
- 3. Clinics
- 4. Restaurants, without Drive-Through
- 5. Private Clubs
- 6. Retail
- 7. Personal Services
- 8. Commercial Services
- 9. Public Facilities
- 10. Clubs/Clavens
- 11. Places of Worship
- 12. Recreation, Outdoor
- 13. Solar Collectors which are not part of the primary structure

3. Maximum Building Height for All Uses (ft):

- A. Planning Area C-1: 45'
- B. Planning Area C-2: 55'

4. Residential Setbacks (unless otherwise approved by the Town at the time of SDP or Plat):

Note: Setbacks which are not a primary structure shall not be considered in determining setbacks which apply. See Section 6.2.

- 1. Minimum Lot Size: None
- 2. Setbacks (ft.):
 - a. Minimum Front Setback: 1.5 ft. or 15'
 - b. Minimum Front Setback to Garage Door Face: 1.5 ft. or 20'
 - c. Minimum Rear Setback: 0'
 - d. Minimum Rear Alley Setback: 0'
 - e. Minimum Side Setback (interior lot): 1.5 ft. or 5'
 - f. Minimum Side Street Setback: 1.5 ft. or 10'
- 3. Minimum Building Separation (ft.): 10'

B. Accessory Structure:

Note: The number and placement of accessory structures shall be approved by the Town at the time of SDP or Plat.

- 1. Setbacks (ft.):
 - a. Minimum Front Setback: 1.5 ft. or 20'
 - b. Minimum Rear Setback: 0'
 - c. Minimum Rear Alley Setback: 0'
 - d. Minimum Side Setback (interior lot): 1.5 ft. or 5'
 - e. Minimum Side Street Setback: 1.5 ft. or 10'
- 2. Minimum Building Separation (ft.): 10'

5. Non-Residential Setbacks: To be established at the time of Site Development Plan/Plat application, review, and approval.

6.4 Planning Area D

1. Permitted Uses:

A. Residential:

- 1. Single Family Detached
- 2. Single Family Attached (Townhome, Duplex, Triplex, Fourplex, Zero Lot Line Dwellings, Pico Dwellings, Motor Courts, Green Courts, Clustered Dwellings)
- 3. Multi-family (Apartment, Condominium, or other similar multi-family configurations)

4. Multi-family:

- 1. Clustered Single Family Dwelling Units
- 2. Condominium
- 3. Green Court
- 4. Motor Court
- 5. Pico Dwelling
- 6. Townhome
- 7. Zero Lot Line Dwelling
- 8. Clustered Single Family Dwelling Units on a single lot as a product for lease
- 9. Detached private garages

B. Non-Residential:

- 1. Adult Day Care Facility
- 2. Assisted Living / Memory Care
- 3. ATM / Kiosk
- 4. Bed and Breakfast
- 5. Clinic
- 6. College / University / Voucher
- 7. Day Care Center Facility
- 8. Drive-Through Facility
- 9. Educational Facility
- 10. Funeral Home
- 11. Gym / Health Club
- 12. Hotel / Motel
- 13. Hospital
- 14. Marriage Office
- 15. Office (including Flex Office)
- 16. Parking Facility (standalone or 1 structure)
- 17. Place of Worship
- 18. Private Club
- 19. Public Facilities
- 20. Reception, Indoor or Outdoor
- 21. Retail
- 22. Restaurant
- 23. Studio Classes
- 24. Utility, Public
- 25. Veterinary Clinic
- 26. Open Space, Public or Private
- 27. Public Parks, Playgrounds, and other non-commercial recreational areas
- 28. Private Recreational and park uses, clubhouse, country club, recreational facilities, including but not limited to swimming pools, sport courts, and jogging, riding, equestrian riding and tennis trails
- 29. Drive-in (including but not limited to gas, electric, telecom. This includes structures or facilities commonly associated or required with the installation and operation of utilities).
- 30. Water infrastructure, including but not limited to detention/retention basins/ponds, lift stations, and piping, as well as structures typically associated with water infrastructure such as pump houses

2. Uses By Special Review:

- A. Solar collectors which are not part of the primary structure
- B. Kennel / Doggy Daycare

3. Maximum Building Height for All Uses (ft):

45'

4. Residential Setbacks (unless otherwise approved by the Town at the time of SDP or Plat):

Note: Setbacks which are not a primary structure shall not be considered in determining setbacks which apply. See Section 6.2.

- A. Primary Structure:
 - 1. Minimum Lot Size: None
 - 2. Setbacks (ft.):
 - a. Minimum Front Setback: 1.5 ft. or 15'
 - b. Minimum Front Setback to Garage Door Face: 1.5 ft. or 20'
 - c. Minimum Rear Setback: 0'
 - d. Minimum Rear Alley Setback: 0'
 - e. Minimum Side Setback (interior lot): 1.5 ft. or 5'
 - f. Minimum Side Street Setback: 1.5 ft. or 10'
 - 3. Minimum Building Separation (ft.): 10'

B. Accessory Structure:

- 1. Setbacks (ft.):
 - a. Minimum Front Setback: 1.5 ft. or 20'
 - b. Minimum Rear Setback: 0'
 - c. Minimum Rear Alley Setback: 0'
 - d. Minimum Side Setback (interior lot): 1.5 ft. or 5'
 - e. Minimum Side Street Setback: 1.5 ft. or 10'
- 2. Minimum Building Separation (ft.): 10'

5. Non-Residential Setbacks: To be established at the time of Site Development Plan/Plat application, review, and approval.

6.5 Planning Areas E-1 and E-2

1. Permitted Uses:

A. Residential:

- 1. Single Family Detached (E-2 only)
- 2. Single Family Attached (Townhome, Duplex, Triplex, Fourplex, Zero Lot Line Dwellings, Pico Dwellings, Motor Courts, Green Courts, Clustered Dwellings) (E-2 only)
- 3. Multi-family (E-2 only)
- 4. Clustered Single Family Dwelling Units, including but not limited to Zero Lot Line Dwelling Units, Pico Dwelling Units, Motor Courts, and other Multi-Family Dwelling Units (E-2 only)
- 5. Clustered Single Family Dwelling Units on a single lot as a product for lease (E-2 only)
- 6. Detached private garages (E-2 only)

B. Non-Residential:

- 1. Assisted Living, Memory Care, or other similar institutional uses
- 2. ATM / Kiosk
- 3. Bed and Breakfast
- 4. Clinic
- 5. Day Care Center Facility
- 6. Drive-Through Facility
- 7. Hospital
- 8. Nursing Home
- 9. Office (including Flex Office)
- 10. Place of Worship
- 11. Private Club
- 12. Public Facilities
- 13. Retail
- 14. Restaurant
- 15. Service - Commercial
- 16. Reception, Professional
- 17. Services, Retail
- 18. Veterinary Clinic (to include 24/7 emergency care)
- 19. Open Space, Public or Private
- 20. Private Recreational and park uses, clubhouse, country club, recreational facilities, including but not limited to clubhouse, swimming pools, sport courts, and jogging, riding, hiking and biking trails
- 21. Public Parks, Playgrounds, and other non-commercial recreational areas
- 22. Utilities, including but not limited to gas, electric, telecom. This includes structures or facilities commonly associated or required with the installation and operation of utilities.
- 23. Water infrastructure, including but not limited to detention/retention basins/ponds, lift stations, and piping, as well as structures typically associated with water infrastructure such as pump houses

2. Uses By Special Review:

- A. Solar collectors which are not part of the primary structure
- B. Public Facilities

3. Maximum Building Height for all uses (ft):

- A. Planning Area E-1: 50'
- B. Planning Area E-2: 60'

4. Residential Setbacks (unless otherwise approved by the Town at the time of SDP or Plat):

Note: The number and placement of accessory structures shall be approved by the Town at the time of SDP or Plat.

- A. Primary Structure:
 - 1. Minimum Lot Size: None
 - 2. Setbacks (ft.):
 - a. Minimum Front Setback: 1.5 ft. or 15'
 - b. Minimum Front Setback to Garage Door Face: 1.5 ft. or 20'
 - c. Minimum Rear Setback: 0'
 - d. Minimum Rear Alley Setback: 0'
 - e. Minimum Side Setback (interior lot): 1.5 ft. or 5'
 - f. Minimum Side Street Setback: 1.5 ft. or 10'
 - 3. Minimum Building Separation (ft.): 10'

B. Accessory Structure:

- 1. Setbacks (ft.):
 - a. Minimum Front Setback: 0'
 - b. Minimum Rear Setback: 0'
 - c. Minimum Rear Alley Setback: 0'
 - d. Minimum Side Setback (interior lot): 1.5 ft. or 5'
 - e. Minimum Side Street Setback: 1.5 ft. or 10'
- 2. Minimum Building Separation (ft.): 10'

5. Non-Residential Setbacks: To be established at the time of Site Development Plan/Plat application, review, and approval.

6. Pedestrian Oriented Area (E-2)

- A. The following are the supplemental design standards for the areas and buildings within the FDP that are categorized as a Pedestrian Oriented Area, which includes a centrally located gathering place (such as "main street") and shall include the following:
 - 1. Include either a publicly accessible and accessible route (such as a bicycle path) or a publicly accessible "main street" (at least 10' block in length) with buildings fronting with entries / pedestrian access oriented onto the space or street and incorporating typical urban design elements such as on-street parking (parallel or head-in), street trees for shade, decorative sidewalk paving, lighted street furnishings, and other elements to help establish and define the public realm of the place/area.
 - 2. Encourage elements to support pedestrian connectivity may include accessible outdoor dining, pedestrian-scale light fixtures and/or bollards, structured bicycle parking / key locations, or similar improvements
 - 3. Development patterns to prioritize pedestrians by placing entrances of buildings providing landscaping along main routes, and allowing on-street parking to help encourage slower vehicular traffic. As far as is possible to be pedestrian oriented, the transportation network in this area should also provide safe crossings for pedestrians and cyclists and include mid-block crossings where necessary.
 - 4. Convenient pedestrian and bicycle access to all adjacent streets.
 - 5. Create pedestrian focal points with enhanced pedestrian shading (such as areas with comfortable seating and tables), benches, or coffee stops, views of landscaped green spaces, or other features that provide visual interest, and safe, non-utilitarian people watching. Where possible provide power and work to encourage people to work outdoors.
 - 6. Accessible parking spaces located, signed, and lighted with clear and convenient access to building entries.
 - 7. For multi-building office developments, pedestrian amenities that allow for use and enjoyment of outdoor spaces as a development focal point or connector among for people from other buildings. These can include a mix of pedestrian-scale lighting, tables, drinking fountains, benches, seating walls, shade trees, raised landscape planters, benches, clock towers, specimen trees, potting plants, information kiosks, interactive exhibits, or art features.
 - 8. Convenient pedestrian access to transit stops and nearby parking areas, if any.
 - 9. Where feasible, design steps to accommodate strollers.
 - 10. Bicycle parking in convenient and visible areas that do not interfere with pedestrian circulation.
 - 11. Interconnection of pedestrian areas with adjacent existing or planned open space.
 - 12. The potential for outdoor dining and/or other amenities to enliven plazas and open space areas.

CHECKED BY: DAWSON TRAILS

DATE
POP-01: 07/08/2021
POP-02: 12/03/2021
POP-03: 04/17/2022
POP-04: 05/27/2022
POP-05: 06/09/2022

DAWSON TRAILS PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
TWO PARCELS OF LAND BEING ALL OF SECTION 2 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 28, 32, 33 & 34, TOWNSHIP 4 SOUTH, RANGE 81 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

PLANNER, LANDSCAPE ARCHITECT
NORRIS DESIGN
Planning Landscape Architecture & Interiors

1100 S. W. 10th Ave.
Suite 100
Denver, CO 80202
303.733.5769

APPLICANT



WESTSIDE INVESTMENT PARTNERS
4100 S. MISSISSIPPI AVE
SUITE 500
DENVER, CO 80246
303.841.6650

ENGINEER & SURVEYOR

CORE CONSULTANTS
1474 S. BROADWAY
ENGLEWOOD, CO 80115
303.730.5769

DAWSON TRAILS

DAWSON TRAILS
PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

FD ZONING REGULATIONS

SECTION 7 | PUBLIC LAND AND OPEN SPACE

7.1 PL-1 District

- 1. Permitted Uses: Uses permitted by right in the PL-1 District are as follows:
 - A. Active and developed parks, recreation centers and related uses including, but not limited to, rest rooms, parking and drives, information kiosks and maintenance and storage buildings.
 - B. Facilities for cultural/art uses, community events and other similar uses.
 - C. All municipal and/or quasi-municipal facilities or utilities, and
 - D. Educational Facilities.
 - E. Facilities for acquisition, selection, disposal, storage of water, sewage, fire, and water.
 - F. Facilities for distribution or storage of electricity (above or below ground as needed).
- 2. Development Standards: Development standards for the PL-1 District are as follows:
 - A. Maximum Height: Fifty (50) feet.
 - B. Minimum Front Yard Setback: A minimum of fifteen (15) feet from the property line, twenty-five (25) feet if abutting an arterial street.
- 3. Use by Special Review: Uses permitted by special review in the PL-1 District are as follows:
 - A. Buildings, structures, or other permanent improvements privately owned and operated, which must be open to public use.
 - B. Special drive buildings and structures (C.R.S. Title 32), and
 - C. Any building or structure more than fifty (50) feet in height, but not to exceed seventy-five (75) feet in height.

7.2 PL-2 District

- 1. Permitted Uses:
 - A. Open space, and its accessory, trails and associated service facilities.
 - B. Off-street parking and drives.
 - C. Facilities for acquisition, collection, disposal, drainage, storage of water, sewage, or reused water.
 - D. Utility and communication distribution lines (under or above ground as needed).
 - E. Facilities for distribution or storage of electricity (above or below ground as needed).
 - F. Impassion facilities.
- 2. Development Standards:
 - 1. Maximum Height: Twenty-five (25) feet.
 - 2. Minimum Front Yard Setback: Twenty-five (25) feet.
- 3. Use by Special Review: Applications for use by special review shall be evaluated under Section 17.38.100 of the Code, provided Section 17.38.100 shall have no application. Uses permitted by special review in the PL-2 District are as follows:
 - 1. Any use allowed in the PL-1 District or otherwise determined by the Director which could be appropriate with additional review.

7.3 Private Open Space (OSP)

- A. Permitted Uses:
 - 1. Active and developed parks, community/recreation centers and related uses, including but not limited to, buildings/structures, restrooms, parking and drives, information kiosks, picnic structures, gazebos and similar amenity structures, and maintenance and storage buildings.
 - 2. Facilities for cultural/art uses, community events, and other similar uses.
 - 3. Public or Private Open Space, wildlife sanctuaries, trails, and associated service facilities.
 - 4. Off-street parking and drives.
 - 5. Facilities for acquisition, selection, disposal, drainage storage of water, sewage, or reused water.
 - 6. Utility and communication distribution lines (under or above ground as needed) (regional facilities).
 - 7. Additions/expansions of open space or PL-1 and PL-2 areas on the PD Plan.
 - 8. Open space corridors along edges and/or internal to the Planning Area.
 - 9. Fences, posted gates and other signage amenity areas.
 - 10. Enhanced portions of street corridors.
 - 11. Creeksways.
 - 12. Gathering places.
 - 13. Development/infrastructure/amenities.
 - 14. Facilities for distribution or storage of electricity (above or below ground as needed).
- B. Development Standards: Development standards for the OSP District are as follows:
 - 1. Maximum Height: Fifty (50) feet.
- C. Setbacks: (unless otherwise approved by the Town at the time of SDP or Plat)
 - 1. Minimum Front Setback: 15'
 - 2. Minimum Front Yard Setback to Arterial: 25' or setback of the adjacent Planning Area, whichever is greater.
 - 3. Other Setbacks are to be established at the time of Site Development Plan Plat application, review, and approval.

7.4 Reclassified Open Space

Private Open Space: Redevelopment Permit: A limited amount (maximum 20 acres) of land depicted as PL-1 and/or PL-2 in this PDP shall be permitted to be reclassified as Private Open Space (OSP). Redevelopment of any future OSP tracts will be coordinated with the Town, as appropriate, during the Site Development Plan Plat stage of the development review process as more detail is known to determine where these sites should be located. Any portion of the potential 20 acres that are not reclassified and plotted as OSP shall remain as PL-1 or PL-2 and shall be jurisdictional to the Town. Replacement of reclassified acreage is not required.

SECTION 8 | ARCHITECTURE

Prescriptive architectural standards have been approved and adopted with this Dawson Trails Planned Development Plan and Planned Development Zoning Regulations and are incorporated herein as Appendix 1.

SECTION 9 | SIGNAGE

Prescriptive signage standards have been approved and adopted with this Dawson Trails Planned Development Plan and Planned Development Zoning Regulations and are incorporated herein as Appendix 2.

SECTION 10 | SUBMISSION OF SITE DEVELOPMENT PLANS AND/OR PLATS

- 1. Following approval of the Dawson Trails PDP Amendment, the Property Owners shall submit a Site Development Plan for all or any portions of the PDP. An area is then ready for development.
- 2. No structural building permits will be issued until a Site Development Plan and Plat have been presented to and approved by the Town.

SECTION 11 | TRANSITIONAL LAND USE

- 1. After approval of the Dawson Trails PDP incorporated herein by reference, any portion or portions of the property described as the Dawson Trails PDP which has not been subjected to a Site Development Plan and development has not commenced, may be used for agricultural purposes until approval of a Site Development Plan for the area or areas in question. Agricultural land uses, for the purposes of this section, shall mean farming, ranching, pre-existing residential uses, gardening, and existing building and out buildings performing therein. It shall not be deemed to include commercial land yards, commercial parking or gas tanks, for farms or ranches.
- 2. Any activity permitted by the Section shall be considered to be a valid pre-existing non-conforming use within the area described in 11.1 above, until a Site Development Plan for such area or areas has been approved and development has commenced.
- 3. Areas of agricultural activities shall be covered to vehicular traffic and off-road recreation motor being operating agricultural vehicles and implements, emergency vehicles, vehicles engaged in utility and other maintenance work, and devices of the Master Developer, or the Town.

CHECKED BY: M.B. SW, D.J. JR.
DRAWN BY:

DATE
PDP-01.07/08/2021
PDP-02.12/03/2021
PDP-03.04/13/2022
PDP-04.05/27/2022
PDP-05.08/09/2022

SHEET TITLE:
PD ZONING REGULATIONS

SHEET
18 OF 20

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
TWO PARCELS OF LAND BEING ALL OF SECTION 28 AND PORTIONS OF SECTIONS 15, 11, 23, 37, 29, 33 & 34 TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO



PLANNING & ARCHITECTURE
1100 S. WASHINGTON ST.
DENVER, CO 80202
303.555.8800



APPLICANT
CORE
1100 S. WASHINGTON ST.
DENVER, CO 80202
303.555.8800

ENGINEER & SURVEYOR
CORE
1100 S. WASHINGTON ST.
DENVER, CO 80202
303.555.8800



DAWSON TRAILS
PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

ARCHITECTURAL DESIGN STANDARDS

General Information

The architectural design standards guide the composition of the architectural styles for the Dawson Trails PUD emphasizing the regional architecture of the Front Range. The diversity presents a unique opportunity to assemble the Dawson Trails neighborhood elements of a scenic Front Range setting. The venerable "Colorado architectural" convention for Dawson Trails is indicative of modern interpretations of rustic, ranch mountain, prairie agrarian, and western hill, arched styles and regional materials. These standards allow for and require variety, including historic architecture components with neighborhood elements to establish a cohesive neighborhood. The Character Areas in the PUD establish a planning framework around an historic architectural nature of Dawson Trails.

A wide range of land uses contemplated in the Dawson Trails development plan. Refer to the Dawson Ridge PUD for descriptions of the West, Central and East Character Areas.

Development types categorized in these standards provide the overall standards that specific criteria for various types of uses that will be incorporated into the PUD Planning Areas, while encompassing the overall intent of the Character Areas.

The architectural design standards shall include the following development types:

- Pedestrian Oriented
- Commercial / Retail / Office
- Industrial
- Multi-Family Residential
- Single-Family Residential (supplemental to existing Town standards)

Design Standards (Overall)

The following design standards aim to create visual interest and consistency by addressing a variety of building types and organizational styles. These standards also address specific design elements including massing, proportions, detailing, materials, and site design.

Building massing at development types listed above should consider the following:

- All sides of a building open to public view shall display a semi-levelness of quality and architectural interest.
- Variation in the building facade by vertical or horizontal articulation, window and entry variations, porches, pilasters or other landscaped pedestrian areas are encouraged. Strong vertical elements such as windows, pilasters, columns, stairs, and towers should be used to identify individual commercial spaces.
- Large volumes or planes of buildings should be broken up into smaller ones to reduce the visual scale of a building. The mass of a building should be varied in form or divided to emphasize the various interior building functions.
- Variations in roofline and building footprint shall be utilized to effectively break up massing and provide visual interest.
- Sheds shall be integrated throughout Dawson Trails via the use of overhangs and architectural screening elements.
- Building design shall incorporate textured surfaces, projections, recesses, shadow lines, color, window patterns, cantilevers, setbacks, changes in parapet height and other treatments to avoid monolithic façades and surfaces.
- The primary entrance of a building or store shall have a clearly defined, visible entrance with distinguishing features such as:
 - Atracodes
 - Architectural details integrated into the building structure to frame the entrance
 - Canopies or porticos
 - Enhanced pedestrian surfaces
 - Framed by outdoor pedestrian features or landscaped landscaping
 - Overhangs
 - Paved and formal or inform
 - Recessed covered porches over the door
 - Recessed projections
- For new buildings, at least two (2) of the elements listed below should repeat horizontally. Buildings with features greater than 100 feet in length that exceed the height to provide additional interest and to include the wall plane including three of the elements listed below:
 - Color change
 - Texture change
 - Material change
 - Architectural variety and interest through a change in plane such as cantilever, overhang, overhang or cantilevering
 - Wall plane projections or recesses
 - A variety of rooflines and parapet heights incorporating changes or elements
- Horizontal alignment of architectural elements such as windows, sills, cornices, banding and other conditions is encouraged.
- Storefronts are to be completed by the building materials. Storefronts may consist of an architectural treatment provided by a storefront brand as appropriate.
- Exterior building materials shall use high quality, durable materials including, but not limited to materials specified that they maintain the overall quality and style of the project. Preferred exterior building materials include, but are not limited to:
 - Architecture metal
 - Brick
 - Clear and tinted glass
 - Concrete roof
 - Masonry: natural color sand or water colored, or stained textured
 - Slate roofs
 - Split face, scored and/or architectural concrete masonry units (CMU)
 - Stone, natural or faux
 - Stucco/EPS
 - T-rip concrete panels, where determined appropriate by the DTACC
- Buildings that utilize CMU walls shall use naturally colored units. Painted CMU is not permitted.

- Buildings that utilize flat roof concepts will provide texture, incorporation of sufficient articulation and color patterning to add a variety of texture and visual interest.
- Murals and graphics, applied to exterior walls are permitted, subject to the Town of Castle Rock Sign Code.
- Roofing materials should be of a color and material consistent with the architectural character of the building and should convey a sense of permanence and quality.
- Screening of all roof top or pad mounted mechanical units is required.
- The style and placement of exterior accent lighting shall enhance the building's architectural elements such as entry features, pilasters, columns, and landscaping.
- Light to medium intensity colors with low reflectivity are preferred as the predominant building color. Brighter colors may be used for accents, trim or highlighting architectural features. The warm, subtle and low reflectivity colors are encouraged.
- Color can be used to reduce the scale of a building by highlighting various architectural elements.
- Integration of landscape elements, flat roof entries, terraces, and other similar treatments is encouraged.
- Buildings shall be situated to provide a visual and physical connection to the public realm/public.
- A sense of entry shall be created into the development site by using building placement, landscaping treatments, signage, and other appropriate elements.
- Commercial development within the PUD are encouraged to provide vehicular access to adjoining portions of development sites in order to provide connectivity between development sites.
- A commercial development site shall provide pedestrian access throughout the site by linking to adjacent sidewalks, pathways, and/or transit stops, when appropriate, unless a grade change or other site constraints are prohibitive.
- Buildings, which are not placed immediately adjacent to the sidewalk, shall promote visibility and pedestrian orientation (pedestrian) with screens, awnings, canopies, or other pedestrian areas.
- Integration of raised planters or potbeds is encouraged to define outdoor spaces.
- Use of site furnishings, such as benches, tables, chairs, and fabric umbrellas are encouraged.
- For mixed use and non-residential uses, multi-building development, pedestrian connections shall allow for use and access to a development's local point or centralized amenity for people from other buildings. These can include areas of pedestrian scaled lighting, tables or seating, benches, seating walls, shade trees, raised landscape planters, terraces, color towers, specimen trees, outdoor planters, information kiosks, historical markers, or art features.
- A variety of well-landscaped lighting fixtures, which reflect architectural style proposed, are encouraged. Landscape lighting fixtures and plants and footcandle are prohibited.
- Off-site lighting towers, and other service poles shall be screened or integrated into the building.
- Screening must be accomplished by a well-constructed of integrally colored CMU, architectural metal screening, stone, color towers, textured masonry concrete, brick or similar materials that are compatible to match the project structure.

Commercial / Retail / Office / Vertically Mixed Use Standards

The overall goal for this development type (categorized as Commercial / Retail / Office / Vertically Mixed Use) is to create an organized campus (if multiple buildings are contemplated) that incorporates a variety of retail, office, residential, hospitality, and other similar types of uses. The development type may incorporate a horizontal or vertical mix of uses. These areas tend to be vertically oriented commercial areas that include pedestrian accommodations serving core areas of the PUD. Combining a complementary mix of uses that are oriented to establish a cohesive environment meant to enhance both daytime and nighttime activities is desired. Including elements such as community gathering spaces, covered patios, generous window areas, and generous architecture that creates a front door presence within the overall neighborhood context further strengthens the type of use area.

Neighborhood mail and services areas and buildings can vary in size (storefront sign facing) and the surrounding context must be evaluated to ensure that also building fits into the specific area. Post-use and in-use mail areas and buildings should utilize similar design elements as the other areas of the specific area of context. These locations shall incorporate a similar level of site-specific building and pedestrian elements that contribute to the overall character of the Dawson Trails neighborhood.

Large format destination retail uses shall provide a presence that is the heart of the specific shopping area. Large scale tenants bring a natural presence to the various use areas in the PUD and provide unique energies amongst themselves. These areas within the Dawson Trails PUD should be designed to promote similar design features that are intended to enhance the overall experience.

Buildings that are associated with national franchise companies shall be allowed to retain the elements required to operate their national identity and brand. These buildings are encouraged to integrate the materials and design standards to complement the overall architectural character, when possible.

Fin Space and Industrial Standards

Intent: Dawson Trails Architectural Standards guide the organization of these commercial areas and maximize the functionality of the Fin Space and Industrial buildings while integrating the overall character of the neighborhood. The following is a summary of the supplemental design standards for these development within the PUD Fin Space and Industrial planning areas:

- Fin space architectural treatments to public street and highway exposures. Shielding and back of house functions from public streets. Focus shall be placed on creating key elements on facade, transitions in wall texture, color, height, plane, and overall impression of mass and void. Drivers shall avoid lanterns, tall walls with 100 feet or greater.
- Surfaces shall be predominantly concrete or masonry materials including the top concrete and other large format masonry materials, painted or textured CMU, stone, and terrazzo of the complementary materials. Metal panels, fabrications, and trim may be a component of the complementary materials when combined with concrete or masonry materials. Concrete floor should be polished, honed, GFS and other treated or polished products may be used as accents.
- Accents of primary and secondary colors may be imposed on a primary field of natural colors and textures. Colors, introduced as a form giving element for entry and feature components.
- Service and loading operations shall be constructed within an enclosed structure or screened area.
- Outdoor storage, toolboxes, motor vehicle storage, contractors' yards, and transfer stations shall be screened or located in the back of house location.
- Major exterior wash and recycling receptacles shall remain within service and storage areas and be painted to match the primary or secondary color used on the main building.
- Curb cut bollards shall be allowed for truck loading and storage areas. Truck loading and storage within close proximity may be limited to bollards to the street level and to the public right of way. These areas shall be screened from public streets and open space networks through landscape design and screening wall technology, determined at time of SPD.
- Outdoor storage:
 - Outdoor service and storage areas shall be screened with solid masonry walls or opaque decorative fences that complement the architectural character of the building from public streets, public spaces and 125' contour.
 - Where applicable, green screens with vegetation may be encouraged to screen utility and service areas. These areas shall be elevated into the architectural character of the building. Green screens are to be used in addition to the required screen wall, they are not a replacement for the required wall.

Multi-Family Residential Standards

Intent: The planning and design approach for Multi-Family Residential development aims to ensure a general level of consistency and quality of a simply multi-story building, in a location of multiple buildings. The overall design should promote the public realm and pedestrian connectivity through the site. Multi-family uses may be horizontally and/or vertically integrated into a mixed-use building or district where it is encouraged to achieve the full-broader of the building with commercial or other appropriate uses. The following architectural features shall enhance the design character of multi-family buildings and to complement the overall character of Dawson Trails.

- For multi-building office, manufacturing, pedestrian amenities that allow for use and enjoyment of outdoor areas like development focal points or enhanced views for people from other buildings. These can include areas of pedestrian scaled lighting, benches, drinking fountains, benches, seating walls, shade trees, raised landscape planters, terraces, color towers, specimen trees, garden planters, historical markers, or art features.
- Grounded pedestrian access to transit stops and existing parking areas, if any.
- Where feasible, design uses to accommodate bus stops.
- Bicycle parking (covered and visible areas that do not interfere with pedestrian circulation).
- Interconnection of pedestrian areas with adjacent existing or planned open space.
- The potential for outdoor dining and/or amenities to enhance pass and open space areas.

Building Design

The following is a summary of supplemental Design Standards for a multifamily residential building:

- Four-sided architecture shall be integral to the design of all sides of a building and display a similar level of quality and architectural interest.
- Entries shall be emphasized with additional detailing.
- Buildings should be designed with a variety of surfaces, textures, shapes, multiplaned roofs, materials, and wall articulation.
- The scale, details, and materials shall be compatible with surrounding residential neighborhoods.
- A variety of heights, colors, textures, and step backs are encouraged to avoid long unarticulated building facades.
- Windows in exterior walls in depth and section are encouraged. Use pop-outs, awnings, and balconies to break up massing.
- Maximize sunlight exposure, such that appearance shall be avoided.
- Minimize the bulk and appearance of structures through the use of rooflines consisting of multiple roof heights, gables, and slopes.
- Materials will include architectural stone, contemporary siding, architectural plaster, high performance windows and glass, and other similar elements.
- Murals and graphics applied to exterior walls are permitted, subject to the Town of Castle Rock Sign Code.
- Glass shall be architecturally integrated into the articulated facade and/or window.
- Building placement and orientation shall vary to design setbacks and visual relief.
- Screening of mechanical units is required, to the extent possible.
- Integration of landscape and hardscape design elements and materials, to be provided in order to create public space and key arrival areas.
- Pedestrian access shall be provided throughout the site by linking buildings in adjacent sidewalks and pathways, when appropriate, unless place controls or other site restrictions are prohibitive.
- Use of site furnishings such as benches, tables, chairs, and fabric umbrellas are encouraged.

Single-Family Residential Standards (supplemental to Town standards)

Intent: These supplemental standards are to be used in addition to the Castle Rock Design Guidelines for Design and Development in the Town of Castle Rock, specifically for corner lots and lots adjacent to open space. The Single-Family Residential development type can be composed of detached or attached rowing styles.

- Architectural features for corner lots or lots adjacent to open space shall address the architectural treatment of residential elevations as listed below:
 - 1) Side elevations on the street side of corner lots, or adjacent to open space or trailheads shall receive full architectural treatment, which includes substantially matching the character of the front of the house, except for materials, window sizes, and architectural details.
 - 2) Cornerhouses, duplexes, single family for rent homes and single-family attached shall require four-side architectural treatment.

Landscape and Irrigation Design Standards

Intent: Landscape areas will be designed in conformance with the TOOR Landscape and Irrigation Criteria Manual, as amended and the Dawson Trails Water Efficiency Plan. Landscape design shall consider the consistency of plant selection, design intent, its compatibility with the overall established landscape theme, and other site specific characteristics, as appropriate. Design shall utilize indigenous, historically adaptable, low maintenance, and hardy, turf, shrubs, and trees per the TOOR Landscape and Irrigation Criteria Manual.

Submital Requirements (Dawson Trails Architectural Control Committee)

Dawson Trails Architectural Control Committee (DTACC) Review and Approval. All drawings for proposed buildings, site improvements, and signage improvements must be reviewed and approved by the DTACC as a condition of acceptance of the Site Development Plan (SDP) by the Town of Castle Rock.

DATE:
_ _ _ _ _
_ _ _ _ _
_ _ _ _ _
_ _ _ _ _
_ _ _ _ _
_ _ _ _ _

SHEET TITLE:
ARCH DESIGN
STANDARDS

SHEET
19 OF 20

MSW
D.J. JAK
CHECKED BY:
DRAWN BY:

DAWSON TRAILS

PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS

(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)
TWO PARCELS OF LAND BEING ALL OF SECTION 21 AND PORTIONS OF SECTIONS 15, 21, 22, 27, 29, 32, 33 & 34, TOWNSHIP 8 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, TOWN OF CASTLE ROCK, COUNTY OF DOUGLAS, STATE OF COLORADO

SIGN DESIGN STANDARDS

SECTION 9 | SIGNAGE

This section addresses signage for the Dawson Trails PDP to guide the overall impression of a corporate master plan for the neighborhood.

Landmark signage and temporary signage will be guided by the Dawson Trails PDP. These signage locations are to be shown at time of Site Development Plan (SDP) and/or with the sign permit application. Landmark signage along the I-25 corridor is permitted in Planning Areas F-1, F-2, F-3, G-1 and G-2 as defined in the PD Plan. Temporary signage in the Dawson Trails PDP as defined by the PD Plan and along the Interstate 25 corridor is permitted, subject to the provisions of the Municipal Code. The following summarizes the criteria for signage.

9.1 Landmark Signage

- A. Landmark Sign is a non-erecting sign to be located within the F and G Planning Areas along the I-25 corridor directing attention to businesses, commodities, services, products, or properties within Dawson Trails.
- B. Landmark Signs are allowed in Planning Areas F-1, F-2, F-3, G-1 and G-2 and must be located within 300 feet of the Dawson Trails PD Plan property line along the Interstate 25 corridor and meet the signage requirements noted below.
- C. Landmark Signs shall be located a minimum of 1,500 feet from other Landmark Signs and shall not be a maximum of eight (8) Landmark Signs. On-site signage per the Dawson Trails Master Sign Plan as defined by the Town of Castle Rock Municipal Code, Title 10 at the date of the application shall not be included in this separation requirement. The distance shall be measured in a straight line from the corner points on each sign.
- D. Landmark Signs are permitted to be up to 70 sq. ft. per sign face with a maximum of two (2) sign faces. Only one (1) sign face shall be visible from any one direction viewed on Interstate 25 for a total of two (2) sign faces.
- E. The Landmark Sign prototype symbol represents a potential configuration for this sign type. The final design for the Landmark Sign will be determined at time of sign permit.



- F. Maximum sign height allowed for Landmark Signs is 70 feet from finished grade.
 - G. Landmark Signs shall be set back a minimum of 25 feet from the nearest street or Interstate right-of-way to the closest portion of the sign. The Landmark Signs shall be placed within landscape areas.
 - H. Pole signs and attached highway obelisk signs are prohibited.
 - I. Landmark Signs, external finishes include concrete, stone, architectural precast concrete, manufactured stone and wood products, aluminum, wood, metal, plastic, transparent panels and laminated sign panels, or other similar materials. Architectural lighting of the sign faces is allowed. This may include internal illumination such as translucent panels, backlit letters or similar techniques for lettering and logos on the sign face areas. All light sources, either internal or external, provided to illuminate Signs shall be placed or directed away from public streets, highways, sidewalks or adjacent premises. The final design for the Landmark Sign shall be approved by the Dawson Trails Architectural Control Committee, refer to the Architectural Standards.
 - J. A sign permit is required for Landmark Signs.
- #### 9.2 Temporary Signage and Banners
- A. Temporary signage and banners directing attention to businesses, commodities, services, products, real estate or properties within Dawson Trails are allowed in Planning Areas A, B, C, D, E, F and G.

CHECKED BY: M.B. SKV
DRAWN BY: D.J. JR.

Unofficial Copy

PLANNING AND CAPABILITY
CONSULTANTS
NORRIS DESIGN
Project | 1140 South Ash Street | Boulder

DATE: 01/27/2022
PROJECT: DAWSON TRAILS
SHEET: 26 OF 26

APPLICANT

WESTSIDE INVESTMENT PARTNERS
4100 E. MISSISSIPPI AVE
SUITE 500
DENVER, CO 80246
303.944.8800

ENGINEER & SURVEYOR
CORE
CORE CONSULTANTS
3472 S. BROADWAY
ENGLEWOOD, CO 80113
303.735.5803

DAWSON TRAILS

DAWSON TRAILS
PLANNED DEVELOPMENT PLAN AND ZONING REGULATIONS
(AN AMENDMENT TO THE DAWSON RIDGE PRELIMINARY P.U.D. SITE PLAN AND A PORTION OF THE WESTFIELD TRADE CENTER PRELIMINARY P.U.D. SITE PLAN)

DATE
PDP-01: 07/08/2021
PDP-02: 12/02/2021
PDP-03: 04/13/2022
PDP-04: 05/27/2022
EDR-09: 08/09/2022

SHEET TITLE
SIGN DESIGN STANDARDS

SHEET
20 OF 20